


SCIENTIFIC AMERICAN




C. H. K. SMITH
1907

MOTOR BOAT NUMBER

MUNN AND COMPANY, PUBLISHERS
NEW YORK

PRICE TEN CENTS

SPEEDWAY Gasoline Marine Engine



3 TO 200 H. P. IN STOCK

The Best That Can Be Built

**CAN BE SEEN IN COURSE OF
CONSTRUCTION & OPERATION
AT OUR WORKS AT ALL TIMES**

We also design and build Steam and Sail Yachts, High Speed and Cruising Motor Boats, Naphtha Launches, and vessels for commercial service, steel and wood construction. Marine Steam Engines and Boilers.

GAS ENGINE & POWER CO. and CHAS. L. SEABURY & CO.

CONSOLIDATED

Morris Heights, New York City

Send 10 cent stamp for illustrated catalogue.


Member of the National Association of Engine and Boat Manufacturers.

THE LAMBERT

THE FRICTION DRIVE CAR

5
New Models

No Fixed
Speed
Any Speed
Desired




Model "G." Price \$2500

Examine
Them
Carefully

Chicago
Automobile
Show,
In the Armory,
Feb. 2 to 9

35-40 H. P. 4-cylinder Rutenberg Motor. Seven passenger, side entrance Tonneau. Wheel base 106 inches. Lambert Patented Friction Drive Transmission, etc. Model "G" is the Greatest Value for the Price ever offered to the automobile buying public. Write for detailed description.


Our New
1907
Art Catalog
Now
Ready



Model "H." Price \$2000

25-40 H. P. 4-cylinder Rutenberg Motor. Our "Shaft Drive" Car, Lambert Patented Friction Drive Transmission, etc. Write for detailed description.


Dealer Agents Wanted in territory not already closed. WRITE US NOW.



LAMBERT CHASSIS

THE BUCKEYE MANUFACTURING CO., Anderson, Indiana, U. S. A.

Member American Motor Car Manufacturers Association, New York.



Cadillac—Model H

Where Dependability and Economy Meet

These are the great foundation stones of Cadillac success—unfailing reliability under all sorts of service; cost of maintenance so low as to be almost incredible. In the magnificent line of Cadillacs for 1907 these qualities are more manifest than ever before. The Model H has proven itself the four-cylinder triumph of the year.

From motor to muffler this machine is an example of simple construction, of finish really super-fine, of accuracy not surpassed in any other mechanical creation—all of which are more pronounced because of the wonderful factory facilities and system that stand behind the

CADILLAC

The superiorities of Model H are so numerous that to select features deserving special emphasis is difficult. Those of prime importance are remarkable ease of control and smoothness of riding, whatever the road conditions. The car is practically noiseless in operation; perfect balance of action removes all vibration. The enormous power is so positively applied that whether for speeding or hill climbing Model H is there with energy to spare. The body possesses lines of beauty and grace and reflects style unmistakable.


Your dealer will gladly give you a demonstration.

Model H—30 h. p. Four-cylinder Touring Car; \$2,500. (Described in Catalog H-N)
Model G—20 h. p. Four-cylinder Touring Car; \$2,000. (Described in Catalog G-F)
Model M—10 h. p. Four-cylinder car; \$950. (Described in Catalog M-N)
Model K—10 h. p. Runabout; \$800. (Described in Catalog K-L)

All prices F. O. B. Detroit—Lamps not included.

Send for special Catalog of car in which you are interested, as above designated.

CADILLAC MOTOR CAR CO., Detroit, Mich.
Member Asso. Licensed Auto. Mfrs.



Locomobile

The Most Reliable Car Built in America

All models
equal throughout
in quality

\$2800

Type E, \$2800
Three other models
\$3800 to \$5800

MODELS FOR 1907

Type E, 20 H. P. Standard.

Price, \$2,800, fully equipped with five lamps, tools, etc.; top extra. Illustrated above. 96-inch wheel base; 32 x 4 tires, all wheels; three speeds and reverse; Hess-Bright ball bearings, wheels and gear box; alloy steel gears; seats five adults.

Type H, 35 H. P. Standard.

Price, \$4,500, with full equipment of five lamps, tools and other accessories. 120-inch wheel base; 34 x 4 tires front; 34 x 4 1/2 tires rear; four speed selective transmission; alloy steel gears. Seats seven, all facing forward. A touring car de Luxe.

Type E, 20 H. P. Limousine.

Price, \$3,800, complete with five lamps. Oil lamps are square and placed on body. Seats six adults. Electric annunciator; electric dome light; toilet set; upholstery and appointments very luxurious, 106-inch wheel base.

Type H, 35 H. P. Limousine.

Price, \$5,800, complete with five lamps. Oil lamps are square and placed on body. Seats seven adults. Electric annunciator; electric dome light; toilet set; upholstery and appointments complete and luxurious. 120-inch wheel base.

The Locomobile Company
Bridgeport, Conn.

NEW YORK: Broadway and 76th Street.
PHILADELPHIA: 249 N. Broad Street.

BOSTON: 15 Berkeley Street.
CHICAGO: 1354 Michigan Avenue.


SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1907, by Munn & Co.]

Vol. XCVI.—No. 8
ESTABLISHED 1845. ★

NEW YORK, FEBRUARY 23, 1907.

★ 10 CENTS A COPY
\$3.00 A YEAR.




"LA MASCOTTE III."

"DIXIE."

Two of the Popular Modern Types of American Power Cruisers.

"La Mascotte III." is 84 feet in length over all; "Dixie" is 93 feet over all. These yachts have comfortable accommodations for passengers and crew, and have a wide cruising radius at fair speed.



The Ocean-Going Cruiser "Hawk," Built for Service in Caribbean Waters.

The "Hawk" was designed for long journeys about Cuba, the Isle of Pines, and Porto Rico, and for this purpose carries a maximum fuel supply of 2000 gallons of gasoline.

LATEST TYPES OF CRUISING POWER BOATS.—[See page 167.]

SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO. - - - Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

TERMS TO SUBSCRIBERS

One copy, one year, for the United States, Canada, or Mexico,\$3.00
 One copy, one year, to any foreign country, postage prepaid, \$3 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS

Scientific American (Established 1845)\$3.00 a year
 Scientific American Supplement (Established 1876) 5.00
 American Homes and Gardens 3.00
 Scientific American Export Edition (Established 1878) 3.00
 The combined subscription rates and rates to foreign countries will be furnished upon application.
 Remit by postal or express money order, or by bank draft or check.
 MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, FEBRUARY 23, 1907.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

THE "LARCHMONT" DISASTER.

The awful disaster which occurred on the evening of Lincoln's birthday off Block Island, and resulted in the sinking of the steamer "Larchmont" with a loss estimated at not less than 150 souls, is not only one of the most tragic events in the history of navigation of Long Island Sound, but there are disquieting elements connected with the event, which may well shake the faith of the public in the safety of the older boats, and in the skill and heroism of the navigation and seamanship in these famous and much-traveled waters. The conditions under which the collision occurred, so far as they can be gathered from published reports, are altogether bewildering. Here, in comparatively sheltered waters, on a clear and starlit night, in spite of the fact that the captains of the two vessels, one a three-masted schooner, the other a side-wheel steamer, distinctly saw each other's lights when they were fully half a mile away—in spite of all this and the further fact that they had deep water and ample sea room, we find these two vessels so handled as to crash one into the other at full speed, and with all the appearance of deliberation. It is useless to speculate on the facts as here presented, and for an explanation we must be content to await the searching inquiry which must follow. It is certain, however, that the sailing vessel had the full right of way, and that it was the duty of the steamer to avoid her. The fact that the schooner rammed the steamer bow on would seem to indicate that the captain of the latter had made the too-frequent mistake of supposing that the superior speed of his ship would enable him to cross the bows of the sailing vessel.

Another feature which is disquieting, and certainly does not ring true with the best traditions of the sea, is the fact that so large a number of the officers and crew were saved, or at least got away in boats, while so many of the passengers, among them several women, went down on the vessel. In the presence of such a fact one's mind harks back to that fine old legend of the sea to the effect that the captain is always the last to leave his ship. On this point also will the public look for further and very definite information; and we can only hope that facts may be developed at the investigation which will give this phase of the question a more wholesome complexion than it wears at present. That the "Larchmont" should have foundered so rapidly after receiving the blow of the schooner proves once more how utterly unfit are some of these older steamers on the Sound and in the sheltered waters of our harbors and rivers for the safe carrying of passengers. It is certain either that there was no safety bulkhead construction in the hull of the "Larchmont," or that, if it existed, it was of a flimsy and practically worthless character. According to one account, the ship had transverse bulkheads built up of six-inch timber, but this, unless it was very heavily braced, would be altogether inadequate to withstand the water pressure, especially when the water in the hold was surging, as it would be, against the bulkheads with a momentum due to the rolling and pitching of the vessel. As a matter of fact, this question of non- or inefficiently-bulkheaded passenger vessels, whether for harbor or Sound travel, is one of wide significance, and fraught with untold danger to the passenger. If the traveling public knew how many of these vessels would prove, in case of collision, to be mere death traps, the shrinkage of travel upon them would be such as to compel the substitution of more modern and safer ships. If it shall result in stringent legislation to debar all but thoroughly well-bulkheaded vessels from the passenger-carrying trade, the loss of life on the "Larchmont" will not have been altogether in vain.

TREND OF MOTOR-BOAT DEVELOPMENT.

One of the most prominent facts connected with the present development of the motor boat is the waning interest in craft of the lightly-constructed and over-powered racing type, and the growing popularity of the more stanchly-built, roomy, seagoing boat of moderate power, with ability to make an extended cruise without replenishing the fuel supply. The decline in popularity of the type which is built exclusively for racing has been gradual, but decided, and particularly so during the past two years. It is unquestionable that there is a fascination about mere speed, which appeals strongly to the public mind; and in the earlier development of any of the high-speed devices which have figured prominently in the great field of sport and pastime, the accomplishment of high speed has appealed to the imagination and stimulated the efforts of designers and builders, largely to the exclusion of other and more valuable considerations. In the later years of the past, and the opening of the present, century this has been particularly true, as witness the construction and development of the yacht, the bicycle, and the automobile. But because of the great cost and limited usefulness of all mechanical creations which sacrifice every other consideration to that of high speed, the cost is so exceedingly high as to place them within reach only of men of considerable wealth and leisure. History shows us that when the possibilities of speed have been pretty well exhausted there is an inevitable reaction in favor of more moderate speeds and more durable and reasonable construction. The "speed mania," however, has always left behind it a valuable legacy in the way of useful knowledge as to the strength of materials, and as to just how far bulk and weight may be cut down without any sacrifice of absolutely essential strength.

The motor-boat industry may be said to have now passed from the first to the second and more important stage of its development, and although the high-speed races of the last year or two have shown that there still exists some enthusiasm in this form of sport, the number of extreme racing craft that is being built on the orders of private yachtsmen is relatively diminishing, while the orders for stancher vessels, of the fast and moderate-speed cruiser type, are increasing at a really remarkable rate. To-day not many of the extreme racing craft are built on private orders, the predisposing motive for such of these craft as are constructed being found in the desire of the makers and builders of engines and hulls to demonstrate the high quality of their product, by exhibiting it under the severe conditions necessary in the construction of a successful racing machine.

The popular type of motor-boat to-day is a moderate-powered cruiser, provided with a roomy cockpit and a substantial cabin with ample headroom, one or more staterooms, abundant lockers, a toilet, galley, and pantry, and all the accessories necessary for comfort on a cruise of several days' duration. Of course, the meeting of these requirements has necessitated an increase in size, and particularly in boats intended for deep-sea cruising, or for an extended trip in the more sheltered waters of Long Island Sound, or the extensive harbors of the South. Hence, the dimensions of a modern cruiser will be represented by a vessel from 30 to 60 feet in length, and furnished with engines of from 20 to 100 horse-power.

Perhaps the most potent influence in the development of this type of craft has been the institution of the long-distance races, which have grown in frequency and popularity during the past few years. Confined at first to courses laid through the Sound from New York to some point on the Massachusetts coast, these races have developed fast cruising boats, of such power and excellent sea-going qualities, that in the present year two important races are being run over ocean courses; one from Miami, Fla., to Nassau, a distance of 190 miles, and the other from New York to Bermuda. The latter is, of course, the more formidable undertaking, and the restrictions which have been laid down regarding the size and construction of the contesting boats have been so well drawn that there is no reason why all the contestants should not make the 700-mile trip in safety.

Although the flimsy racing craft has waned in popularity relatively to the moderate-powered cruiser, there will always be a demand for high-speed yachts, capable of averaging about 18 knots an hour, for what is coming to be known as "ferry" service, or the work of carrying business men to and fro between New York or other maritime cities and their distant summer residences. These craft run in length from 75 to 100 feet or over, and carry engines capable of giving them a sustained speed in sheltered waters of from 16 to 20 knots an hour. They are provided with ample deck space and spacious cabin accommodation, while frequently they will have a dining room and galley sufficient to enable the owner and guests to dine aboard if they should so wish.

The question has been asked as to whether the gasoline engine will be applied to ocean-going yachts of a size capable of making the transatlantic passage.

One of our leading naval architects has recently expressed the opinion that in the present condition of the art this is not practicable, because of the prohibitive cost of the fuel. Moreover, it is undeniable that many prospective yacht owners would be deterred by considerations of the supposed risk attaching to the storage of large supplies of gasoline; although, as a matter of fact, by the use of proper precaution, the danger may be so greatly reduced as to be practically negligible. It is likely that under the stimulus afforded by the introduction of free alcohol, the designers of internal-combustion engines will succeed in designing motors so well suited to the use of this fuel, that it will ultimately prove to be more economical than gasoline; and there is not the slightest doubt but that with the more extended use of alcohol the price must ultimately come down to a point which will render it as economical as gasoline. When that point is reached, the added advantages of safety and absence of odor, etc., will render it such an ideal fuel that we may look for its extended use in the larger sizes of yachts, even in those capable of making the transatlantic passage.

Furthermore, the internal-combustion engine has several collateral advantages which must commend it strongly to the prospective yacht owner. By saving the expensive installation of boilers for a steam plant, the first cost of a gasoline or alcohol plant will be considerably less; and there will be a decided saving in the important matter of space. Also, for the same bunker or tank capacity, the steaming radius, or sailing radius, will be much larger than where steam power is used; while the comfort of the owner will be further assured by the absence of smoke and ashes, and the inevitable dust and disfigurement attendant upon coaling. Already, the way for the appearance of the large ocean-going gas-driven yacht has been prepared by the successful operation of the large auxiliary schooners, in some of which gasoline engines of considerable power have been installed and successfully operated.

GYROSCOPIC ACTION OF MARINE TURBINES.

We are most of us familiar with that ingenious device for preventing, or rather modifying, the rolling of ships, which consists of a heavy gyroscope, placed with its axis of rotation transverse to the longitudinal axis of the ship. The machine works on the principle that, to change the plane of rotation of a swiftly-rotating body by tilting the axis, requires an amount of effort which is determined by the weight and rotative speed of that body. The anti-rolling gyroscope, rotating in a plane at right angles to the direction in which movements of rolling of the ship take place, tends to resist those motions and modify their extent.

Simultaneously with the appearance of this device, and possibly suggested by it, there has arisen a discussion of the action upon turbine-driven vessels of the heavy and swiftly-rotating rotors of the steam turbine; for these, in addition to their proper work of driving the ship, undoubtedly act, because of their weight and high speed of rotation, with a powerful gyroscopic effect upon the pitching motion of the vessel. In this case, however, the gyroscopic action is felt in the direction of the longitudinal axis of the ship, and not, as in the case of the anti-rolling device, transversely thereto. Moreover, just as the anti-rolling gyroscope tends to modify rolling, so the gyroscopic effect of the heavy rotors of the steam turbines must tend to modify pitching, or vertical movement in a plane passing through the keel. Whatever modifying effect the device above referred to may have upon the rolling of a vessel, it is certain that the gyroscopic action of the turbine rotors can have none, or practically no effect upon the pitching. But since the gyroscopic resistance of the heavy rotors to a change of position of their plane of rotation is present and is considerable in quantity, it follows that they must exert a stress of no little amount upon the framing of the vessel itself. The proportion which these stresses will bear to the normal stresses for which the hull was designed will be largest in the case where turbines of great weight and high speed of rotation are carried in a long, shallow, and lightly-constructed hull, as in the case of a high-speed turbine torpedo-boat destroyer. These stresses would act very materially to increase the bending stresses which occur when a torpedo boat is being driven rapidly across the seas. In such a vessel they would become so large as to call for an increase in the scantling of the vessel, beyond that which would be necessary were reciprocating instead of turbine engines installed.

In the course of a valuable analysis of this action of a steam turbine, Mr. A. H. Gibson, of the Institute of Civil Engineers of Great Britain, some months ago called attention to the fact that the "Cobra," one of two high-powered turbine destroyers, built several years ago for the British government, and capable of steaming 36 knots an hour, broke her back and went down during a gale in the North Sea. This destroyer was built of the same scantlings as other destroyers in the British and Japanese navies, the difference be-

tween them and her being that they were driven by reciprocating engines and the "Cobra" by steam turbines of nearly double the power. Although no satisfactory reason was assigned for the disaster, Mr. Gibson believes that the additional stresses caused by the gyroscopic action of the rotors were mainly responsible for the disaster. Assuming that the two high-pressure turbines weighed 8 tons each and the two low-pressure 14 tons each, and that the speed of revolution was about 1,100 per minute, he finds that under certain conditions a couple might be called into play of 48 foot-tons, which would have to be resisted by the framing and shell of the vessel.

LONG-DISTANCE MOTOR-BOAT RACES FOR 1907.

There are at present but two important power-boat races scheduled for the coming season. Both of these are for cruising craft, and it is noteworthy that no contestant is eligible to entry in both races. These are known as the Marblehead and Bermuda contests.

The Marblehead race is the third annual race of a series which has been pulled off between New York and Marblehead, Mass., while that to Bermuda is an entirely new venture in the long-distance cruiser field. Both these races are laudatory, since such contests tend to develop a seaworthy, convenient, comfortable, and sensible type of cruising craft. If the results this year do not prove this to be true, indications are certainly misleading.

The first long-distance race for cruising power boats was conceived by Mr. Thomas Fleming Day, of "The Rudder," who offered a \$250 trophy, to be known as "The Rudder Cup," to the Knickerbocker Yacht Club of College Point, with absolutely no restrictions as to conditions except that it was to be raced for by cruising power boats. This was late in 1904. The Knickerbocker Yacht Club accepted this cup, but, as there had been no previous contests of a similar nature, the club fully realized the amount of strenuous work such an enterprise would entail.

After several meetings the regatta committee presented to Mr. Day, for his approval, a draft of the conditions for the first race in 1905. These rules provided for a race for *bona fide* cruising power boats, not exceeding 40 feet length over all, and for the exclusion of any craft not having living and cruising accommodations for a crew of at least four persons. Paid navigators were also barred. American Power Boat Association rules were to govern. As a result there were sixteen entries, with twelve starters, as follows:

Boat.	Owner.	Engine.
"Blink".....	C. W. Estabrook.....	Buffalo.
"Aquila".....	A. H. Chase.....	Chase.
"May".....	A. A. Low.....	Fulton.
"High Ball".....	Richard Hutchison..	Essex.
"Woodpile".....	A. L. Lincoln.....	Barber.
"Glissando".....	F. L. Andrews.....	Standard.
"Yeddo".....	S. M. Smith.....	Twentieth Century.
"Em Bee".....	Louis Neumann.....	Buffalo.
"General Bumps"....	P. D. Irwin.....	Giant.
"Igniter".....	C. A. Mezger.....	Buffalo.
"Aranca".....	Arnold Schlaet.....	Standard.
"Talisman".....	William Saville.....	Murray & Tregartha

Of these, all but six, viz., "Yeddo," "General Bumps," "Aranca," "Glissando," "Em Bee," and "Talisman," were new boats, built to conform to the conditions of the race.

The weather was the worst of the season, and after a hard trip across Nantucket Shoals, but five were able to finish and in the following order: "Talisman," "Blink," "Aquila," "Glissando," "Woodpile."

As "Talisman" was entitled to an allowance of nearly seventeen hours, there was no question of her winning the cup.

"Glissando" received second prize, and the other three handsome souvenirs.

In this race, as in that of the year following, the Eastern Yacht Club, of Marblehead, rendered valuable assistance, not only to the Regatta Committee of the Knickerbocker, but to the contestants themselves, the other two yacht clubs, the Boston and Corinthian, each vying with the Eastern as to which could do the most in that line.

Before the close of the year 1905, the Knickerbocker Yacht Club decided on a race for 1906. This was to be run in the opposite direction, i. e., from Marblehead to College Point. As a result, four prizes were offered, with fourteen entries and the following twelve starters:

Boat.	Owner.	Engine.
"Davy Jones".....	Richard Hutchison.....	Jager.
"Unome".....	Alfred L. Lincoln.....	Barber.
"May".....	A. A. Low.....	N. Y. Kerosene Oil.
"Yo-Ho".....	R. R. Curry & Sons.....	Ideal.
"Whew".....	F. C. Webb.....	Murray & Tregartha
"Aranca".....	Arnold Schlaet.....	Standard.
"Sis".....	Eben Stevens.....	Craig.
"Susie".....	J. B. Schmelzel.....	Fulton.
"Gertrude".....	J. J. Tobin.....	Murray & Tregartha
"Shawna".....	George C. Sutton.....	Lamb.
"Alice J".....	Sidney Williams.....	Hasbrouck.
"Sarapa".....	Swasey, Raymond & Page.....	Buffalo.

In 1905 "Talisman" took nearly 54 hours and 25 minutes to cover the course.

"Unome" finished first in 1906 in 33 hours, 45 minutes, and 40 seconds, with "Whew" second, "May" third, and "Sis" fourth. The last boat of nine to finish, "Susie," completed the 280 nautical miles in 39 hours, 5 minutes, and 29 seconds elapsed time.

Time allowance was figured on a modification of the 1905 American Power Boat Association rules, using 60 per cent of the table, with arrivals corrected so that the winners in their order were as follows: "Sis," "May," "Susie," and "Davy Jones."

The owner of "Sis," Mr. Eben Stevens, promptly offered a cup for a race in 1907. The Knickerbocker Yacht Club could not see its way clear to undertake the management of another race. Consequently, the New Rochelle Yacht Club will this year have supervision over the third Marblehead race.

Very slight modifications in the rules governing the 1906 contest have been made, the two principal ones being to limit the minimum length to 30 feet over all, instead of on the waterline, and the use of 50 per cent of the table of time allowance of the American Power Boat Association rules, rather than 60 per cent. The race this year will be from New Rochelle to Marblehead and will probably start on July 4.

The other race is from Gravesend Bay, off the Brooklyn Yacht Club, to Bermuda, a distance of about 700 statute miles. The minimum length of boats eligible for this race is placed at 39 feet, and the maximum at 60 feet.

This race is for a valuable trophy offered by Mr. James Gordon Bennett, the well-known yachtsman. It will be run under the joint auspices of the Brooklyn and Royal Bermuda Yacht Clubs. Careful conditions have been formulated, to avoid probability of disaster to any competing craft, each one being compelled to carry 6 square feet of sail for every foot of over-all length, and one and one-half times the quantity of fuel necessary to cover the distance under favorable weather conditions; while several other important salutary regulations are embodied in the requirements for eligibility for entrance. The conditions under which entries are to be made were published in the SCIENTIFIC AMERICAN of December 22, 1906.

This race is scheduled to start from the club house of the Motor Boat Club of America on June 1, and with good weather the run should not consume more than two and a half or three days.

It is reported that several boats are already under construction for each race, and it is likewise probable that boats already built, and eligible for the Marblehead race, will compete, while slight modifications, consisting in the main of the addition of auxiliary sail equipment, will allow several well-known boats to enter in the Bermuda trial, which will test the best points of such craft, such as their seaworthiness and endurance.

POWER BOAT NOTES.

You cannot "throttle" a four-stroke cycle engine to slow speed, unless the exhaust valve springs are sufficiently strong to prevent ingress of the spent gases through the exhaust valves, when there is a partial vacuum in the cylinder formed by the descent of the piston during its induction or drawing-in stroke. Weak exhaust-valve springs are sometimes encountered on marine gasoline engines.

There is an island near Marblehead, Mass., which is often mentioned in print. It is sometimes called Thatcher's and often Thatcher. It could not be Thatcher's, for in all geographical names now the apostrophe is omitted. What used to be called Riker's Island is now Rikers Island, while Fisher's Island has become Fishers Island. In the particular case mentioned, the latter is and has always been correct. It is Thatcher Island.

Conditions may necessitate installing propellers with excessive pitch, but such an installation should be avoided if possible. It must be remembered that the flywheel of the engine must be kept out of the water in the boat's "run," or space below the floor. This is sometimes accomplished by using a copper or galvanized pan under the lower part of the flywheel. Two-cycle engines give more trouble usually than four-cycle, when thus installed, and two-port engines more than three-port, if supplied with float-feed carbureters, the usual tendency being to get too rich a mixture in the after cylinder and too poor a mixture in the forward cylinder. Too much lubricating oil is quite likely to interfere with the ignition in the after cylinder if the engine is of the four-cycle type.

If you are in a power or sail-driven boat, and some other craft, steam or gasoline driven, willfully violates well-known "rules of the road," you should, at your earliest convenience, report the occurrence to the nearest United States inspector of steamboats, giving a full account of the occurrence, with names and addresses of eye-witnesses. A few cases of this sort would give many of our licensed masters and pilots what they richly deserve—suspension of their licenses—even although they are often goaded to desperation, as no doubt many of them claim, owing to the wanton

disregard of the usual rules by many of our power-boatmen. Moral: Learn the "rules of the road" yourself, and do not take any chances, giving the other party plenty of leeway.

A sailing yacht shows the same lights as any sailing craft, the regulation red and green side lights, when under sail, and the white riding light when at anchor. A light is sometimes suspended from the end of the main, or spanker boom, to reduce liability of fouling, and while of great utility, and in a measure considered necessary, is not demanded by federal law or regulation. Small sailing craft are allowed to show a combination red and green light displayed in front of the mast, in place of the usual separate side lights. Small power craft, when using combination lights, should have a white light showing between the red and green. When showing separate side lights they should display a white masthead light. Towboats or any power craft when towing another craft alongside, should show two white masthead lights, one above the other, and when towing astern there should be three of these lights vertically arranged. The regulations governing lights on all craft are the same, no matter whether used for pleasure or business purposes, and are in force from sunset to sunrise.

Galvanized sheet-iron gasoline tanks are unsafe, and their use should be prohibited in all boats. Copper is very much better than any other material for fuel receptacles, although high-grade house boilers, galvanized after they are made up, on account of their cheapness, are permissible. The electric-welded, pressed-steel tank, however, is preferable to the riveted style. A precaution to be observed in the use of galvanized-iron or steel tanks is to see that salt water does not collect on them, or that they are not partially submerged in the boat. More important it is that no oak, or any wood carrying tannic acid, comes in contact with galvanized-iron tanks, else their life, owing to corrosive or galvanic action, is materially shortened. Galvanized-iron "swash" plates are preferable to those made of copper, owing to their greater rigidity, and such plates should be used in copper tanks. Soft, or hot-rolled, copper makes safer tanks than cold-rolled, and even this should be "tinned" on the inside, to insure the solder holding. All copper tanks should be protected against any possibility of fracture or puncture, by means of suitable bulkheads.

Rarely does a power-boat owner aspire to own the second craft with the propeller unprotected. Speed maniacs have set the custom. Floating debris, rocks, shallows, etc., make bad work with the unprotected propeller. It has been abundantly proven that high speed, with its allurements, is not all that is claimed or desired, that a comfortable, safe, good sea boat is a much more merchantable article and one less often offered for sale than so-called semi-speed or racing craft. It is possible so to design power boats that a good, satisfactory type with sufficient speed for comfort, may be produced rather than "freaks." Boats of abnormally high speed are decidedly dangerous playthings, not only for their own occupants, but those of other craft, who have equally as good rights to navigate crowded harbors and other constricted bodies of water. Power-boat racing, except for sensible cruising craft, died naturally something over a year ago. There is but one really good power-boat racer, and that is the very fastest one afloat. When such a craft is once beaten, her value is considerably decreased. In designing a boat to get the very highest speed possible, it is usually necessary to have the propeller project below the keel.

A jump-spark coil may be put out of commission easier by too high voltage than from any other cause. Adjusting the trembler, or vibrator, until there is very little play between the core and the small button or armature, is quite likely, especially with cheap coils, to fuse or burn up the metal contacts, between which a small spark shows when the primary, or low-tension, circuit is closed at the timer or distributor. Some coils are wound for but six volts, because they can be produced more cheaply than if wound to stand nine or twelve. Such coils should never be used with more than four dry cells, or six cells of so-called oil battery. A very frequent source of trouble with coils may be traced to their use in connection with sparking dynamos or generators. It is not safe to use them in the jump-spark system, without using an accumulator or storage battery, and a cut-out, either by means of a switch or an automatic device to prevent short circuiting the storage battery through the generator, when the engine stops. If the governor on the generator could be depended upon to maintain just the proper speed to produce the correct voltage, there would be no trouble, but around salt water particularly the governor is liable to "stick," with disastrous results. This is one of the bad features incidental to the use of jump-spark ignition. In the make and break system an increase of voltage to even twelve volts has no bad effect other than a tendency to burn out the igniter points, unless it runs so high as to break down the generator itself.

RECENT PERFORMANCES OF FRENCH HYDROPLANE BOATS.

BY OUR PARIS CORRESPONDENT.

The gliding boat, or hydroplane, has been occupying considerable attention of late, mainly owing to the remarkable performance of the boat which the Count de Lambert constructed not long since and equipped with a light-weight, high-power motor. This craft succeeded in out-distancing all the racing boats of the usual build in a race held October 15 last upon the Seine near Paris, and it was this performance especially which directed the attention of the public toward the question of gliding boats, seeing that heretofore it was not generally known what could be expected from the new craft. Owing to the good results which have now been obtained by the hydroplane, there seems to be no doubt that it is quite in the line of progress, and we may expect to hear of still more remarkable performances from this class of craft in the future. The question is being actively taken up in the vicinity of Paris, and no less than three different forms of hydroplane boats have been run upon the Seine, with very encouraging results. As regards the principle which underlies all the recent forms of gliding boats, it consists in making the craft glide upon the surface of the water with scarcely any immersion of the hull. This is done by giving the boat a sufficient speed from the use of a light and powerful gasoline motor and at the same time placing a set of planes under the boat which are slightly inclined and turned upward from back to front, so that when the boat reaches a sufficient speed the action of the planes causes it to be lifted partly or almost entirely out of the water, the latter being the ideal condition. While the usual practice of the first experimenters was to use a boat of about the ordinary section and then adapt underneath it a set of separate planes whose angle was adjustable, in all the present boats the plane surfaces are formed simply by the bottom of the boat, this being constructed so that there are at least two surfaces of this kind. What is essential for the hydroplane action is to have the boat light enough to be easily lifted out of the water and at the same time to provide sufficient power to give the proper speed for bringing about the lifting action. This is now easy to accomplish in the

present state of gasoline motor construction, especially since the new light-weight motors for aerostatic purposes have been brought out. In the early days of the hydroplane, inventors were handicapped, since they had only the steam engine available for the purpose,

in making his craft work practically, as afterward he ceased to experiment with it and appeared to have abandoned the idea. This was no doubt due to the fact that at that date the gasoline motor was not sufficiently developed to be of service for gliding boats. Count de Lambert built his first gliding boat in 1897 and tried it in England, where he worked for some time upon the question. He used the idea of a catamaran formed of two long and pointed floats and between them he placed a set of flat pieces which constituted the planes and lay below the surface of the water. The planes were adjusted at the proper angle, which was found by experiment. On the craft he mounted a small steam engine of the Field type, together with its boiler, but as this gave him a heavy weight for a small power he could not bring the boat up to the speed which he is now able to secure with a light gasoline motor. Nevertheless, his results were encouraging, and he found that his idea was a good one. Since the advent of the gasoline motor he has been at work upon the question and has already built a number of boats. The most recent type which he is now running upon the Seine still holds to about the same construction, using two main floats running along the whole length and joined at the top by a light platform. In the present form the planes extend clear across underneath the floats so as to cover the whole width of the craft. The planes are formed of flat surfaces and there are a number of them (five) in the length of the boat. However, the plane which forms the front end of the boat has the end somewhat curved upward, as will be noticed in the photographs. During his experiments Count de Lambert has found the best angle to give the planes and the proper length, width, and spacing that they should have. The right spacing of the planes is one of the most essential points for the proper working of the boat. These are 10 feet long by about 4 feet wide and spaced about a foot apart. Toward the front end of the craft is mounted a 50 horse-power gasoline motor

which weighs only $2\frac{1}{2}$ to 3 pounds per horse-power. We have already described this type of motor, which has been adopted by Santos Dumont, Capt. Ferber, and other aeronauts, and which will go far toward solving the problem of the gliding boat, since for the solution of this problem a motor of high power and



The Hydroplane Gliding Boat of Count de Lambert Getting Under Way and Rising to the Surface.

The boat consists of a catamaran mounted on five planes, each of which is about 4 feet wide by 10 feet long, giving a total lifting surface of about 200 square feet. The planes are set upon five per cent incline, with the exception of the front one, which is at a slightly greater angle. The 50 H. P., 8-cylinder motor has driven this boat, the inventor claims, at a rate of speed of thirty-four miles an hour.

and thus a heavy weight had to be lifted, a weight which was out of all proportion to the power which the motor would give.

As far back as 1876 M. de Sanderl had the idea of a hydroplane which consisted of a simple flat-bottomed boat of rectangular shape. At each of the four corners of the boat he mounted a propeller which worked horizontally in the water and was mounted on a vertical shaft. The boat also had a main propeller placed in the rear in the usual way. By giving the proper speed to the four screws at the corners, the boat could be lifted more or less out of the water so as to lessen the resistance to forward movement, and then the main propeller would cause the craft to glide on the surface of the water. He was not successful at that time in realizing this idea, since he found that the boat would require a considerable motive power, and hence that it could not be lifted by the use of a steam engine. Later on, M. Ader, of Paris, who is well known for his experimental work in different fields, took up the idea, and as late as 1895 he built a model of a gliding boat which somewhat approaches the present types. In this case he used a boat which was pointed at each end and was provided with a series of separate planes. At the front of the boat there were two planes spreading out at the sides and lying under water. They could be adjusted at any desired angle from the inside of the boat. At the rear there was a single plane which formed a tail and could also be adjusted. M. Ader had also the idea of injecting compressed air underneath the surface of the three planes, so that they would work more or less upon an air cushion and in this way the resistance of the boat would be still further diminished. It seems, however, that he did not succeed



Rear View of Count de Lambert's Hydroplane Boat Traveling at a Speed of $25\frac{1}{2}$ Miles an Hour.



"Nautilus B. V. Jacqueline" Under Way. This Boat Won the Cruiser Race at a Speed of 16.84 Miles an Hour.

RECENT PERFORMANCES OF FRENCH HYDROPLANE BOATS.

light weight is essential. It is to be remarked, however, that this power is needed only in starting up the boat and bringing it up to the speed where the planes cause it to lift out of the water, for it is evident that as soon as it commences to glide upon the surface it requires much less power to run, owing to the great diminution of the resistance. This, at least, is the theory of the hydroplane, although in practice the large catamaran shown made only 25.46 miles an hour with the motor developing 50 horse-power at 1,000 R. P. M., while a smaller one of about one-half the size and one-fourth the hydroplane surface made the same speed with from 12 to 14 horse-power. The present motor is of the eight-cylinder V pattern and is rated at 50 horse-power, running at the standard speed of 1,000 revolutions per minute, at which it runs when driving the boat. The displacement of the present boat, without fuel or water, is stated by the inventor to be 1,100 kilogrammes (2,425 pounds), and with three men the displacement is brought up to 1,500 kilogrammes (3,306.9 pounds), although as many as five persons, inclusive of the mechanic, can be carried. The displacement of the smaller boat, loaded, was 1,763 pounds. From the motor the slightly-inclined propeller shaft passes to the rear. The blades of the propeller are each pivoted so that they can be turned and the pitch of the propeller altered. This is found very convenient for handling the boat. There is also a rudder which is mounted in the rear in the usual way. As to the size of the boat, the length is 7 meters (22.96 feet) and the width about 3 meters (9.84 feet). The whole is of a very light and solid build, and the top platform is made of the usual slat work.

This craft made the remarkable performance which we mentioned above during the races which were held last fall upon the Seine at Maisons Laftite, in the suburbs of Paris. In spite of the fact that there were entered some of the fast racing boats, the hydroplane carried off the honors and made the record for speed over a 100-kilometer (62.1-mile) course, covering this in 2 hours, 25 minutes, which is equivalent to a speed of 25.46 miles an hour. The boat carried three persons and besides was obliged to make a number of turns, which are a decided disadvantage for this class of craft. In a straight line, Count de Lambert says, he made a speed of 55 kilometers (34.175 miles) an hour upon the Seine. At present he is constructing a new hydroplane, which is even of a simpler form. It is made up simply of a series of box floats placed between two long timbers on each side. Each float has the required plane surface on the bottom, and the assemblage of floats forms a kind of raft which has a number of gliding surfaces. It may be mentioned that Count de Lambert has been granted fundamental patents for the use of hydroplanes.

Another hydroplane boat which follows the same

general principle, but which is much smaller in size, is the "Ricochet-Nautilus," constructed by the Bonnemaison boat-building firm of Paris. Its general appearance is shown in the illustration. The bottom is formed of two inclined plane surfaces one of which


meters (29.825 miles) an hour. It is built to carry a single person. The oiling of the motor is carried out from an air-pressure oil tank, and the air pressure is given by a bicycle air pump. The rudder of the boat is shown at the front in the photograph, although two rudders at the stern are generally used.

The "Antoinette" speed boat is built on somewhat different lines. In front it carries a flat-bottomed boat of somewhat the usual form, while in the rear is attached a float forming a tail-piece which aids in obtaining the gliding action. The front boat carries the motor and passengers. From the motor a shaft runs to a propeller carried in the rear of the tail-piece. The latter (see diagram) has at the end a box-shaped piece whose under surface forms a plane, and the whole device gives a constant angle for the front boat in order to secure the gliding action. By using the front boat, the craft can stand bad weather and run even upon rough water, although its speed will be slower in this case. It will run on the hydroplane principle in smooth water.

The craft is built for the Levavasseur motor firm, who have mounted on it one of the light motors previously described and rated at 50 horse-power. Alone, the motor weighs 132.27 pounds, or 176.36 pounds with all accessories and ready to run. The displacement of the craft is 200 kilogrammes (440.9 pounds) counting the motor, and the total length is less than 9 meters (29.52 feet). It has already been run upon the Seine and showed a good speed. Capt. Ferber and also Santos Dumont piloted it on different occasions and were favorably impressed with its performance, stating that it had a good balance and gave almost the same sensation as an aeroplane in the air. Owing to the use of the long tail, there is but little spray at the back of the boat, seeing that this is forced to the rear. Since it has entered the field the new craft promises well and gives the gliding effect without losing its qualities of good floating and balance. Another point is the low consumption of fuel, which is claimed to be below what the ordinary craft use, while a higher speed is obtained.

In the cruiser class, the record for 15½ miles was made by the "Nautilus B. V.-Jacqueline," which covered the distance in 52 minutes 36.3-5 seconds, at an average speed

of about 16.84 miles an hour. This boat is noteworthy from the fact that it was driven by one of the new Bourdreaux-Verdet Duplex motors, which works on a new principle, and which we had occasion to describe in SUPPLEMENT No. 1597. The Duplex motor seems to be coming to the front on account of the different merits which it possesses in the way of low gasoline consumption per horse-power and the small space it occupies. One of the photographs on the preceding page shows the new cruiser at full speed. The clean way in which it cuts the water shows the design of hull to be a good one.



Plan and Longitudinal Section of Levavasseur Motor Boat.




The Levavasseur Freak Motor Boat, "Antoinette."




Tail of the Curious Two-Part Levavasseur High-Speed Boat.

extends from the stern to the middle of the boat. Commencing a few inches lower down, at the middle, is the second plane, which also runs upward toward the front and forms the bow of the boat. A cross-section of the boat one-third of the way back from the bow shows that the forward plane is not quite flat, but has a slight curve. Upon the boat is mounted a three-cylinder, air-cooled, Buchet motor of 10 horse-power, from which a shaft runs to a propeller at the rear. The latter runs at the motor speed of 2,000 revolutions per minute when at full speed. The new craft has been tried upon the Seine, and is stated to run at 48 kilo-



The "Ricochet-Nautilus," which has attained a speed of about 30 miles an hour with a 10-horse-power motor. This boat is about 11 feet long.



Count de Lambert's Hydroplane Boat at Rest, showing the normal submergence when stationary.

THE BRANGER CUP RACE FOR MINIATURE MOTOR BOATS.

BY THE PARIS CORRESPONDENT OF THE SCIENTIFIC AMERICAN.

Considerable interest was recently manifested in Paris in a series of races for model motor boats. A cup for one of these events was presented by M. Branger, a well-known French photographer of sporting subjects. The races were held on the lake of the Bois de Boulogne over a course some 150 meters (492.125 feet) in length, and they were watched with interest not only by the children but by their elders as well.

Some of the little craft traversed the distance at surprising speed, and a number of curious forms of miniature launches were to be seen, as the accompanying illustrations show. One of the conditions of the contests was that none of the competitors was to exceed 5 feet in length. Some of the latter were considerably smaller; in fact, one of the winners was but 23.6 inches long. There were twenty-four starters in the races, which were watched with great interest by a large crowd of spectators.


There were races for different classes and a special class contested for the cup. Some of the boats were driven by electricity, while others were provided with explosive motors; one of the latter was of $1\frac{1}{4}$ horse-power and was, as can be seen in the illustration, a single-cylinder, air-cooled motor fitted with high-tension magneto ignition, fly-wheel, friction clutch, etc.

Despite a damp and rainy day, these toy racers made a very fair performance, as can be seen by the following table of winners:

Racers 0.60 Meter (23.62 inches) in Length: Winner, "Girard IV." (owned by Girard), 2 minutes 27 seconds.

Racers 1 Meter (39.37 inches) in Length: Winner, "L'Eclair" (owned by Leroy and Breton), in 2 minutes

second in 2 minutes 20 seconds; and "Lorraine" was third in 2 minutes 25 seconds. The consolation prize was won by "Catarina" in 1 minute 16 seconds. This first toy motor-boat meet was very amusing, and was attended and directed by several constructors of motor



The "Girard I.," Winner of the "Coupe Branger."

boats, who gained not a little information as to the speed capabilities of different forms of hulls.

The Death of Henry C. Sergeant.


In the death of Henry C. Sergeant, which occurred January 30 at his home in Westfield, N. J., America has lost one of her most brilliant inventors. To the inventive genius of Mr. Sergeant the elevated railroad companies owe the chopping boxes, which enabled them to stop the use of uncanceled tickets on their lines,

The Effects of Ether and Chloroform on Plants.

The forcing of plants by means of ether has attained great practical importance. The process, however, is not applicable to all plants, for the growth of many species is retarded by ether, which appears to exert on them an inhibiting action as it does on the nervous system of animals. Alfred Burgerstein has recently published the results of experiments on the effects of ether and chloroform on a great variety of plants. He studied especially the action of ether on the buds of deciduous trees and shrubs and the effects of both ether and chloroform on the growth of bulbs and the germination of seeds. The unfolding of some buds was accelerated, that of others unaffected by etherization. Begonia buds were retarded. Etherized narcissus bulbs sprouted a week earlier and etherized onions three days later than untreated bulbs, while tulips were not affected by ether.

Etherization continued for 48 hours, using 3 volumes of ether to 10,000 volumes of air, exerted no further injurious effect on bulbs, but the same proportion of chloroform killed them all in 8 hours. The germination of air-dried seeds was accelerated by exposing them for 24 hours to an atmosphere containing from 2 to 8 volumes of ether to 10,000 volumes of air, but the proportion of seeds that germinated was not altered. Chloroform, employed in the same manner, accelerated the germination of some seeds and retarded that of others, but it generally reduced the proportion of seedlings. When the seeds were first soaked in water etherization diminished their germinating power and chloroform, in most cases, killed them.

The growth of bean, pumpkin, and sunflower plants was almost or entirely checked in an atmosphere containing 0.004 per cent of chloroform, but the same proportion of ether promoted their growth and the plants



Plan View of the "Girard I.," Showing the $1\frac{1}{4}$ -Horse-Power Air-Cooled Motor, the Gasoline Tank, and Carbureter.



A Group of Model Motor Boats, Showing the Different Types and Sizes.

47 seconds; 2, "Girard III.," in 4 minutes 30 seconds.

The winner of this event was given the superb silver medal donated by "Les Sports."

Racers $1\frac{1}{2}$ Meters (59.05 inches) in Length: 1, "Girard I.," in 1 minute 5 seconds (5.16 miles an hour); 2, "Lorraine" (owned by Pierre de Fontbrune), in 1 minute 50 seconds; 3, "Catarina" (owned by Le-tang), in 2 minutes 45 seconds.

The race for the "Coupe Branger" was won by the "Girard I." in 1 minute 20 seconds. "L'Eclair" was

and materially to increase their profits. His first invention, which he worked out when only eighteen years old, was a machine for making wagon wheels. In 1862 he patented a governor for marine engines to prevent the racing of propellers. This governor the United States government at once adopted for war vessels. He took out patents on more than fifty air compressors and drills, and his development of the drill that bears his name made it possible to carry out some of the greatest engineering achievements of the last quarter century.

threw in air thrice as strong in ether. The effects on the power of reaction to light and gravitation were analogous to the effects on growth.

It appears, therefore, that the entire vital energy of some plants is increased and that of others diminished by ether and chloroform.

The special commission appointed to consider the construction of bridges will recommend to the New York Legislature the construction of two bridges from Staten Island and one from Manhattan to New Jersey.



A Well-Designed Entry.



Preparing Some of the Contestants for the Races.

THE RACES IN THE LAKE OF THE BOIS DE BOULOGNE, AT PARIS, FOR MINIATURE MOTOR BOATS.

LATEST TYPES OF CRUISING POWER BOATS.

In the first-page illustration of this number of the *SCIENTIFIC AMERICAN* are shown three of the latest types of cruising power boats. The two shown in the upper part of the illustration are "La Mascotte III." and the "Dixie," the first of which was designed by Mr. H. J. Gielow for Mr. F. C. Havens, of San Francisco, and the latter by the Electric Launch Company.

"La Mascotte III." is 84 feet over all, 75 feet 9 inches on the waterline, with a beam of 13 feet, and a draft of 3 feet 6 inches. On deck forward are a pilot house and a cabin, provided with the usual transoms, table, lockers, and buffet. The staterooms, which contain berths and lockers, are arranged on each side of a passageway leading to the engine room.

Each of the staterooms connects with a private toilet room. The quarters of the crew are aft, and provide accommodations for two men. In the engine room are two berths, seats, lockers, etc., for the members of the engine-room staff.

The vessel is driven by two 75-horse-power Craig gasoline engines, and it is provided with the necessary lighting, ventilating, and other auxiliaries. The fuel supply—620 gallons at a maximum—is carried in tanks located in water-tight compartments. The vessel is steered from a bridge aft of the pilot house, and is equipped with a single military mast and a stack.

The "Dixie" is 93 feet over all, 85 feet 9 inches on the waterline, with a breadth of 13 feet 6 inches, and a draft of 4 feet. Her accommodations consist of a forecabin, finished in quartered oak with brass air ports for light and ventilation. The owner's quarters, which are also forward, and are finished in African mahogany, contain two Pullman berths equipped with regular Pullman car fittings with drawers for storage. There is also a bureau with plate-glass mirrors and extra wide and deep drawers. The owner's private bath is adjoining and contains a porcelain tub, shower bath, basin, and a large closet. The windows in the owner's quarters are of plate glass, protected by Venetian blinds, while additional ventilation is secured through a large skylight.

The galley is situated aft of the engine room and extends the full width of the boat. A large range burning either coal or wood is provided, together with a roomy ice box, having a capacity of 650 pounds of ice, a sink, cupboard, dresser, and closets.

The main saloon is 19 feet long, finished in mahogany, and contains a large Chippendale sideboard with glass doors, drawers for silver, linen, etc. There are also four standard Pullman berths, and a toilet room opening into the saloon on the port side forward. The windows in the saloon are protected by Venetian blinds, as in the owner's quarters, while a large skylight furnishes additional light and ventilation.

The engine room contains two 110-horse-power 6-cylinder Standard reversible engines and an 8-horse-power gasoline engine direct connected to a dynamo for supplying electricity throughout for lighting, searchlight, fan motors, heating and cooking.

The yacht will be steered from the bridge and will also be equipped with military mast, stack, one 14-foot dinghy, and a 15-foot 6-inch power tender, with a 2-horse-power engine; an awning covers the entire yacht.

The hull has been very substantially built, having an oak keel and frame and yellow pine planking, all copper or yellow metal fastened.

The craft illustrated in the lower engraving is the "Hawk," which was designed and built by Mr. C. Du Poix, of New York city, for a gentleman residing on the Isle of Pines. It was intended for use both as a pleasure yacht and as a passenger carrier during the busy season of commerce. The conditions of service necessitated a seagoing power yacht of fair speed and wide cruising radius for operation in and around the Caribbean Sea. Weather conditions in that part of the world often put the craft plying those waters to the severest possible tests, and the question of seaworthiness was a factor of the greatest importance in the design of the "Hawk."

The vessel is built entirely of steel, with six water-tight compartments, and the construction is one which offers great strength of hull. The deck is flush, with but a single companion way, that leading to the owner's quarters. All other openings are either watertight torpedo hatches or watertight steel skylights. There are two engines, each of 75 brake horse-power, using gasoline fuel. The latter is carried normally in four tanks placed abreast, each in a watertight compartment and provided with a water seal. Extending forward from the engine room bulkhead for 14 feet is a double bottom, the space within which is adapted to be used as a reserve fuel tank, or otherwise as a ballast tank. The full tank capacity totals 2,000 gallons.

Most of the auxiliary power devices are electrically driven. They include the lighting plant, the fire and bilge pumps, an ice-making plant of the Brunswick Refrigerator type, and the ventilating system. The ice machine compressor is driven by a 1½-horse-power motor in the engine room. The cold storage and ice com-

partments are located in the galley. Twenty pounds of ice are manufactured per day, while at the same time two refrigerating compartments are cooled. The cooking is done upon an electric range, an auxiliary oil stove being provided for emergencies.

A system of forced draft provides ventilation. An electric blower is placed aft of the conning tower, where it is shielded from breaking seas. This forces air through lines of pipes, one on each side of the boat, just above the cabin floor. Each room contains proper regulating apparatus for use in connection with the ventilation system. The air is withdrawn from the various parts of the craft through flat pipes located near the gusset plates on each side of the hull. These pipes unite in the engine room and communicate with an exhaust blower, which expels the air through a ventilator.

The conning tower is located well forward, and not only provides a place for the steersman in bad weather, but is also a chart room and smoking den. It is provided with a large, comfortable leather divan, adapted for sleeping purposes in case of necessity. Two sets of steering gear are provided in the conning tower, as well as an engine-room telegraph, a telephone to all parts of the vessel, and the usual bell signal system and speaking tubes. The electric masthead and side lights have telltale lights showing in the conning tower. The lights, as well as the searchlight and the siren, are controlled from within the latter. An auxiliary steering gear is provided on the platform aft of the conning tower for use in fair weather.

The accommodations and living arrangements are all of the very best. The toilet and bath rooms are of the latest design. The main saloon is large, airy, and comfortable, and is provided with two transom berths, a self-playing piano, buffet, bookcases, lockers, etc. Accommodations are provided in the forecabin for a crew of four, and two berths are located in the engine room for the crew of that department.

The joiner work throughout is of composition fire-proof board painted with white enamel. Interlocking rubber tiling is used in the saloon, bathroom, passageways, and in the pantry and galley. The upholstery is of dark green leather. Two boats are carried in patent folding davits—a power dinghy and a whaleboat. The deck is of teak, with all deck fittings of steel.

Aeronautic School in Germany.

Arrangements have just been completed to establish at Chemnitz a training school for aeronauts and constructors of airships. A similar school has been in operation in Paris for a year past. The Chemnitz institution will be the second enterprise in this new pedagogical field. A one year's course is contemplated for the present, the school to be opened in May, 1907. This course, at the outset, is limited to the construction and use of balloons. It will be enlarged so as to include aeroplanes, as soon as practical working types have been developed.

The successive divisions of instruction during the year's course are as follows: Calculation of volume of balloons; methods of cutting the material; methods of rendering the material impermeable; construction of nets; gases used for inflation; the general theory of balloon construction and use; scientific instruments used in balloon ascensions; meteorological observations; ascents alone; ascents with passengers; special instruction for passengers; methods of landing, and the application of airships. The tuition for a year's course is 600 marks, or \$143.

The Current Supplement.

The current SUPPLEMENT, No. 1625, opens with an article by Dr. Alfred Graevenitz on the Southwestern African Railway, which is probably the longest road of its kind in the German colonies. Good pictures accompany his description. Mr. Walter J. May tells how unusual castings can be made. The mechanical design of ball bearings and roller bearings is ably discussed by W. S. Rogers. The first installment is given of a series of articles on plaster-of-Paris. Mr. W. E. Parsons contributes a well-considered forecast of our manufacturing industry. Mr. F. P. Fish's admirable elucidation of the ethics of trade secrets is concluded. The purchase by the British Admiralty of a gasoline, motor-driven torpedo boat is an official indorsement of a new type of fighting craft. For that reason the SUPPLEMENT's illustrations of these new types, together with an article, will be of interest. The flights of Zeppelin's airship on October 9 and 10, 1906, are described in detail by Prof. Hergesell and Capt. von Kehler. Electric sleep or anesthesia is a subject of which we are bound to hear more in the future. Dr. G. H. Niewenglowski's brief review of his experiments and those of Prof. Leduc should, therefore, be read with interest. In an article entitled "Theory and Action of a 100-Mile Wireless Telegraphic Set," A. Frederick Collins tells something of the theoretical action and the practical working of the instruments employed in the 100-mile wireless telegraph equipment which is described in SUPPLEMENT, No. 1605.

INFLUENCE OF THE AUTOMOBILE ON LAUNCH DEVELOPMENT.

BY W. P. STEPHENS.

Following closely on the Automobile Show comes the Motor Boat Show at Madison Square Garden, marking a new era in launch and gasoline-engine building. As the Automobile Show had its germ in the great bicycle shows of the late nineties, so the gasoline launch has served as an incidental attraction to the annual Sportsmen's Show until the present time, when it takes its place as one of the great yearly show attractions of New York.

Though antedating the automobile by nearly a dozen years, the marine gasoline engine was at the time of the first Automobile Show in 1900 but little advanced beyond its early primitive stage. Its manufacture was regularly established, it had found a limited market among yachtsmen and to a certain extent among fishermen and other workers, and, mechanically, it had reached a point where it was sufficiently reliable and economical in operation to justify its use in spite of many serious defects; but it was found in only one very heavy type, built almost entirely of cast iron, which made it bulky. Its design was such that it was limited practically to the low speed of about 300 revolutions per minute. Besides this it was weak in its respiratory organs (the primitive vaporizer or carbureter of the day), and was fitted with an ignition system of the make-and-break type that had hardly passed the experimental stage. Its possibilities being unknown to the yachting world, the only demand was for this ordinary heavy type of engine for cruising launches or working boats, and there was no inducement to the builder to invest large sums in the development of lighter and more efficient engines. Even the most progressive builders of the day aspired no higher than the improvement in detail of the heavy launch engine.

In England and France the development was even more backward, launches being few in number and mainly propelled by kerosene, in every way inferior to gasoline as a fuel. The awakening came, however, in the latter country, where in 1900 the new type of light, high-speed, automobile engine was first tried in a launch hull. The experiment was successful. New hulls of special design and construction were soon afloat, driven by the leading makes of automobile engines; the vocabulary was enriched by a brand-new term—"canot-automobile"—and the new sport of high-speed motor-boat racing was fairly launched.

From the start the "auto-boat" or "canot-automobile" all but rivaled the motor car in popularity. Races were held for valuable prizes; the cleverest of naval architects were called on for designs of lighter and faster hulls, and all the resources of automobile engineering were called into play for the perfection of the new type of "auto-marine" gasoline engine. The fever was by no means confined to the Seine and the Mediterranean, but found its way across the Channel and even across the broad Atlantic, meeting a hearty welcome from American clubs and yachtsmen.


The high-speed auto-boat has proved to be little more than a costly and useless toy; the hull, designed solely for the highest possible speed, gives neither comfort nor accommodation, while the passenger, even in smooth water, is drenched with a cataract of spray thrown by the razor-like bows. The extremely light construction makes the boat useless except for racing; the light and delicate engines require the highest possible skill for their care and manipulation, and they are always liable to derangement and breakdowns. The first excitement over, the sport has proved far less fascinating than at first promised, owing to the great number of failures of entered boats to start, or, having started, to finish the course.

In spite of its own defects, however, the auto-boat has been a blessing to yachtsmen and to engine builders alike, in that it has forced in less than five years a development that, to all appearances, would in its natural course have taken twenty years. To put it briefly, where the average speed of the pleasure launch was well under ten miles per hour half a dozen years ago, the effort to attain a speed of thirty miles in the auto-boat has raised the average speed probably 50 per cent, while there are staunch, strong, and seaworthy launches that run regularly over twenty or twenty-two miles in the hour.


One of the most generally useful and popular of the many new types is that called "the ferry launch," of 50 to 80 feet length, fitted with at least a cabin for bad weather, if not with conveniences for a meal and a bed on occasion, with large comfortable cockpit, and having sufficient power to carry the owner and his family or friends from his home on the Sound or the Hudson to some New York pier at a regular speed of eighteen to twenty miles an hour or even higher.

The first step in this development has been through the engine. In France all the resources of the automobile builder—the highly-skilled engineer-designer, the chemist and metallurgist, the maker of fine steels and bronzes, the expert machinists, and fine machine


(Continued on page 170.)



The 50 H. P., Twin-Screw, 60-Foot Motor Yacht "Katrina II." Speed, 13 Miles an Hour.




A Typical Racing-Boat Stern.




A Typical Cruiser. The 25 H. P., 46-Foot "Hazel."




The 33½-Foot "Josephine." Her 36 H. P., Speedway Engine Has Driven Her at a Speed of 22.9 Miles per Hour.




The 26¼-Foot Cruiser "Buddie II."
Photo copyright 1906 by Edwin Levick.



The 67-Foot, 50 H. P., Twin-Screw Coast Defense Inspection Motor Boat "Norka." Speed, 14 Miles per Hour.



The 36-Foot, 30 H. P. Cruiser "Unome," Which Reached College Point First in the Race Last Year from Marblehead, Mass. Average Speed, 9.5 Miles per Hour.



The 90-Foot, Twin-Screw, Gasoline Motor Yacht "Dodger" Driven by Two 300 H. P. Standard Engines. This Boat is Said to Have Reached a Speed of 25 Miles per Hour.



The 60-Foot Racer "Standard," Fitted With a 300 H. P. Double-Acting Standard Gasoline Motor. Average Speed in Mile Trials, 29.39 Miles per Hour.

VARIOUS TYPES OF MOTOR BOATS.

NEW TYPES OF GAS ENGINES FOR MARINE WORK.

BY COMMANDER A. B. WILLITS, U. S. N.

The four-cycle principle is the most perfect one in theory and practice. Here the explosion of a charge performs its expansion and works completely to the end of the first stroke. It is then exhausted and expelled by the return of the piston through the entire second stroke, while the third stroke draws in fresh mixture, which is compressed on the fourth stroke ready to be exploded at the beginning of the next. Here there is certainty of obtaining a full charge of the mixture in the proportions delivered through the carbureter, and both the increased reliability of action of this type and the decreased fuel consumption per horse-power are positive and marked. It is the type used in nearly all of the automobile engines built, and, in the marine-motor field, is the type along which high powers are being designed.

The Bureau of Steam Engineering has taken keen interest in the current advances in this class of motive machinery, and has had its representatives witness the tests of the latest types with a view to the opening for such installations in torpedo boats when the fuel question is less uncertain. Already there are fourteen gasoline and gas motors installed in naval small craft and eight others waiting completion of hulls. Besides these, motors for light-powered boats for torpedo craft have been designed and are being built under the Bureau's directions at the Norfolk yard. The question of replacing the machinery of some of the torpedo boats by explosive-mixture motors is still under advisement, and nothing is being lost through lack of keeping in touch with the latest developments. The naval installations thus far are as follows:

	H. P.
"Adder," submarine.....	Otto 4-cycle, 160
"Grampus," submarine.....	Otto 4-cycle, 160
"Moccasin," submarine.....	Otto 4-cycle, 160
"Pike," submarine.....	Otto 4-cycle, 160
"Porpoise," submarine.....	Otto 4-cycle, 160
"Shark," submarine.....	Otto 4-cycle, 160
Sixty-foot Indian Head ferryboat.....	"Standard" 4-cycle, 300
Yard ferryboat, Portsmouth, N. H.....	"Standard" 4-cycle, 300
"Sylph's" tug.....	"Standard" 4-cycle, 25
"Sylph's" tender.....	"Standard" 4-cycle, 12
"Maine's" 28-foot whaleboat.....	Jager 4-cycle, 10
Special 20-foot whaleboat, Norfolk.....	Godschalk 2-cycle, 10
Special 20-foot tender, Norfolk.....	"Standard" 4-cycle, 12
"Vesuvius" 23-foot launch.....	Jager 4-cycle, 10
Total.....	1,639

Those awaiting completion of hulls are:

	H. P.
Submarine "Nine" (Fore River).....	Craig 4-cycle, 250
Submarine "Ten" (Fore River).....	Craig 4-cycle, 250
Submarine "Eleven" (Fore River).....	Craig 4-cycle, 250
Submarine "Twelve" (Fore River).....	Craig 4-cycle, 250
Seventy-five-foot ferryboat, Training Station, S. F., U. S. N.	Works 4-cycle, 250
Water barge, Mare Island, Union Gas Co., 4-cycle.....	120
Water barge, Portsmouth, N. H., (2) Globe, 100 each, 4-cycle.....	200
Total.....	1,570

It is seen by the above that 300 I.H.P. is the largest size motor thus far purchased by the government, and this installation in the 60-foot launch built for service between Indian Head and Washington stood a most satisfactory trial and gave excellent performance. This is a single-acting, six-cylinder, "Standard" gasoline motor. It is of light construction, and its peculiarity is that it is started as well as reversed by means of compressed air and a single movement of a cam-shaft lever, exactly as if handling an ordinary reversing link motion. Compressed air to 250 pounds per square inch is primarily pumped up into two air tanks running along the side of the engine room, by means of a small auxiliary, 1-horse-power gasoline engine driving an air pump for the purpose, this engine being also intended to drive a bilge pump and small dynamo for lighting and charging storage battery. Only the three after cylinders are connected to compressed air, and when

the reverse lever is thrown to the first notch away from center, either forward or back, the cam shaft is shifted along to such a position as will bring cams to operate the compressed-air valves on these three cylinders, and to lift the exhaust valves on same once every revolution, instead of every other revolution. The three forward cylinders operate always on gasoline, the cam shaft shifting governing the rotative direction of the engine only. The three after cylin-

ders are now operated by opening the compressed-air throttle valve, and the instant the engine starts and makes two or three revolutions, the lever is pushed on to the next notch, which cuts out the compressed-air valves, and adjusts the cams to trip the valves in a regular, four-cycle sequence. Practically, the handling of this motor is very simple, there never being a minute's hesitation in the action of the engine or the result on the boat, as the motor jumps to full speed




Fig. 1.—Vertical Cross-Section of Double-Acting Four-Cycle Gasoline Engine.

almost instantly. While running, an air pump or compressor, attached to the main-engine shaft, keeps the air supply up in the tank, but can be shut off at will. There is no difficulty in keeping up pressure for weeks at a time in the tank, and in reversing there is usually but a drop of about five pounds in the pressure.


There will be no future for the single-acting motor for large powers in marine work. The manifest advantages in the matter of weight and arrangement for variations in cruising powers, as well as in greater effectiveness in distribution in the double-acting type, will make it unquestionably the only one to be considered in the development of this class of machinery for sea-going craft. The difficulties at first experienced in arranging for the proper cooling of pistons and rods, and in devising efficient packing for the rod stuffing boxes, have been overcome, and, as before

motor for the Indian Head boat, except that a regular reversing controlling cylinder is used with compressed air instead of steam, bringing the reversing under perfect control. Means can also be provided by which, with one motion of a lever, all the lower exhaust valves can be lock opened and all the lower inlet valves can be lock closed instantly, thus changing the engine at once to a single-acting six-cylinder motor, or, in other words, cutting down to half power with one movement and without any substantial decrease in economy. Furthermore, the two units of three cylinders each can be unclutched so that the after three cylinders can be operated alone single acting, which actually reduces the power to one quarter of the original. Taking these points into consideration, together with the fact of being able (with a liquid primary fuel) to get under way at a moment's notice under full power and maintain absolute regularity of speed as long as the fuel lasts, there seems to be little more to be desired toward securing an ideal marine motor, and, even should producer gas be used, the same control of the variations of the power is maintained, although the ability to instantly start from cold port conditions is not secured, there being, of course, some delay in getting the fire properly under way in the retort.

Many of the details of the construction of this 500-horse-power double-acting motor are shown in the photograph and are extremely interesting to the naval engineer. In Fig. 2 the inlet side is shown, the carbureter (overflow type) being in the middle and placed low down, and directly controlled by the throttle-valve lever at the reversing cylinder on the left. The inlet valves for compressed air are on the back, and not shown, but are merely applied in this type to the lower ends of the three after cylinders, so that the three upper ends of these cylinders and the entire three forward cylinders are constantly "on" gasoline, either in the go-ahead or backing position of the cam shafts; and, as the sparking continues in all cylinders during the action of reversal, the very moment the compressed air starts the engine in reverse the other cylinders immediately take up action with gasoline, and the engine is running on explosive fuel immediately, so that the action of the compressed air is not practically more than the shifting into reverse motion and starting the engine in the desired direction. The moment this results the reverse lever is shifted to the full-throw notch, which restores the lower ends of the after cylinders to gasoline. This reversal is practically instantaneous. All the cam shafts are positively driven by gearing from the main shaft, and, consequently, the adjustments of the cams are exact, and the tripping of the valves in this arrangement is accomplished almost noiselessly.

The lubrication of this motor is also a very interesting feature. Forced feed with sight-feed adjustment is accomplished through plunger boxes shown on the after end of the motor, the upper box being for delivery to the center of each cylinder, and the lower box for delivery to the middle of the piston-rod stuffing boxes, the plunger pumps for each of the small pipes being worked by a lever with a small connecting rod to a pin on the end of the exhaust-cam shaft, which

gives sufficient rotary motion for the desired lift, the lift being also further regulated by a slot in the plunger lever, to which the connecting rod is attached. The lubrication for the crossheads and crank pins is accomplished by a small plunger pump worked by a gear at the forward end of the exhaust-cam shaft, similar to the gasoline pump shown at the forward end of the inlet-valve cam shaft in the photograph, the oil being kept in a constant flow from the crank pit into which it falls, up through a strainer box between the two sets of three cylinders (and just seen in the photograph), back of the middle branching of the inlet pipe, and fed by gravity from this tank to the journals; a surplus of oil being constantly circulated by this method and kept



A 6-Cylinder, Double-Acting, Standard Marine Gasoline Engine of 500 Horse-Power.

The cylinders of this engine are of 12 1/4-inch bore and stroke. A 1000 H. P. engine with 16x16-inch cylinders is under construction.

A NEW TYPE OF GAS ENGINE FOR MARINE WORK.

noted, examples of double-acting gasoline motors of 500 horse-power are already in satisfactory operation afloat.

It will be seen from Fig. 1 that the valves are positively operated, water-cooled, and balanced. The pistons are cooled by water circulating through the cross-head, up a tube in the piston rod, providing a return circuit around this tube. The reversing of the engine is similar to that described for the 300-horse-power

constantly strained without waste. The journals are of ample dimensions and give no trouble whatever from heating with this system of lubrication.

Another important feature in this installation is that connected with the circulating water. As the boat is designed to run in salt water, there has been a connection made by an ordinary keel condenser between a small fresh-water tank inboard and the circulating-water pump, this latter pump being a slow-moving one

of ample dimensions worked by direct gearing on the main shaft. It is found by this means that ample cooling water can be maintained from a very moderate original supply of fresh water, and the objectionable features of having salt-water circulation are entirely obviated. Unquestionably this will be an important factor in all salt-water installations of this kind, and will greatly add to the endurance and protection of the outfit. Where the circumstances make a keel condenser in any degree objectionable, a regular tube condenser (more properly a cooler) can be adopted with circulating pump for it, and secure ample provision for the work.

In the boat inspected containing this motor, an independent installation of a small 4-horse-power "Standard" motor was made for the purpose of driving a dynamo for lighting the vessel and charging storage battery, a bilge pump for constant use, an air compressor for pumping up the compressed-air tanks whenever necessary, and a small magneto for sparking. This auxiliary is not necessary to use except when particularly desired, as, when the main engines are in operation, the air supply is kept up in the tanks by attached pumps, and it is easy, of course, to attach bilge pumps to the main shaft, so as to permit disuse of the auxiliary engine, except at night.—Journal of the American Society of Naval Engineers.

A HIGH-SPEED MOTOR BOAT THAT CAN BE BUILT AT HOME.

The illustrations shown herewith depict the Brooks Boat Company's "No. 13," as viewed from the front, rear, and side when traveling at high speed through the water. When the fact is considered that this boat was claimed to be going 28 miles an hour when the photographs were taken, one can readily see that the model of hull used is a good one, and one that throws but little spray when compared, for instance, with the "Standard," shown at the bottom of page 168. Fitted with a 60-horse-power, six-cylinder Sterling engine, "No. 13" is claimed to have made a measured mile in 2 minutes 8 seconds last summer, which would be at the rate of 28.12 miles an hour. As the photographs show, this boat looks every inch a racer, and appears from the shape of the hull to be capable of attaining the speed claimed. It is 39 feet 7 inches in length by 5 feet beam, with a depth of hull at the bow, amidship, and at the stern of 31, 29, and 19½ inches, respectively. The draft depends upon the size of propeller used, as the hull is made flat at the stern, so that it glides nearly on the surface of the water.

The builder of the above-described speed boat is one of the oldest boat-building concerns in this country. This company not only builds boats, but also makes a specialty of furnishing frames complete, with all the necessary material for putting them together and with patterns for cutting the planking. When supplied with all this material and instructions, which can be had at relatively small cost, the amateur can build himself a boat during leisure hours, knowing that when it is completed, his craft will not be an experiment either with regard to appearance or speed.

Besides the racer shown, the Brooks Company builds, or supplies frames for, several smaller speed craft, among which are a 30-foot racing boat claimed to make 16¼ miles an hour with an engine of 10 horse-power, and a 22-foot speed launch, claiming also 8½ miles an hour with a 2-horse-power motor, and which should therefore make as high as 12 miles an hour with 6 to 8 horse-power. Still another interesting model is a stern-paddlewheel boat, which can be built in varying sizes from 25 to 40 feet in length. This boat can be built as an open or closed launch or as a boat for freighting purposes on shallow lakes or streams. Equipped with a 7 to 12 horse-power motor, it will attain a speed of from 6 to 9 miles an hour.


Cupro-nickel, says the Brass World, is used for two purposes: In the manufacture of bullet jackets and in the production of five-cent pieces.



Bow View, Showing Wave Formation.



Stern View, Showing Wake.



The Brooks "No. 13" Making 28 Miles an Hour.
A RACING MOTOR BOAT FOR AMATEUR BUILDERS.

Bullet jackets consist of 80 per cent of copper and 20 per cent of nickel. The five-cent pieces made by the United States government are composed of 75 per cent of copper and 25 per cent of nickel.

INFLUENCE OF THE AUTOMOBILE ON LAUNCH DEVELOPMENT.

(Concluded from page 167.)

tools—have been utilized in the production of engines of phenomenal lightness, up to 300 horse-power or high-

er, and especially designed for launch installation. At the same time every improvement in the automobile world in the line of carbureters, ignition devices, lubricators, etc., has been transferred to the marine engine.

In this country, under somewhat different conditions of manufacture, the builder has had on the one hand his old, heavy, slowly-turning engine, and, on the other, the French automobile and auto-marine engines, of wonderful refinement and lightness. The result is seen in several magnificent machines in the larger sizes, purely of the marine type, with the skeleton framework of the steam torpedo-boat engine, light and powerful to an extent not dreamed of five years ago, with all the latest advances in gas-engine practice and electrical science making them as reliable and practically as flexible and tractable as the steam engine. Every development of automobile engineering in the line of better materials, finer tools, and improved methods has gone to further the perfection of the marine engine.


But the full measure of advance is not to be gaged solely by such costly machines as the double-acting, six-cylinder engine of 500 horse-power, started and reversed by compressed air. The improvement begins with the smallest and cheapest of the two-cycle engines, where better materials, improved design, standard tools of greater accuracy, and more scientific carbureters and ignition devices, have raised the standard and decreased the relative cost. Throughout the whole range of heavy engines, still in demand for much of the yacht work and in fishing and working vessels, there has been a general improvement along the same lines. Next to these stands a new class of launch engines of varying sizes from 20 to 80 horse-power, mostly of high speed as compared with the old type, but far lighter, more compact, practically as strong and durable, and superior alike in reliability and economy.

With the improvement of the engine and the multiplication of types and sizes has come a reconstruction of the entire power pleasure fleet on new lines. Limited no longer to a few sizes of engine of a single type, the yachtsman and his designer have been free to plan a great variety of new craft. For day use there are launches of comparatively high speed of from 20 to 80 feet; for ordinary pleasure running there are comfortable and convenient craft of good speed, easily handled by one person and safe in any ordinary weather. Where cruising is the main object, the reduction in size and weight of engine has brought about a corresponding change in the refinement of the hull, which is no longer a homely box from which a speed of but six or seven miles per hour is expected, but is as handsome and graceful as a sailing yacht, with double the accommodation on the same length, and with a speed of at least a dozen miles. Still another new type is the rough-water cruiser, from 30 feet upward, including the 40-footers that raced around Cape Cod in 1905 and 1906 and the 40 to 60-footers that will race to Bermuda this year. While for this special work the old type of heavy engine still takes precedence of all others, the development of this most useful and interesting class may be traced back directly to the autoboat racing of two and three years ago—a reaction and a protest it is true, against the extreme racing type, but nevertheless owing its origin to it.

CANOVETTI'S AIR-RESISTANCE EXPERIMENTS.

BY THE PARIS CORRESPONDENT OF THE SCIENTIFIC AMERICAN.

In view of the great activity which we find at present in the line of aeroplanes and airships of different forms, the study of the resistance which the air offers to moving bodies becomes one of considerable importance. This question is also of interest in the design of high-speed trains or automobiles and in another field, in the design of projectiles for artillery. Newton was the first who formulated a series of laws for air resistance, supposing that it is produced directly by the inertia of the molecule of air as acted upon by the moving body. But this hypothesis is far from being in accord with what happens in reality, and the laws which result from it



Cabin of the U. S. Coast Defense Inspection Boat "Norka," Which is Noteworthy for Its Roominess and Comfortableness.


A TYPICAL MOTOR-BOAT INTERIOR.

are only good within certain limits, and then approximately. Following him, Euler brought out another theory which comes nearer the practical conditions but without corresponding with them completely. On account of its great elasticity, the air gives rise to phenomena which are not to be foreseen by theory. It acts differently according to the speed of the moving body. Up to a speed of 800 feet per second the velocity follows a certain law, and after that it departs considerably from this law. It is difficult to establish any sure data of this value of air resistance for various shapes of bodies, and in spite of the experiments which have been made hitherto in this direction, we may say that the question is far from being completely solved.

An important contribution to this subject is the recent work of the eminent Italian engineer Canovetti. The experimental work which Signor Canovetti has been carrying out of late concerning the question of air resistance to bodies moving at a high speed is of great interest. The first experiments which Canovetti undertook were made at Brescia in 1897 and from the commencement they proved highly successful. To carry out the tests, he used a steel cable of small diameter which was stretched from the top of the Castle of Brescia, a structure of considerable height, some 260 feet, down to the ground at an easy slope of about ten degrees. The wire was tightly stretched so as to give a nearly straight path, and upon it was made to run a two-wheeled carriage, transporting the body upon which the experiments for air resistance were to be made. The bodies were hung below the carriage, and were variously shaped. For instance, one or two circular disks were formed of a metallic hoop with canvas stretched upon it. Where a pair of disks were used, these were placed one behind the other and at different distances. The researches were carried out with special reference to the forms of the bodies and the speeds which would have a direct application in aerial navigation, either for aeroplanes or elongated balloon bodies such as are used for airships.

Since the first experiments were made, Canovetti desired to carry on another series of researches, but on a larger scale. This he had an opportunity of doing, for the Como Brunate inclined plane, which runs up the mountain slope, was put out of working order by a

series of repairs which had to be made, so that Canovetti found that he could make use of the inclined tracks for carrying out his new experiments, and thus means were at hand for making these tests upon a much larger scale both as to distance and size of the apparatus than before. In this work he received aid from the Accademia dei Lincei which enabled him to carry it out in a very thorough manner. To this end he had built a four-wheeled carriage frame of light and strong steel tubing, so as to run upon the rails of the track. Mounted at the front end of the carriage is a large square frame of bamboo upon which is stretched a cloth covering having a total surface of ten



Canovetti's Car on Track With Air-Resistance Frame Using Small Amount of Canvas.

square yards. In the center of the carriage are placed two ballast carriers in the shape of steel cylinders which can be loaded with small lead weights to the extent of forty pounds for each cylinder or a maximum of eighty pounds for the carriage. The total weight of the latter is about 160 pounds. The apparatus thus constructed is taken to the top of the incline and allowed to run down the slope by its own weight. At the bottom of its course the carriage is stopped by a metallic network which is stretched upon a properly designed frame and is rendered elastic by a system of springs and counterweights so that the carriage is


stopped without too much of a shock. Starting with the square frame a number of other frames having different forms are used, such as a flat round disk, a conical form, and others. When using the square frame and varying its surface from ten to two square yards, and at the same time varying the weight on the carriage, the latter was found to take different and increasing velocities each time, and the speed of travel was measured and registered very accurately by means of an electric device. A series of contacts are placed along the track, spaced about eighty feet apart, and the contacts are connected with the registering station at the foot of the slope. Here are placed a set of apparatus which have been specially designed for this purpose and upon which is observed the exact course of the carriage at any given moment. The registering instrument consists of a double Morse register, and the paper strip which is unrolled at a regular rate contains two sets of punctures. The first series of dots are made at regular intervals by means of a clock, while the second set lying alongside the former are formed by a needle-point on the armature of an electro-magnet through which current is sent from the contacts lying along the track, and when the car passes over a contact a dot is formed on the paper, thus giving an exact record of its passage, and the time can be measured by comparing with the set of chronometer dots. Upon the data which are thus obtained Sig. Canovetti makes the necessary calculations for finding the air resistance and the laws which govern the latter.

After the experiments were made with different forms of flat planes, a new series of data were obtained by using a cone-shaped frame covered with canvas. First the cone was placed with the pointed end in front, and next the point was placed in the rear, in order to show the effect of the air resistance upon the body of an airship. These experiments have a close analogy to the researches which are made upon various forms of hulls of vessels in a naval testing basin. Another series of tests which are likely to be of great value are those which Sig. Canovetti is carrying out with the frame disposed as we find it in an aeroplane, in a flat or slightly inclined position, and this may throw some light upon the different conditions of balance and resistance which enter into this question.




Spring Frame or Buffer for Stopping the Car at the End of Its Course.

Frame stretched with wire net and held by coiled spring.




Car Running Backward.

Canovetti's car using a conical air-resistance piece (canvas-covered bag) coming to a stop on the spring mattress. Cone is small end foremost and bamboo frame toward rear.




Same But Running Forward.

Car having same conical bag now placed against the bamboo frame, with the large end foremost.



Canovetti's Car on Down Grade to Test the Air Resistance.

The experimental bamboo frame is partly covered with canvas. In front is a separate conical canvas frame or bag for other tests.



Canovetti's Experimental Car Used on Inclined Track, Running on Rails for Air-Resistance Tests.

On the bamboo frame in front is stretched more or less canvas for different air resistances. Other shapes are used as seen in the illustrations, especially a conical shape, useful for gathering airship data.

CANOVETTI'S AIR-RESISTANCE EXPERIMENTS.

SOME NEW AND USEFUL ELECTRIC HAND TOOLS.

BY A. FREDERICK COLLINS.


It is generally acknowledged abroad, according to Consul J. I. Brittan, of Kehl, Germany, that the Americans excel their foreign competitors in the manufacture of machine tools, due chiefly to their thorough knowledge of the industry and their aptness in meeting every possible requirement.

The above statement is fittingly justified by a new branch of the business, namely, that of building portable hand tools driven by electricity. There are several companies in the United States that have given special attention to the manufacture of these devices, some of which are illustrated on this page.

One company's latest development along this line includes an electrically driven bench drill suitable for small works, a portable electric breast drill and an electric buffing and grinding outfit for household use. The bench drill has been especially designed for the use of jewelers, chauffeurs, repair men, and manufacturers who have a large amount of drilling on small work and in other places where the drilling service is not too heavy and severe.

Machine and general repair shop men, as well as manufacturers, are becoming better informed and more convinced of the advantages of the electric motor for driving their machinery, and realize that the saving of both time and money are possible in just those operations for which the electric bench drill is designed. The bench drill shown herewith is furnished with a vertical motor mounted

to No. 40. The bearings are provided with self-oiling cups which require attention only every three or four months. The outfit includes a chuck of standard design, ten feet of attaching cord and an Edison plug.




Electrical Tool-Post Grinder.

able electric hand-driven tools, including a number of grinding outfits for both external and internal work, radial and hand drills. The electrical tool-post grinder which we illustrate covers a wide range of work and is useful for grinding centers, cutters, reamers, dies, rolls, and the like, as well as for surface, parallel, and internal grinding jobs of all kinds.

The shank of the grinder is clamped in the tool-post of the lathe, the motor carrying on its shaft the emery wheel so that it may be set at any desired angle, in which case the wheel is moved across the face of the center to be ground by means of the handle, as the shank may be set in the tool-post of a planer, shaper, or milling machine, or it can be clamped in an ordinary bench vise. A flexible cord and attachment plug are connected and on securing the plug into any incandescent lamp socket it is ready for work.

These portable grinders are usually wound for 110 or 220 volts direct current, though in special cases they are wound for 50 to 250 volts and also for alternating current. All parts of the motor are inclosed, making it dust-proof; the spindle carries taper cone bearings and the wear may be taken up by means of a unit on the rear end of the spindle, these being also provided with dust-proof caps. A V slide having a 3-inch travel by means of a worm through the handle A is fitted with a gib to take up the wear.

The shank B is of steel and is fitted to the hole in the V cap; it is held in position with a screw clamp so that different sized shanks can be used. The extension mandrel C is



The Portable Breast Drill Motor.

on top of a column sliding in a socket cast integrally with the base, in which it can be adjusted for various heights. The motor body or head is also adjusted radially for drilling positions.

The whole outfit rests on a broad base 6 x 10 inches which gives it the necessary stability. The minimum height is 16 inches when the motor arm is in the lowest position and the maximum height is 22 inches when the arm is fully raised; thus giving a range of 6 inches through which the motor body may be raised or lowered. The work is fed to the drill by raising the circular table, which is operated by a lever within a range of 1 1/4 inches vertically. The motor is series wound and can be supplied with 115 or 230 volt winding, for use on direct-current circuit only. A single gear reduction is provided between the armature shaft and drill spindle. The hand wheel mounted on the armature shaft at the top is convenient for turning the spindle and adds a fly-wheel effect to the spindle as well, giving a smooth and steady rotation to the drill. The amount of power required for the operation of the drill naturally varies with the work performed, but in no case is it excessive. The largest drill the chuck will hold is 21/64 inch in diameter and from this all sizes down

The weight of the bench drill complete is about 40 pounds, enough to insure firmness and rigidity.

The new domestic grinding and buffing outfit illustrated has been put on the market especially for grinding knives, scissors, and other small edged tools, and for polishing silverware, jewelry, and other like articles. A grinding wheel of suitable character to insure a smooth cutting edge without the use of a sharpening tool is interchangeable with the buffing wheel. These outfits are adapted for the intermittent service required in the ordinary household but are not suitable for the heavier continuous work required by jewelers and dentists.

The household outfit consists of a motor with shaft extending two inches from the end of the bearing to the inside of the wheel, the necessary washers and nuts for holding the wheel in place, one rag wheel 3 1/2 inches in diameter, one 3-inch emery wheel 1/2 inch thick, together with attaching plug and cord. These outfits are furnished for 110-volt direct or alternating current and can be especially wound to 220 volts.

The alternating-current motor weighs about 25 pounds, while the direct-current motor is much lighter, weighing but 15 pounds. Both motors are very simple, requiring no more attention than a fan motor. In connecting with a source of current supply the cord is attached to the binding post of the motor and the plug inserted in the nearest socket at which the proper current is available.

A Cincinnati company builds a number of port-



Grinding and Buffing Motor in Use.



Portable Electric Bench Drill in Use.



Method of Using Buffing and Grinding Motor.

used for internal grinding by removing the regular wheel and screwing the mandrel to the spindle. A tool-rest D is a valuable attachment, serving as an index for grinding cutters, reamers, etc.; this detachable tooth-rest insures that each tooth of the cutter will be ground correctly.

Where the grinder is set in a lathe for internal grinding the larger wheel is removed and the extension mandrel is screwed to the spindle in its place. The mandrel C will grind a hole from 3/8 to 1 1/2 inch in diameter. The grinder may be set in a milling machine and the cutter ground without removing it and the tooth-rest D may be used for indexing as previously indicated.

Attached to the tool-post of a planer it is invaluable for grinding surfaces and for heavy parallel grinding, such as rolls, journals, bushings, and all kinds of hardened work. Heavier grinders operating on 1/4, 1/2, 1, and 2 horsepower are also constructed. In these latter types the bases of the angle plates are bolted in the tool-post rest of the lathe and it has a vertical adjustment to bring it in line with the centers.

A labor-saving hand and breast drill shown in one of the cuts is useful for drilling holes in wood or metal. It

is designed to be used wherever the old style hand drill can be used, and not only does it save the strength of the operator but it does the work many times more rapidly, for it is driven continuously and at a much higher speed. The motor is provided with a switch to start and stop it, so that it is absolutely under control at all times, and as the switch is located near the vertical handle it is within easy reach of the index finger. The chuck spindle is so arranged as to allow drilling on a line with the base of the motor and by this arrangement angle and corner drilling are possible.

The drill shown in the cut has two speeds operated by means of the lever on the front end of the motor and with this useful arrangement a slow speed for large drills may be used or a faster speed for smaller ones. These electrically driven tools are without doubt the most powerful and compact machine tools ever built and their extremely light weight makes them especially desirable for all classes of small work.

LEATHER GOODS MADE OF HUMAN SKIN.

BY M. GLEN FLING.

It is a fact well known to a very few skilled workmen, and not known at all to the world at large, that human skin can be prepared, tanned, and made into durable articles quite as successfully as can the skin of our four-footed friends. You can say over and over again to yourself that there is really no reason why human skin should not be so utilized, and you can be told by the workmen who handle it that there is nothing gruesome in the work; you can reason and argue with yourself about the matter, and try to be "matter-of-fact and sensible," and still there will be little shudders running through you and creeping up and down your spinal column at the thought of having the skin taken from a human body and made into some article of wearing apparel.

The only way to overcome this sensation, if you want to get over it, is to examine some of the articles made from the skin, and you will find that the leather is very much like dogskin or pigskin.

Mr. William Hansell, of Philadelphia, has the largest article which has ever been known to be made from human skin. He was particularly fortunate in getting enough of one grain, and succeeded only after a long and systematic search. The article is a beautiful pure white saddle, and any one examining it would be at a loss to tell the kind of skin from which it is made. When you are told, you realize that the pores which show have a familiar look; but when you are given a bit of the skin, of which Mr. Hansell has retained a few samples, you are amazed at the thickness. Three layers of skin you know you have, but knowing how easily a needle prick will draw blood, you are astonished to find what a good thick covering these three thicknesses make. This saddle is made from the skin of one man. A woman's skin, generally speaking, would be too delicate.

Now, it is not to be supposed that there is a general trade in human leather. Human skin is an exceedingly rare article. Sometimes a physician will have a piece, made into a cover for an instrument case, and occasionally medical students get enough to be made into a purse or a pair of slippers. Patients sometimes have a belt or a book cover or some such article made from a limb which has been amputated. It seems a peculiar mind that would take pleasure in "souvenirs" of this order.

The wearing public are not alone in their aversion to the use of human skin for the purposes to which they unhesitatingly put the hides of animals. It is very hard to get workmen to handle the "leather." Mr. Hansell gave his piece of skin, after it had been tanned, to an old workman who had always made up all his leather goods, and told him to make it into a saddle.

Three weeks the workman kept the skin, and one day he brought the partly finished saddle to Mr. Hansell with some question about finishing. "By the way, Hansell," he remarked as he was leaving, "I wish you would tell me what this skin is. It is the most contrary stuff I ever worked with; it's worse than pig or goat skin."


Very injudiciously Mr. Hansell informed him that it was human leather. At that the workman dropped the half-finished saddle, and left without a word. He never returned, and nothing would induce him to finish his job. Mr. Hansell, after waiting three months, hoping he would change his mind, turned the unfinished saddle over to another workman, but he took good care not to tell him what kind of leather the "contrary stuff" was.

The work of tanning human skin is pretty much the same as that of curing any other skin. Curiously enough, tattooing goes through the epidermis to the under skin, and not a little of the tanning of human skin is done for the purpose of preserving the designs

tattooed upon it. Human skin may, however, be tanned with the hair on it, in which case the epidermis is not removed. Scalps so tanned are said to make the best wigs known, and because the tanning is done with alum instead of with oils, as is the case with furs and most of the hair-covered skins of commerce, the resulting leather is much more durable.

HUGE BOWLERS RAISED BY BUCKET DREDGES.

The dredging operations which G. S. Mayes is carrying out for the Dominion government in Sand Point slip




A SADDLE OF TANNED HUMAN SKIN.

of the west side of St. John harbor are presenting difficulties which it is safe to say were not altogether anticipated by the contractor when the work was started.

From a spot to the north of berth No. 2 an area 600 feet wide and extending northwest toward the junction between North Rodney Wharf and Union Street, has been found to consist of immense boulders varying in weight from nearly 100 tons downward. Firmly imbedded in the mud, which in places covers them to a depth of 40 feet, the rocks have proved extremely difficult to handle, and the time spent in enabling the dipper of the dredge "Beaver" to obtain a correct balance beneath one of the giants frequently runs to hours.

The picture showing a boulder being raised in the dredge's bucket gives a good idea of the work. The boulder weighs about 30 tons, and when raised to the surface was found to be lodged endways in the bucket, and jammed so that it could not be removed without considerable delay and trouble. The bucket, it may be



THIS BIG BOWLER, WEIGHING 30 TONS, WAS DREDGED FROM THE HARDPAN IN 60 FEET OF WATER IN ST. JOHN HARBOR, NEW BRUNSWICK.

mentioned, is 6 feet 2 inches in diameter and is 9 feet 2 inches at its deepest part.

But this boulder was greatly exceeded by one measuring 12½ by 12 by 7½ feet and weighing about 92 tons, which was raised by the same means. It was dug at a depth of 60 feet below high-water mark. The dredge was then moved, with the stone in the bucket, about 150 feet, when the stone was deposited.

In the prosecution of the work the greatest difficulty has been found in digging out or unearthing of these boulders, as the material they are found in is marl or

hardpan, which is next to impossible to dig. The work has involved the destruction of ten large spuds or anchors, 80 feet long, 38 inches square, incased in heavy iron, as well as the breaking of three heavy steel dip-pers and three 16-ton dipper handles. The main engines of the dredge are two 24 x 24 cylinders geared up to 1 to 14, so that tremendous power is exerted to remove the boulders, bedded as they are in such tough material. Another great difficulty is that the abnormal rise and fall of the tide, which frequently reaches 29 feet, makes it difficult to carry on the work at high and low water.

Effect of Duration of Stress on Strength and Stiffness of Wood.

It has been established that a wooden beam which for a short period will sustain safely a certain load, may break eventually if the load remains. For instance, wooden beams have been known to break after fifteen months under a constant load of but sixty per cent of that required to break them in an ordinary short test. There is but little definite and systematic knowledge of the influence of the time element on the behavior of wood under stress. This relation of the duration of the stress to the strength and stiffness of wood is now being studied by the Forest Service of the United States Department of Agriculture at its timber-testing stations at Yale and Purdue universities. The investigation should determine: The effect of a constant load on strength; the effect of impact load or sudden shock; the effect of different speeds of the testing machine used in the ordinary tests of timber under gradually increasing load; and the effect of long-continued vibration.

To determine the effect of constant load on the strength of wood, a special apparatus has been devised by which tests on a series of five beams may be carried on simultaneously. These beams are 2 by 2 inches in section and 36 inches in length, each under a different load. Their deflections and breaking points are automatically recorded upon a drum which requires thirty days for one rotation. The results of these tests extending over long periods of time may be compared with those on ordinary testing machines, and in this way safe constants, or "dead" loads, for certain timbers may be determined as to breaking strength or limited deflections. The experiments of the Forest Service show that the effects of impact and gradually applied loads are different, provided that the stress applied by either method is within the elastic limit of the piece under test. For example, a stick will bend twice as far without showing loss of elasticity under impact, or when the load is applied by a blow, as it will under the gradually increasing pressure ordinarily used in testing. The experiments are being extended to determine the relations between strength under impact and gradual loads.

Bending and compression tests to determine the effect of the speed of application of load on the strength and stiffness of wood have already been made at the Yale laboratory. The bending tests were made at speeds of deflection varying from 2.3 inches per minute to 0.0045, and required from twenty seconds to six hours for each test. The woods used were longleaf pine, red spruce, and chestnut, both soaked and kiln-dried. From the results are obtained comparable records for difference in speeds in application of load. A multiplication of the results of any test at any speed by the proper reduction factor, derived from these experiments, will give equivalent values at standard speed. The tests also show concretely the variation of strength due to variations of speed liable to occur during the test itself. The results plotted on cross-section paper give a remarkably even curve as an expression of the relation of strength to speed of application of load, and show much greater strength at the higher speeds.

It is common belief among polemen that the continual vibrations to which telephone poles are subjected, take the life out of the wood and render it brash and weak. Nothing is definitely known as to the truth or falsity of this idea. Tests will be undertaken to determine the effect of constant vibration on the strength of wood.

During 1905 the oilfields of the United States produced 134,717,580 barrels of petroleum, as against 117,080,960 barrels in 1904. The production was greater by 17,000,000 than that of any previous year. It is significant, however, that the value of the 1905 products was \$17,000,000 less than that of 1904. The largest quantity of oil produced by any State in the Union is to the credit of California, which produced 33,427,473 barrels of oil in 1905, or 24.81 per cent of the total output. Next comes Texas, with 28,136,189 barrels or 20.89 per cent of the total, and third Ohio, with 16,346,660 barrels, or 12.13 per cent of the whole.

RECENTLY PATENTED INVENTIONS.

Electrical Devices.

PRINTING-TELEGRAPH.—J. D. WHITE, 50 Clanciarde Gardens, London, England. The object of this invention is to provide a "compound selective relay" for use in connection with an apparatus like that described in the specification of Mr. White in his former United States patent, so that the various local circuits which control the mechanism may be operated by a main circuit in such a way that messages transmitted along that circuit from an ordinary Morse or similar transmitter may be printed automatically in the proper characters at the receiving end.

Of Interest to Farmers.

GROOVING AND DITCHING PLOW.—W. M. BENSON, Newport, Pa. The purpose of the inventor is to provide a tandem gang grooving-plow, particularly adapted for use in semi-arid land, and to so construct the implement that the plows are set tandem or one directly behind the other, each consecutive plow-point being set deeper in the furrow than the preceding one for the purpose of producing a deep groove at one operation, and wherein also the plow-points are of graduated width, the lowest one being narrowest, the uppermost the widest.

FENCE-POST.—M. C. WIX, Milburn, Ky. Definitely stated, the invention has to do with the strand or fence wire fastening means, the object being to provide means of the character stated which shall not only facilitate securing of the strand-wires to the posts, but provide inexpensive and ready means for effecting the securing of the strand-wires to the posts.

PLOW OR CULTIVATOR.—W. T. GEORGE, Fayetteville, Tenn. The object of the improvement is to enable the distance between the shovels of the plow to be adjusted in a transverse direction with respect to the direction of advance of the implement, and, further, to provide an arrangement which will enable the degree of advance of certain shovels with respect to the others to be adjusted.

WEEDING AND CULTIVATING DEVICE.—T. J. KING, New York, N. Y. In this case the invention pertains to improvements in devices for extracting weeds, plants, and the like from the ground, the object being to provide a device of this character by means of which weeds or the like may be readily drawn from the ground with but little manual labor.

FERTILIZER-DISTRIBUTOR.—H. T. YOUNG, Florence, S. C. The center of revolution of the wheels being eccentric to that of the sleeves, the knives are projected upon one side of the cylinder and retracted upon the opposite. By adjusting the collars circumferentially of the shaft the commencement of point of projection of knives may be varied. Edges of the knives in passage beneath the hopper follow the outline of the bottom thereof and remove a thin layer of fertilizer, and continued revolution of cylinder drops fertilizer on the ground. After dropping it the knives begin to retract into the cylinder thus cleaning themselves from the fertilizer. A continuous layer is spread, of a width equal to the cylinder's width.

Of General Interest.

SHIP FOR CARRYING LIQUID CARGOES IN BULK.—C. E. BURNLEY, Newport News, Va. The invention is an improvement in ships for carrying petroleum or other liquid cargoes in bulk. It is steady in a seaway, operating on the same principle technically known as "winging the weights," which consists in removing weights on board of a ship from the center line out to the sides, causing her to be steadier and roll more easily.

COMPOUND CONDIMENT-HOLDER.—L. B. PARKER, Sulphur, Ind. Ter. The inventor has for objects the production of a device in which the caps of the shakers or distributors adapted to contain salt and pepper and other condiments can be readily removed and replaced and the perforations therein remain in a free and open state by the action of means carried by a closure-lid operable to close that shaker not in use.

APPARATUS FOR SMOKING MEAT.—C. SCHMITT, New York, N. Y. One purpose of the invention is to provide for a perfect combustion of the gas, and, further, means for heating and for producing smoke entirely independent of the chamber in which the articles are placed for smoking and cooking, thus preventing them from absorbing the odors peculiar to gas when burning, and also preventing the deposit of carbon on the products, which occurs at times under ordinary conditions.

SPEED-INDICATOR.—W. C. PLANK, Las Flores, Mexico. The object of this invention is to overcome the difficulty of taking the speed of shafts by producing an indicator in which there will be no danger of the spindle communicating its movement to the indicator-dial until such time as desired by the user. This is done by making the spindle in two sections, which are adapted to be automatically connected by pressing the indicator forward.

ATTACHMENT FOR MOUTHPIECES OF TELEPHONE-TRANSMITTERS.—W. C. PLANK, Las Flores, Mexico. The mouthpiece of a transmitter through constant use becomes foul and unsanitary. The invention consists of numer-

ous concentric removable linings of antiseptic paper so molded as to properly fit the mouth-piece and fastened therein and which is adapted to be readily removed sheet by sheet as the inner sheet becomes soiled or unsanitary.

Hardware.

NUT-LOCK.—W. S. MASON, La Salle, Ill. The device may be employed with nuts of square, hexagonal, or other shape. An object of the invention is to provide a lock which will securely hold the nut upon the bolt against accidental displacement or loss, and which may easily and quickly be placed in position or removed.

ECCENTRIC CUTTING-BIT.—J. H. TOMBRAGEL and J. F. SCHUNDER, Covington, Ky. The invention relates to bits used in boring holes in wood or metal; and one object of the improvement is to provide novel details of construction for a bit of the character indicated which is easily adjusted, enabling the lateral adjustment of the bit to the axis of its shank, whereby the bit will bore a hole of any desired diameter and depth within its capacity.

Household Utilities.

IRONING-BOARD.—L. C. KRANS, East Greenwich, R. I. In the present patent the invention relates to ironing-boards, such as used in laundries for ironing clothes; and the object of the improvement is to produce an ironing-board which can be quickly set up in position, which will maintain itself rigidly in position when erected, and which will normally be folded into small space when not in use.

Heating and Lighting.

WATER-HEATER.—J. A. FREY, Washington, D. C. This portable heater is adapted to be connected with a source of water-supply and is provided with an eduction-pipe by which water which has circulated through the apparatus and become heated may be drawn off. The heating is effected very rapidly and economically by a kerosene or other burner. There are improvements in the heater proper or interior part through which the water circulates, and in connecting parts, comprising the casing, the flame-deflector, and supports thereof.

Machines and Mechanical Devices.

CRYPTOGRAPHIC MACHINE.—H. BURG, Molkirch, near Rosheim, Germany. The invention is applicable to all type-writing machines in which the type are carried by a circle, even when they are mounted on type-bars or movable levers, and, indeed, all that need be done is to render movable the type-carrying circle and to connect the same with a mechanism of a kind to produce a predetermined series of various motions of said circle or a cylinder in order to obtain the discrepancy between the types marked on the keys struck and the types printed.

FILTER FOR DEFECTION.—R. M. VILLARINO, Campechuela, Cuba. A tank is employed for containing molasses or other syrup to be defecated and within which are disposed stirrers for the molasses in connection with shafts, means being employed for revolving the same in opposite directions. Means regulate the speed of each of the shafts, and further means clean the structure, and still further means are associated with the tank for receiving the overflow and which may be caused to return to the tank at will, said named means embodying a valve-controlled discharge-pipe for lees or sediment collecting therein.

Prime Movers and Their Accessories.

MUFFLER AND WHISTLE DEVICE.—M. ZWICKL, New Durham, N. J. This device is especially useful for small water-craft propelled by explosion-engines. Such water-craft must use a whistle for signaling purposes, and these are commonly blown by compressed air. The use of this air has a serious disadvantage, in that there is no visible signal when the whistle is blown, so that navigators of other craft have difficulty in locating the signal. The object is to produce a device adapted to be used in connection with an explosion-engine which will enable the steam-whistle to be over-acted when desired.

STOP MECHANISM FOR STEAM-ENGINES.—A. A. FULLER and D. K. CARTER, Jasper, Ala. The invention is in the nature of a stop device for at will throwing a Corliss steam-engine or other engine out of gear from any part of a plant or by the automatic action of its governor when racing or running wild. It consists of the novel construction and arrangement of electromagnetic tripping devices and their connection with the valve-gear.

Railways and Their Accessories.

MINE-CAR.—C. A. KELLER, Rosedale, Ind. The object in this improvement is to produce a car adapted to be used for transporting the material mined and constructed so as to facilitate automatic dumping of the material carried; at the same time the car is made so as to enable the same to be readily adapted for carrying dirt or similar material which is to be shoveled from the car.

CAR-STAKE.—R. L. EDWARDS, Perry, Oklahoma Ter. The invention refers to car-stakes

such as used at the sides of freight-cars employed for carrying lumber or logs. The object is to produce a stake having a mounting which will permit it to be readily adjusted into an erect position, but which will enable it to be quickly folded down in an inoperative position.

AIR-BRAKE SYSTEM.—W. H. EICHELBERGER, Royalton, Pa. The improvement provides a reliable safety attachment for the weakest point of an air-braking system—that is, the coupling between the sections—and that the attachment is operative under any abnormal condition which may be present. To prevent dragging of chains when the cars are uncoupled, they may be attached by any suitable means to the free end of the hose.

Designs.

DESIGN FOR A COVER-DISH.—R. L. JOHNSON, Stoke-upon-Trent, Staffordshire, England. In this ornamental design the cover-dish is of oval form. From the cover handle down to the edge of the cover the slope is gradual, varied, and pleasing. There is a gracefully scrolled handle at each end of the body of the dish. The body lines show a beautiful curve from the top to the base.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.



HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication. References to former articles or answers should give date of paper and page or number of question. Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn. Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same. Special Written Information on matters of personal rather than general interest cannot be expected without remuneration. Scientific American Supplements referred to may be had at the office. Price 10 cents each. Books referred to promptly supplied on receipt of price. Minerals sent for examination should be distinctly marked or labeled.

(10383) B. W. N. asks for information concerning transfer ornamenting. A. There are many different ways of putting on the ornament, some preferring one way, others a different method, according to circumstances and individual skill. We shall endeavor to give the most simple and successful method known. First, let it be understood that all pictures that show the colors complete are only suitable for white or very light colored brown; those that are covered with a white grounding, gold, metal, or silver leaf, can be used on any color, light or dark. After getting the work ready for ornamenting, give the picture a smooth, thin coat of some quick-drying copal varnish, thinned with turpentine (other preparations are used of which we will speak hereafter), being careful not to go beyond the outline of the design. Allow it to dry until it has a good tack, and put it on the work in its proper place. Roll it smooth with an India-rubber roller, or smooth it with a paper folder, until every part adheres well. (For very large pieces, it is well to lay them, after they have the right tack, between two sheets of damp blotting paper. It will stretch the paper and make a smooth transfer.) Now wet the paper, smoothing it down at the same time, until it has absorbed all the water possible; leave it about a minute, and pull off the paper carefully. Should any parts of the design still adhere to the paper, press it down again, wet-rub it until it separates easily. After having removed the paper, press the design on well and wash and dry it off. Should any blisters appear, prick them with a pin and press down. In a few hours the design may be varnished, which will increase the brilliancy of the colors. An improved method has been introduced which saves time and works with more certainty. The design is coated with a transfer cement of his own manufacture, without regard to outline, transferred as usual, and the traces of the cement around the design washed off, with the detergent (also his own invention), which will remove every particle of cement without injuring the colors or gold in the least. A few drops poured on a sponge or chamois skin are sufficient. For fine ornaments, having many fine lines and touches, it is necessary to use these preparations to make a neat job.

(10384) G. E. D. asks how to wind a small 75-watt dynamo to run same as a motor on a 110-volt direct current. How to reduce a voltage of 110 direct current to one of 20 volts most advantageously and in the simplest manner in order to run a motor wound for only 20 volts in circuit with a 110-volt current. A seventy-five watts are a tenth of a horse-power. We do not know where the winding for so small a dynamo can be found. The nearest we can come is a machine with a sixth horse-power. This is in Poole's "De-

signs of Small Dynamos," price \$2. We cannot give you directions for reducing a 110-volt current to 20 volts, without knowing the amperes also which flow. You can do the calculating as well as we. Divide 90, the rest of the voltage, by the number of amperes. The quotient will be the ohms of wire to be used. A small iron wire will be a proper one for the resistance.

(10385) G. G. asks: 1. Is there a paper on the market which, when damaged, will be discolored by the passage through it of a mild electric current, such, for instance, as would be generated by five dry cells? A. Perhaps a paper for determining the pole of a circuit can be purchased. If not, it may be made as follows: Dissolve one part of phenolphthalein in ten parts of alcohol, and add 100 parts of distilled water. Soak blotting paper in this and dry it. Then soak again in a 20 per cent solution of sodium sulphate in water and dry again. To use this moisten a piece of the paper in water and apply the wires to it. The space around the negative pole turns a bright red. 2. Is there any harmless chemical preparation which would cause paper dampened in it to take a dark color by the passage through it of such a current? A. Dissolve some potassium iodide in water, add starch and bring to a boil. Soak paper in this, and while damp apply the wires as before. A dark color is formed around the positive wire. By moistening the paper of No. 1 with the starch solution two colors would be formed.

INDEX OF INVENTIONS

For which Letters Patent of the
United States were Issued
for the Week Ending

February 12, 1907.

AND EACH BEARING THAT DATE

(See note at end of list about copies of these patents.)

Abrading, A. H. Radell	844,046
Acousticons, connection for, H. W. Hall	843,890
Advertising, etc., apparatus for, Gilman & Kendall	843,889
Aeronautical machine, A. McCarthy	844,172
Agricultural implement, E. Vol. Fielder	843,741
Air brake attachment, G. Emery	843,270
Air brake system, G. Macloskie	843,758
Air compressor, A. McCarthy	844,173
Alarm, C. Mahla	843,904
Alarm for gages, clocks, etc., A. Charland	843,929
Amusement device, A. Francovich	844,116
Annealing and bluing furnace, continuous, T. J. Costello	844,101
Armature, attachment for motor, J. W. McManiman	843,836
Atmosphere regulating system, Peters & Hunsberger	843,909
Auger, combination, M. Lingel	843,832
Auger, earth, T. M. McWhorter	843,741
Automatic alarm, P. Bourne	844,241
Automatic switch, A. N. Bradley	843,575
Automatically operated shovel, F. Ernst	843,784
Automobile gearing, D. D. Culver	843,796
Automobiles, reversing and change speed gear for, C. W. Duer	843,589
Axle box, W. F. Grattis	844,122
Axletree, J. A. Lease	844,029
Back pedaling brake, C. A. Penn	843,583
Bag fastener, Erickson & Heilmann	843,934
Baggage coupon check, excess, F. H. Crump	844,102
Ball for cooking utensils, Bowman & McIntosh	843,863
Balance wheels, posing and truing tool for, J. S. Kirstein	843,754
Balers, power attachment for hay, L. A. Ryther	843,631
Baling press, J. J. Stopple	844,053
Baling press, C. E. Wehrenberg	844,068
Baling press, J. M. De Coster	844,258
Baling press feed mechanism, G. V. Davis	844,103
Bath tub waste fitting, J. W. Sharp, Jr.	843,968
Bearing, box, R. J. Heafors	843,601
Bearing, sprag, R. J. Edwards	843,591
Boring machine, G. F. Pross	843,910
Bin, See Coal bin.	
Blast furnace, S. A. Kennedy	843,950
Blind adjuster, L. L. Garside	844,118
Blind and the like, window, D. I. Andrews	843,922
Block, Grainger & Klepsch	844,123
Boiler flue cleaner, J. P. Thompson	843,976
Boilers, furnace door for, F. L. Fox	843,742
Book, loose leaf memorandum, E. C. Suckert	843,714
Bookbinder, R. J. Nicholson, release	842,606
Boat and shoe machinery, J. Northern	843,839
Boat and shoe tree leg, G. E. Finquist	843,673
Boring machine, A. Collet	844,099
Bottle capping machine, G. Kirkegaard	844,144
Bottle indicator, medicine, A. R. Swope	844,054
Brace block, Kamerzel & Schofield	843,948
Bracelet, T. D. Ciguere	843,888
Braids and trimmings, machine for making, J. E. Kirberg	844,027
Brake beam fulcrums, forming, F. W. Baumann	843,659
Brake control system, L. A. Hawkins	843,749
Brake operating mechanism, R. H. Nichol	844,038
Brick press, hand, H. B. Murdock	844,104
Brush cutting machine, T. B. Hendricks	843,604
Brush, fountain, R. H. McDowell	843,999
Brush, fountain, R. Curcio	843,256
Brush, sink, C. A. Fogarty	843,596
Buckets, soap and brush holder for, H. F. & F. E. Neumeyer	844,177
Buckle, attachable stitchless, M. Barabasz	844,082
Buckle, cross line, H. H. Pijan	844,184
Buggy top rest, P. D. Hickerson	843,677
Building construction, E. J. Winslow	844,294 to 844,296
Building, metal, H. Niesen	844,179
Burglar alarm, C. W. Kuen	843,614
Burning liquid fuel in conjunction with steam, apparatus for, F. Cotton	844,004
Burnishing machine, Haubert & Olsen	844,019
Bust supporter, J. Bree	844,242
Butchers' blocks, machine for surfacing, D. R. Ingram	844,022
Button blanks from shells, cutting, A. P. Wallace	844,064
Cable hanger, E. H. Skinner	844,200
Calculating device, R. L. Hubbard	843,944
Calculating machine, N. J. Goldfarb	844,120
Camera, W. J. Little	844,152
Can closure, G. H. Dunbar	844,108
Can opener, F. C. Smalstig	844,202
Candle holder, O. Kampfe	844,136
Canning operations, apparatus employed in, M. J. Hawkins	843,893
Caustic solutions and the regeneration of rubber waste, production of aqueous, P. Alexander	844,077
Car, child's hand, J. F. Vogel	843,646
Car coupling, W. N. Hensley	843,605
Car coupling, S. W. Wibel, et al.	843,858
Car door, Vorhes & Crisman	843,647

31 Years of Success THE PRUDENTIAL


Foremost in Public Usefulness, Security and Public Confidence

Thirty-first Annual Statement, January 1, 1907, shows:

ASSETS, over	- - - - -	127 Million Dollars
LIABILITIES (including Reserve over \$103,000,000) nearly	- - -	107 Million Dollars
CAPITAL STOCK, - - - - -	- - -	2 Million Dollars
SURPLUS (largely for ultimate payment of dividends to Policyholders), over	- - -	18 Million Dollars
INCREASE IN ASSETS, nearly - - - - -	- - -	20 Million Dollars
PAID POLICYHOLDERS DURING 1906 over - - - - -	- - -	16 Million Dollars
INCREASE IN AMOUNT PAID POLICYHOLDERS 1906 over 1905, over	- - -	2 Million Dollars
TOTAL PAYMENTS TO POLICYHOLDERS to Dec. 31, 1906, over	- - -	123 Million Dollars
CASH DIVIDENDS AND OTHER CONCESSIONS Not Stipulated in Original Contracts and Voluntarily Given to Holders of Old Policies to date, nearly - - - - -	- - -	7½ Million Dollars
LOANS TO POLICYHOLDERS ON SECURITY OF THEIR POLICIES, nearly - - - - -	- - -	5 Million Dollars
NUMBER OF POLICIES IN FORCE, nearly - - - - -	- - -	7 Million
NET INCREASE IN INSURANCE IN FORCE, over - - - - -	- - -	82 Million Dollars

Bringing Total Amount of Insurance in Force to over

One Billion, Two Hundred and Fifty Million Dollars.



The Year's Record Shows:

Efficient, Economical Administration.

Increased Payments to Policy Holder for Death Claims and Dividends.

Large Saving in Expenses.

Lower Expense Rate than Ever Before.

Reduction of Expense Rate in Industrial Department nearly 3½% of Premium Income.

Favorable Mortality Experience.

The business operations of The Prudential are confined to the United States and strictly limited to selected lives.

DIVIDENDS TO POLICYHOLDERS DURING 1906 OVER	= = =	\$1,250,000
DIVIDENDS PAYABLE TO POLICYHOLDERS DURING 1907 NEARLY		\$1,700,000

Many letters from Policyholders receiving Dividends demonstrates that the results more than meet the expectations of the Insured.

THE PRUDENTIAL INSURANCE CO. OF AMERICA

JOHN F. DRYDEN, President

Incorporated as a Stock Company by the State of New Jersey.

Home Office, Newark, N. J.

For Every \$100 of Liabilities The Prudential has \$119 of Securely Invested Assets

WRITE FOR INFORMATION OF POLICIES, DEPARTMENT 121.

"Star" Foot and Power Lathes

FOR FINE, ACCURATE WORK
Send for Catalogue B.
SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N. Y., U. S. A.

Engine and Foot Lathes
MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. BEST MATERIALS. BEST WORKMANSHIP. CATALOGUE FREE
SEBASTIAN LATHE CO., 120 Culvert St., Cincinnati, O.

Foot and Power and Turret Lathes, Planers, Shapers, and Drill Presses.
SHEPARD LATHE CO., 133 W. 2d St., Cincinnati, O.

Veeder Counters
to register reciprocating movements or revolutions. Cut full size.
Booklet Free
VEEDER MFG. CO., 18 Sargeant St., Hartford, Conn.
Cyclometers, Odometers, Tachometers, Counters and Fine Castings.

WORK SHOPS
of Wood and Metal Workers, without steam power, equipped with **BARNES' FOOT POWER MACHINERY** allow lower bids on jobs, and give greater profit on the work. Machines sent on trial if desired. Catalogue Free.
W. F. & JOHN BARNES CO., Established 1872.
1999 Ruby St., Rockford, Ill.

THE B. F. BARNES 14-INCH DRILL
is adapted for work from 1-16 inch to 3/4 inch. A strong, substantial, well built drill. Plain lever or power feed as desired. We build a full line of Drills. All sizes furnished in Gangs. Also have 9-inch, and 11-inch Screw Cutting Lathes, and a 24-inch Wet Tool Grinder. Catalogue on request.
B. F. BARNES COMPANY, Rockford, Ill.
European Branch, 149 Queen Victoria St., London, E. C.

Peninsular Marine Motors
Four-cycle spark ignition Automobile design. Are designed and built for high speed and steady all day running. They are practically indestructible, every part is interchangeable. Don't fail to get our catalogue before purchasing. 2 1/2 to 40 H. P. Prompt delivery guaranteed.
PENINSULAR MOTOR CO., 200 S. Front St., Grand Rapids, Mich.

A. M. Tiber.
Manufacture Established 1761.
Lead-Colored & Slate Pencils, Rubber Bands, Erasers, Inks, Penholders, Rulers, Water Colors, Improved Calculating Rules.
Send for descriptive Circular S.
44-60 East 23d Street, New York, N. Y.
Grand Prize, Highest Award, St. Louis, 1904.

ELECTRONS AND THE ELECTRONIC
Theory are discussed by **SIR OLIVER LODGE** in SCIENTIFIC AMERICAN SUPPLEMENTS 1428, 1429, 1430, 1431, 1432, 1433, 1434. Price 10 cents each, by mail. Munn & Company, 361 Broadway, New York City, and all newsdealers.

JAGER Marine 4-Cycle Engines
Skillfully designed and well built. Single lever control, combining automatic carburettor with spark advance. Develops wide speed range and reliability under most trying conditions. Sizes 3 to 60 h. p. Send for catalog.
CHAS. J. JAGER CO., 281 Franklin, cor. Battery March St., Boston, Mass.

THE EUREKA CLIP
The most useful article ever invented for the purpose. Indispensable to Lawyers, Editors, Students, Bankers, Insurance Companies and business men generally. Book marker and paper clip. Does not mutilate the paper. Can be used repeatedly. In boxes of 100 for 25c. To be had of all booksellers, stationers and notion dealers, or by mail on receipt of price. Sample card, by mail, free. Manufactured by **Consolidated Safety Pin Co., Box 121, Bloomfield, N. J.**

PIPE CUTTING AND THREADING MACHINE
For Either Hand or Power
This machine is the regular hand machine supplied with a power base, pinion, gear, etc., and can be worked as an ordinary power machine or taken from its base for use as a hand machine. Length of pipe up to 15 in. handled easily in small room. Illustrated catalogue—price list free on application.
THE CURTIS & CURTIS CO., 6 Garden St., Bridgeport, Conn., New York Office, 41 Centre St.

To Book Buyers
We have just issued a new 112-page catalogue of recently published Scientific and Mechanical Books, which we will mail free to any address on application.
MUNN & COMPANY
Publishers of SCIENTIFIC AMERICAN
361 Broadway, New York

Car door, grain, J. Johnson	844,024
Car door, grain, E. Schreiber	844,193
Car haul, C. W. Miller	844,161
Car haul, A. W. F. Steckel	844,201
Car, passenger, W. A. Jacobs	844,133
Car safety appliance, railway, J. T. Andrew	844,228
Car seat, J. A. Wolle	844,224
Car wheel, pit, Fownes & Gardner	843,883
Cars, automatic air brake coupling for, way, F. H. Rutherford	843,702
Carbonator, F. R. H. Thomas	843,778
Carousel, E. R. Olson	843,908
Carpet stretcher, J. Driver	844,107
Carpet sweeper, H. W. Ru Ton	843,770
Carrier. See Hay carrier	
Casting machine, W. A. McAdams	844,169
Catamenial sack, J. J. Shtuchka	844,198
Cattle guard, S. C. Kettner	843,752
Cement work, tool for, R. L. Sohn	844,204
Chain casting mold, J. Traut	843,977
Chain, elevator, E. R. Purdy	844,288
Chain, making, unwelded, S. K. von Eneghy	844,006
Chart for drafting garments, R. H. Blackburn	843,862
Chemical receptacle, Weiss & Harey	844,070
Cherry stoner, B. Mai	843,955
Chimney, J. V. Boland	844,297
Chimney stack base, J. Herrin	843,813
Chuck, W. S. Davenport	843,600
Chuck, Macleod & Rich	843,682
Chuck, drill, W. Borchert	844,091
Churn operating mechanism, W. I. Kersh	843,751
Cigar filler cutting machine, Bright & Davis	843,927
Cigarette shell, S. I. Prescott	843,923
Cistern cover, G. Ertel	843,801
Clamp, L. P. Imhoff	843,820
Clamp, R. Miller	844,309
Cleaning appliance, household, Dunn & Taylor	843,590
Clock controlled by reversals of electric current, M. Fischer	844,010
Clock for induction currents, electric sympathetic or secondary, M. Fischer	844,009
Clothes hanger, M. L. Schoonmaker	843,633
Clutch throwing mechanism, A. H. Fetter	844,273
Coal bin, J. A. Koch	843,895
Coating gilded surfaces, composition of matter for, J. A. Henry	843,812
Cock, gage, A. P. Prendergast	843,842
Coffee maker, A. E. White	843,727
Coffee separator, R. F. Cordero	844,253
Coil spring, J. B. Knudsen	843,827
Coiling spindle, J. W. Sommer	844,206
Coin counting machine, C. W. Johnson	844,308
Coin holding and delivering device, J. W. Meaker	844,282
Coin tray, J. W. Meaker	844,283
Collapsible box or can, W. C. Marshall	843,684
Collar and cuff, etc., folding machine, Clearwater & Temple	844,001
Collar supporter, Gaston & Moore	843,855
Coloring matter, azo, Kothe & Ossenebeck	843,756
Comb, A. Ehrlich	844,007
Comb fastener, J. L. Simpson	844,199
Computing machine, etc., key releasing mechanism for, D. W. Shiek	843,635
Concrete building construction, A. S. Reavis	843,768
Concrete walls, making, J. L. Given	843,937
Conveyer plant, H. H. Campbell	843,582
Conveyer, C. O. Gustavsen	843,076
Conveyer, pneumatic, C. L. Groves	843,068
Cooking utensil, A. H. Meyer	843,905
Cooler, L. H. Brinkman	843,864
Cores, producing laminar for transformer, W. A. Hall	843,747
Corn husking machine, H. H. Bursell	843,866
Corn knife, W. C. Heimerdinger	843,602
Cotter, T. F. McAndrews	844,170
Cotton chopper, W. M. Gibson	843,675
Cotton picker's vehicle, T. J. Merritt	844,031
Couch, convertible, A. Wheatley	843,780
Cow tail holder, N. A. Angel	843,657
Crane operating gearing, M. Troyer	844,058
Crate tilting device, N. J. Sherrill	843,708
Cream separator, centrifugal, E. W. Broomall	844,244
Crib, C. S. Bentley	844,233
Crusher. See Ice crusher	
Crushers and pulverizers, dumping cage for, M. F. Williams	843,729
Culinary system, chronometric, R. S. Woodward, Jr.	844,074
Cultivator, C. P. Michaelsen	844,163
Cultivator attachment, C. B. Clark	844,249
Cultivator, planter, and fertilizer distributor, combined, J. T. Wright	844,227
Cutter head, rotary, E. E. Shimer	844,197
Cutting board, H. Zimmerman	844,065
Cylinder wrench, C. T. Hara	843,693
Decoy, C. H. Ditto	843,588
Dental floss holder, C. M. Verbaugh	844,181
Dental matrix, E. Armstrong	844,079
Desk, B. L. Umberger	843,719
Desk furniture, school, J. A. Wilkinson	843,649
Detinning apparatus, M. Leitch	843,616
Dish for holding oranges, etc., H. F. Provance	844,287
Display holder for cards or similar articles, A. V. Groupe	844,279
Display rack, E. B. Weston	844,071
Display stand, knockdown, J. B. Warren	844,065
Distilling wood, C. S. Hammatt	843,599
Door and window locking device, J. Wittmann	843,730
Door check, screen, D. W. Anderson	844,078
Door holder, C. F. Ash	844,081
Door opening, closing, and locking device, sliding, J. F. Connell	844,251
Door securer, C. Scheer	844,191
Draft equalizer, G. B. Elliott	843,737
Draft gear for agricultural machines, J. Tilly	844,214
Drafting instrument, L. R. Loughborough	844,157
Drainage system clean out, Hoffman & Hever	844,020
Drier, W. F. Hutchinson	843,608
Drier, E. F. Cordero	844,252
Dumb waiter releasing device, J. H. Miller	843,618
Dust pan, E. R. Murray	844,168
Dye and making same, black azo, Hagemann & Stange	843,808
Dye and making same, greenish blue, H. Loretan	844,156
Egg testing machine, A. I. McTaggart	843,622
Electric furnace, E. R. Taylor	843,776
Electric heater, S. V. Tallafiero	843,775
Electric light bulb, E. E. Leberg	843,900
Electric machine, alternating current dynamo, C. P. Steinmetz	843,774
Electric motor starting device, A. C. King	843,753
Electric regulator, A. C. Carey	843,733
Electric switch, H. J. S. Lewis	843,901
Electric switch, J. C. Pinkerton	844,045
Electric switch, multiple, H. J. S. Lewis	843,902
Electric timing device, H. H. McIntire	843,621
Electrical conductors, connector or terminal for, J. McLaughlin	843,763
Electricity, neutralizing static, W. H. Chapman	844,300
Electrocapillary apparatus, Armstrong & Oring	844,050
Electromagnet, J. B. Washburn	843,919
Elevator boot, R. Munn	844,033
Elevator controlling apparatus, J. J. Westbrook	843,980
Embroidering machine, F. Gegauf	844,015
Enameling or glazing metallic and other surfaces, Atkinson & Smith	843,985
End cell switch, automatic, J. Bijur	844,090
Engine, C. H. Moore	843,619
Engine cylinder, internal combustion, H. P. Martin	843,759
Engine house smoke jack, F. P. Gutellus	843,941
Engine starting mechanism, explosive, P. Kane	843,611
Envelope machine, J. A. Sherman	843,707
Envelope machines, forming well and plunger for, B. Pahlitzsch	843,623
Erasor cleaning apparatus, blackboard, S. W. Long	844,154
Excavating apparatus, L. A. Desy	844,104
Eye exerciser, G. Bullock	843,603
Eyeglass connection, S. N. Stone	843,972
Faucet, Wares & Holman	844,065
Faucet, J. C. Wright	844,226
Feed bag, A. M. Schappa	843,967

HAYNES
WHY THE HAYNES IS FIRST

The Haynes factory was the first automobile factory to be built in America (1893).
The Haynes was the first to adopt low tension make-and-break ignition (1895).
The Haynes was the first to use nickel steel and aluminum alloy in a car.
The Haynes was the first to adopt Side entrance bodies and large wheels.
The Haynes is first to adopt the roller pinion and beveled sprocket direct drive, making possible the combination of shaft drive and high power.
The Haynes is first to establish a reputation for reliability.
The Model T Chassis on the car shown herewith is the same chassis that proved its merit in the Vanderbilt Cup race.
The Haynes is the Highest Powered Shaft Driven car built. The exclusive Sprocket and Roller Pinion Drive makes this possible.

The Haynes Standard 50 H. P. Touring Car for 1907, Model "T," the highest powered shaft driven car built. Price, \$3,500.00.

For full information and specifications, address Desk H 3.
HAYNES AUTOMOBILE CO., KOKOMO, IND.
Oldest Automobile Manufacturers in America. Members A. L. A. M.
NEW YORK, 1715 BROADWAY. CHICAGO, 1420 MICHIGAN AVENUE.

Wouldn't You Like to Own This 16 Shot Repeating Rifle? Only \$7.75

Hopkins & Allen .22 Caliber Repeater

The squirrels and rabbits can't get away from you when you carry this rifle. If you miss one, the first time—you have 15 more shots coming almost before he can move.

It makes a ramble in the forest a pleasure—productive of full game bags—and all the excitement of quick successful shots.

Description: This is the finest and most reliable repeating rifle ever offered at the price. It shoots 22 long or short or 22 long rifle cartridges—16 shots for shorts and 12 for long or long rifle—and the ejector works like lightning. You can deliver 12 or 16 shots (depending on the cartridge used) almost as quick as you can pull the trigger. THE GAME SIMPLY CANNOT GET AWAY.

Quick take-down pattern—full length 38 1/2 in. length of barrel 20 in.—weight 5 1/2 lbs. Has that excellent military bolt action—the first ever put on an American sporting rifle. HAS THE BEST SAFETY DEVICE—A SIMPLE TOUCH OF THE LEVER PREVENTS ACCIDENTAL DISCHARGE. HAS THE ONLY EJECTING DEVICE THAT WILL QUICKLY EMPTY THE MAGAZINE WITHOUT FIRING A CARTRIDGE. HAS MORE UNIQUE, DESIRABLE FEATURES THAN ANY OTHER 22 CALIBER REPEATER. Has beautifully polished walnut stock, military butt plate, every part drop forged—lock work made of spring steel. AN EXCELLENT RIFLE FOR FIELD, FOREST OR GALLERY PRACTICE—SURE TO GIVE SURPRISING PLEASURE TO ITS POSSESSOR.

PRICE—Safe delivery guaranteed—\$7.75—IF YOUR OWN DEALER CANNOT SUPPLY YOU.
We publish two delightful stories—"William Tell," the experience of an expert with his first Junior Rifle, and "My First Rifle," by the famous marksman, Capt. Jack O'Connell. WHICH WE WILL SEND FREE, with our illustrated catalogue of rifles, revolvers and shotguns.

HOPKINS & ALLEN ARMS CO., Dept. 138, Norwich, Conn., U. S. A.
London Office: 6 City Road, Finsbury Square, London, England.
The largest manufacturers of High Grade Shot Guns, Rifles and Revolvers in the World.

Do You Own An Automobile?

If you desire to keep in touch with motor topics, and gain many practical hints of value in everyday automobile operation, you should subscribe to **THE MOTOR CAR**. It is published monthly exclusively in the interests of people who ride for pleasure, and every number is worth the yearly subscription price to any motor enthusiast.

Subscription price \$1.00 per year. Single copies 10c. **THE MOTOR CAR** may be ordered through any news dealer.

SPECIAL OFFER.—Send us One Dollar now for a year's subscription and we will send you, free of charge, a gasoline tester in a neat pocket case. Will tell you every time whether or not you are getting the right kind of fuel.

Send us your subscription now—and subscribe for your friends at the same time.

W. G. PIERSON PUBLISHING CO.
108 Fulton Street New York

BECOME A CARTOONIST

An Illustrator, Designer, Mechanical, Architectural or Sheet Metal Pattern Draftsman. You incur no obligation by writing now for full information about the "Acme Way" of teaching by mail. "At it 8 years." State which course you prefer.

You can qualify at home in sparetime to earn \$25 a week. Men like McCutcheon, Briggs, Davenport, Outcalt, Kemble and others earn \$5,000 and upward a year.

We shape the course to meet your individual needs; develop you to the original work that enables artists to hold high salaries positions; guarantee proficiency to earnest students and secure positions when complete.

THE ACME, School of Drawing
A-478 Acme Building Kalamazoo, Mich.
Resident instructions if preferred

STEAM TURBINES. — THEIR CONSTRUCTION, Operation and Commercial Application.
SCIENTIFIC AMERICAN SUPPLEMENTS 1306, 1307, 1308, 1422, 1400, 1442, 1370, 1372. The articles have all been prepared by experts in steam engineering. Price 10 cents each, by mail. Munn & Co., 361 Broadway, New York City, and all newsdealers.

Porox Ignitor Storage Batteries
High-capacity! Light Weight!
The only American ignition accumulators put up in celluloid jars. They surpass in capacity, lightness and durability the imported French cells. 1500 miles on a single charge with a 4-cylinder car. We guarantee more mileage on a charge than any other make. Write for circular and price list.
Muller Porous Plate Accumulator Co.
295 West 41st Street, New York

The Perfection Power Block Machine

Makes Hollow Concrete Building Blocks. Perfect form, uniform size and quality. Concrete accurately measured, mixed by power under pressure over 100 tons.

Full Details, List of Machines in Operation, on Application.

THE PERFECTION BLOCK MACHINE CO.
321 Kasota Bld., Minneapolis, Minn.

DYNAMO AND MOTOR COMBINED.—Fully described and illustrated in SCIENTIFIC AMERICAN SUPPLEMENTS 844 and 865. The machines can be run either as dynamos or motors. Price 10 cents each, by mail. Munn & Company, 361 Broadway, New York City, and all newsdealers.

Palmer Gasoline Motors

Marine & Stationary
Over 20 sizes. 1/4 to 25 H. P. One, two and four cylinder. Two and four cycle. Jump and snap spark. 25,000 engines running. Catalogue FREE.

PALMER BROS.
Cos Cob, Conn.

Saving Energy

means much in these strenuous days. That is why **Telephone Service**

is so helpful in both home and office.

NEW YORK TELEPHONE CO.
15 Dey Street.

New Portable Gasoline

Submerged Propeller



The Lightest, Most Practical, Most Powerful.

EASIEST APPLIED.

Attached and Detached to ANY BOAT in a Moment. Can be raised and lowered to run in shallow water.

PERFECTLY SAFE.

Entire Outfit is Outside of Boat. **INEXPENSIVE.**

Introductory price to May 1, \$75.00.

SUBMERGED ELECTRIC MOTOR CO.
Menomonie, Wis.

ELECTRICAL APPARATUS REPRESENTED BY CONVENTIONAL DIAGRAMS IN DRAWINGS.—Fifty diagrams showing the usual method of illustrating electrical apparatus in drawings. A labor saving paper. Contained in SUPPLEMENT 1106. Price 10 cents. For sale by Munn & Co. and all newsdealers.



If you know the many good points of last year's model, you'll be all the more interested in this handsome car. It has greater simplicity, more power, better material, and a finer appearance. Wider wheel base, longer tread, one hand lever only, single nickel chain, standard tires and the JEWEL 2-cycle, single cylinder engine, giving full 8 H. P., with two speeds forward and reverse—4 to 30 miles an hour on the high gear.

Do you know all about the JEWEL motor? It's the greatest talking point any car ever possessed. For simplicity, economy and thorough reliability it has no equal to-day.

Write at once for full information.

THE FOREST CITY MOTOR CAR CO.
202 Walnut St., Massillon, O.



DURYEA AUTOS



Have One Hand Control. The only autos simple enough to be handled by a single hand. This proves their great simplicity. Get our leaflets.

DURYEA POWER CO., Aeyrud Street, Reading, Pa.

CRANK SHAFTS

LARGEST MANUFACTURERS

Write for prices, also on all other **DROP FORGINGS**

Detroit Forging Co., DETROIT, MICH., U.S.A.

How to Construct An Independent Interrupter

In SCIENTIFIC AMERICAN SUPPLEMENT, 1615, A. Frederick Collins describes fully and clearly with the help of good drawings how an independent multiple interrupter may be constructed for a large induction coil.

This article should be read in connection with Mr. Collins' article in SCIENTIFIC AMERICAN SUPPLEMENT, 1605, "How to Construct a 100-Mile Wireless Telegraph Outfit."

Each Supplement costs 10 cents; 20 cents for the two. Order from your newsdealer or from

MUNN & CO., 361 Broadway, New York

Feed regulator, G. Halliday	844,124
Feed water heater, M. K. Bowman	843,791
Feed water heater, Kieley & Mueller	844,026
Feed water regulator for boilers, automatic, J. E. Wallace	843,722
Feeder, boiler, J. F. Senter	843,706
Feeding and watering device, poultry, A. A. & G. F. Conrad	843,664
Feeding trough, stock, S. N. Boyd	843,792
Fence, Greene & Krepsky	843,744
Fence post making machine, G. Falk	844,306
Fiber dishes, machine for press forming, F. W. Waterman	843,854
Filter, W. Bodge	843,991
Finger shield, H. F. Huntley	843,819
Fire extinguishing apparatus release, H. Sandvoss	843,847
Fire hose is coupled to hydrants, device whereby, H. J. Page	843,963
Fire pot, A. G. Cripps	843,795
Fireproof chimney, Dauben & Ryan	843,797
Fireproofing textile materials, W. H. Perkins, Jr.	844,042
Fish parachute, F. J. Howard	843,946
Fishing boat, W. S. Pettis, Jr.	844,182
Fishing tackle, C. R. Willing	843,951
Fishing tackle, J. B. Harris	843,748
Floor covering, C. H. Bach	844,230
Floor polishing machine, P. Sass	843,966
Flooring, Helt & Smith	843,817
Flour purifier, aspirator, and bleacher, S. T. Wilson	843,783
Flue expander, J. P. Brown	843,869
Flue stop, W. Weller	843,855
Flushing device for rag engine vats, E. A. Peterson	843,965
Frame, See Hat frame	
Frame joint, E. G. Budd	844,245
Fruit packing device, dried, C. F. Fleming	844,275
Funnel, H. G. De Veaux	843,873
Furnace, A. Bergman	843,924
Furnace for obtaining zinc from zinc ores, Desgraz & Schmidt	843,872
Furniture fastening device, D. W. Tower	843,717
Furniture leg fastening device, N. Andersen	843,656
Fuse housing, K. Wieser	844,223
Fuse, non-arcing muffed, F. B. Cook	843,939
Fuse or electric cut-out, C. A. Steller, Jr.	843,852
Fuse, time, K. Wieser	844,222
Game board, A. Boswell	843,992
Gape worm extractor, J. S. Klock	843,951
Garbage can, F. Posthoff	844,185
Garment fastener, W. A. Nickless	844,178
Garment hanger and lock, J. C. Epler	844,305
Garter, G. H. Phelps	843,627
Garter, J. F. O'Brien	844,286
Garter or the like clasp, C. E. Schaffner	844,048
Gas burner for sad irons, R. Wundt	843,653
Gas engine, vertical, W. von Bechellhauser	844,040
Gas from crude oil, device for generating, M. G. Norton	843,692
Gas generating apparatus, G. M. S. Tait	843,715
Gas generator, acetylene, E. M. Rosenbluth	844,047
Gas producer, C. J. Atkinson	843,787
Gas producing apparatus, C. Ellis	843,669
Gas retort, G. A. Heckert	843,811
Gate lock, crossing, W. C. Smith	843,637
Gate mechanism, A. E. Miller	843,617
Gear, friction, W. J. Seitz	843,634
Gear, reeling, D. C. Jennings	843,822
Gear, variable speed, M. M. Smith	844,203
Gearing, changeable speed, E. A. Johnston	843,603
Gearing, elastic, L. F. Dieter	844,261
Glass grinding, smoothing, and polishing apparatus, plate, E. Bagnall, reissue	12,604
Glass plates, corner clamp for, L. Bartelstone	843,861
Glass press, E. C. Schrader	843,849
Glass, roller for drawing sheets of, E. Fourcault	844,115
Glass with or without an embedded strengthening structure, apparatus for making sheet, A. J. Baldwin	843,860
Glassware, manufacturing, L. A. Fletcher	843,594
Gold prospecting and mining device, R. Hornbeck	843,606
Governor, Hill & Purcell	844,129
Governor, Fraser & Nichols	843,803
Grader, L. W. Brophy	843,662
Grain binder, G. L. Phelps	843,626
Grain screen, Trace & Fifield	844,216
Grapple, E. Y. Moore	844,032
Grate, shaking, C. H. Langill	843,952
Grease cup, C. C. Martens	843,833
Grinding machine, J. T. Wheatman	843,725
Grinding machine, E. A. Peterson	843,964
Gun, air, Blomen & Ewerlof	843,573
Gun, air, F. F. Bennett	843,950
Gun, magazine, C. Hansen	844,017
Halter, compound twitch, C. McClintock	843,659
Ham for market, preparing, L. Burk	844,096
Handle attachment, L. Wojdkow	844,073
Handle fastening means, Stencil & Nunnelee	843,970
Harrow attachment, disk, W. Fetzer	843,671
Harrow with tongue truck, disk, W. Fetzer	843,672
Harvester guard, J. W. Pridmore	843,629
Harvester, stripper, J. J. Charley	844,000
Hat brim curling machine, D. Clerico	844,098
Hat crown shaping apparatus, C. W. Stevens	843,640
Hat forming machine, C. W. Stevens	843,638
Hat frame, M. W. Elser	844,268
Hatch fastener, E. H. Frey	843,804
Hay carrier, C. D. Barker	843,580
Hay loader, E. A. Johnston	843,610
Hay loader, C. J. Shaw	844,196
Headlight operating mechanism, L. J. Martineau	843,834
Heat retaining or excluding receptacle, J. L. Fate	844,272
Heater, See Electric heater	
Heating and annealing furnace, G. Bods-worth	843,574
Heating systems, combined steam and water trap for steam, T. F. Dexter	844,105
Heating systems receiver for vapor, A. P. Broomell	843,995
Heel sweep brace, J. H. Ingram	844,023
Hemmer, E. Page	843,841
Hinge, C. J. Caley	843,581
Hinge, Weil & Gross	844,069
Hinge, door, J. F. Brice	843,661
Hitching post, B. R. Long	843,954
Hoisting jack, C. O. Brewster	843,666
Holding and draining rack, M. C. Kleopinger	843,826
Hook and eye, A. Bessen	844,059
Hook setting machine, A. Raiche	843,607
Horse shoe calk, R. N. Goodwin	844,121
Horseshoes, means for fastening, J. P. O'Brien	843,907
Hose coupling for train lines, air, W. E. McKinley	844,035
Hot water heater, R. H. Bradley	843,793
Ice crusher, E. T. Larkin	844,146
Imitation tree, E. A. Straub	843,712
Indexes or the like, box for card, J. S. Newberry	844,039
Induction coil, C. L. Bopp	844,240
Induction motor, E. J. Willis	843,981
Inhaler, Y. Q. Caldwell	844,097
Innersole making machine, A. Thoma	843,975
Insulating material and manufacturing same, G. Kelly	844,139
Insulating material and manufacturing the same, G. Kelly	844,140
Insulating saddle staple, W. T. H. Taylor, et al.	843,916
Insulator, electric, F. A. Feigert	843,739
Insulator for leading in cables, etc., L. Steinberger	844,208
Insulator, third rail, R. N. Redmayne	843,844
Ironing machine, G. F. Glazer	844,016
Jewelry holder, M. Jerseman	843,678
Joining or uniting wooden parts, J. A. Wilkison	843,656
Journal box, H. Bensch	844,058
Kettle, A. G. Redwood	843,698
Keyed instruments, apparatus for automatically playing, F. Stone	844,052
Kitchen implement, J. F. Dotson	844,266
Knee protector, F. W. Owens	844,041
Knob, Waddell & Tower	843,720
Labels, means for holding and detaching ribbon strip, Burr & Davis	843,579
Lace with metal, coating, J. A. Daly	844,304
Ladder and scaffold combined, M. Bauer	843,984
Lamp, C. B. Braughton	843,928
Lamp bulb, incandescent gas, C. M. Lungren	843,903



It will out-last your engine

Apple Ignition Dynamos

in use to-day have given A 1 service for the last ten years.

This 1907 model is better than ever.

It retains many of the features of previous models which have proven so successful and it also possesses many new and remarkable improvements.

A 200 R. P. M. reduction in running speed is alone evidence of surprising advancement.

The Apple Ignition Dynamo can be used on any automobile, boat or stationary gas engine as a storage battery charger to complete the "Floating the battery on the line" system, or as an automatic spark for starting and running engines without batteries.


It will pay you to investigate an ignition system that will do its work unfailingly as long as you run your engine.

Send for this bulletin today.

Every automobile, boat and stationary, gas engine manufacturer, jobber, dealer and user ought to have it. Free on request.

The Dayton Electrical Mfg. Company
98 St. Clair Street, Dayton, Ohio.

We exhibit at the New York and Chicago Motor Boat Shows.



TRANSMISSION STEEL TOWERS GALVANIZED

For high tension transmission lines. They are made from 30 to 150 feet in height, and to withstand horizontal strains at the top of from 2,000 to 30,000 pounds. We design and build these towers and guarantee them under actual test to fully meet the specified requirements. Completely GALVANIZED by the hot process after all work of manufacture has been completed.

AERMOTOR CO., CHICAGO

STARRETT TOOLS

are the standard for Accuracy, Design, Workmanship and Finish. Send for Free Catalogue No. 17B, of up-to-date tools for mechanics.

The L. S. Starrett Co., Athol, Mass., U.S.A.

Automatic Water Supply

Most economical, reliable and efficient. If you have running water the Niagara engines will elevate 33 feet for each foot-fall obtainable from spring, brook, or river, delivered to any distance. Write for catalogue. **Niagara Hydraulic Engine Co.** 140 Nassau St., N. Y.



HOW TO MAKE AN ELECTRICAL

Furnace for Amateur's Use.—The utilization of 110 volt electric circuits for small furnace work. By N. Monroe Hopkins. This valuable article is accompanied by detailed working drawings on a large scale, and the furnace can be made by any amateur who is versed in the use of tools. This article is contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1182. Price 10 cents. For sale by MUNN & CO., 361 Broadway, New York City, or by any bookseller or newsdealer.

ELECTRO MOTOR, SIMPLE, HOW TO

make.—By G. M. Hopkins. Description of a small electric motor devised and constructed with a view to assisting amateurs to make a motor which might be driven with advantage by a current derived from a battery, and which would have sufficient power to operate a foot lathe or any machine requiring not over one man power. With 11 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 641. Price 10 cents. To be had at this office and from all newsdealers.

It's a Fine Piece of Work

in itself. That's the best reason why all the work it touches has the stamp of quality and perfection.

Goodell's Hand Drill

has new 20th century features. Double gears. Two speeds. One chuck. Capacity to 3/8 inch. Send for catalogue.

GOODELL-PRATT COMPANY
Greenfield, Mass.



The Kickdrive Circular Saw

is a simple power for light work of the kinds most done by carpenters, cabinet, box, pattern and picture-frame makers, and wood workers generally, besides engravers and electrotypers. This Machine has a strong, solid iron frame and steel shaft; is thoroughly well-built and suitable for various kinds of work, as ripping, cross-cutting, grooving, etc. Can be operated sitting or standing. We also make all kinds of foot power devices.

MAYER SLOTKIN
210-212 Canal St., New York.

Classified Advertisements

Advertising in this column is 50 cents a line. No less than four nor more than ten lines accepted. Count seven words to the line. All orders must be accompanied by a remittance. Further information sent on request.

SALE AND EXCHANGE.

FOR SALE.—Road Leveler, Grader and Drag combined. Patented Nov. 20, 1906. Easily changed, cheaply made. Will sell or on royalty. Chas. W. Kaufman, Route No. 5, Box 74, Bloomington, Ill.

BUSINESS OPPORTUNITIES.

PATENTS SOLD ON COMMISSION.—If you wish to buy or sell a patent write for particulars to E. L. Perkins, 72 Broad Street, Boston. Patent Sales Exclusively.

A FEW DOLLARS will start a prosperous mail order business. We furnish catalogues and everything necessary. By our easy method failure impossible. Write today. Milburn-Hicks Co., 718 Pontiac Building, Chicago.

HAND AND MACHINE WOOD TURNING of every description; job and contract work solicited. Pioneer producers of Rustic Novelties. Established 1875. Barton & Spooner, Cornwall-on-Hudson, N. Y.

CAPITAL put in touch with profitable investment. Doubtful enterprises weeded out. Only the best offered. Some fine advertising propositions. What do you want? Costs you nothing to say. Long, 633 Ellicott St., Buffalo.

A BARGAIN to Manufacturing Co.—By manufacturing Gear Chipping Corn Harvester, Patent No. 693,065 and Husk Shredder, No. 707,013. Combined or separate. Get a half interest to make or buy all. Munn & Co., Patent Office Solicitors, A. W. Richards, Indianapolis, Iowa.

WANTED.—PARTIES TO MANUFACTURE Churn on royalty. Made principally of wood. For further particulars and full information, address John C. McVey, 303 Indiana Avenue, Kansas City, Mo.

CHEAP ICE.—Make your own ice. From 1 pound to 1,000 pounds of ice produced daily by the Howell system. Address Howell Ice Making Company, 7 Centuries Ship, New York City.

SEND SKETCH for estimate if you have anything you want made on contract. Experimental work. Inventions developed. Metal patterns a specialty. Osborne Manufacturing Co., Erie, Pa.

WE ARE IN POSITION to secure capital, special or active partners for good, sound business propositions; we have several clients on hand who will consider business openings that will stand thorough investigation. Sam'l T. Bondhus & Co., 97-99 Nassau St.

FINANCING AN ENTERPRISE.—Practical 500-page book, by Francis Cooper, telling how money is secured for enterprises. The only successful work on promotion. Endorsed by business men all over the country. Two volumes, buckram binding, prepaid, \$4.00. Pamphlet and list of business books free. Ronald Press, Rooms 30-32, 229 Broadway, New York.

FOR SALE.—Portable Compressed Air House Cleaning Wagons and Machinery sold to responsible parties to operate in cities of from five thousand inhabitants upwards. Each Portable Cleaning Plant has an earning capacity of from \$50.00 to \$70.00 per day, at a cost of about \$8.00 per day. Capital required from \$2,000 upwards. Stationary Residential Plants also from \$450.00 upwards. Over 100 companies operating our system. We are the pioneers in the business, and will prosecute all infringers. State references. Address General Compressed Air House Cleaning Co., 443 Olive Street, St. Louis, Mo.

SELL PATENTS.—To buy or have one to sell, write Chas. A. Scott, 719 Mutual Life Building, Buffalo, N. Y.

HELP WANTED.

GOOD OPENING for young technical graduates eager to gain practical experience; salaries \$700-\$1,000 to start; write us to-day. Hapgoods, 305 Broadway, N. Y.

MEN \$30-\$100 WEEKLY.—Learn Hairdressing, Manicuring, Cosmetology, Massage, Beautifying, which pays ten times better than any other calling. Personal and Mail Courses. Prof. Rohrer's Institute, 147 W. 23d St., N. Y.

TYPEWRITERS.

WELINGTON Typewriter! Durable, strong, speedy. All reliable features of standard machine. Permanent alignment and simplicity eliminating repairs. Workable in eight. \$80. Williams Mfg. Co., 335 E. 4th St., N. Y.

TYPEWRITERS, OUR OWN MANUFACTURE, fully guaranteed, \$10 to \$50. Special terms if you mention SCIENTIFIC AMERICAN. American Typewriter Co., 261 Broadway, New York.

CLEARANCE SALE.—Remingtons, Denmores, Jewetts, Blickensderfers, Williams, \$12.50; Postals, Hammonds, \$10; Underwoods, Oliviers, \$5. Orders filled or money back. Standard Typewriter Exch., Suite 45, 231 Broadway, N. Y.

TYPEWRITERS.—Calligraph, \$5. Hammond, \$10. Remington, \$12. Remington two-color ribbon attachment, \$18. Send for catalogue. Typewriter Co., Dept. L, 45 W. 125th Street, New York City.

SPECIAL BARGAINS.—Remington No. 2, writing two colors; Denmore, Hammond, Franklin \$15 each, shipped privilege of examination. Write for complete catalogue. E. F. Eagle Typewriter Co., Suite 11, 227 Broadway, N. Y.

PATENTS FOR SALE.

OFFERS are invited for purchase of four United States Patents covering Incandescent Gasoline Lamps. The Lamp is a great success in Britain as manufactured by Petrolite, Ltd., 106 York Road, Lambeth, London. The Lamp is safe (liquid being contained in absorbent block), clean and economical, with brilliant light. No smoke, no smell, no cleaning. Inquiries to Guthrie & Cairns, 4a St. Andrew Square, Edinburgh, Scotland.

FOR SALE.—U. S. patent No. 840,263. Patented January 1, 1907. New improved carpenter tools. (Cheap) to manufacture, easy to sell. Address Bruno Stoll, Gardena, Bottineau Co., N. D.

LATELY PATENTED everlasting combination door lock without key, \$40.00. Can be adjusted on any door. For sale. Would consider royalty. John Sliga, 1028 St. Clair Ave., Cleveland, Ohio.

FOR SALE.—A patent—Simple device for converting any coffee pot or vessel into an ideal French coffee pot. For particulars address R. L. Griffith, Mills Building, New York City.

FOR SALE.—U. S. patent on something new in pulley blocks. Noiseless. Self-lubricating. Strongest. Can be manufactured at small cost. For cuts and copy of patent address Frank P. Whiteside, Youngstown, Ohio.

FOR SALE.—Patent for Door Latch and Lock. Entirely new principle of construction and operation. Will revolutionize lock industry. See description, this paper January 5. Peter Ebbeson, St. Paul, Neb.

STAMPS AND COINS.

1,000 FINEST QUALITY STAMP HINGES and price list free. 1,000 different stamps mounted and arranged by countries, \$3. 100 different U. S. stamps, 1851-1900 for 20c. Metropolitan Stamp Co., 81 Nassau St., N. Y.

EYE-GLASS SPECIALTIES.

ABSOLUTE COMFORT AND ASSURANCE OF SAFETY means wearing the 12 Kt. Gold-filled, Patent Slip-not Eye-glasses, \$1.50. Hold tight and feel light. M. Singer, Manufacturing Optician, 116 Fulton St., N. Y.

FOR THE HAIR.

OUR VACUUM CAP when used a few minutes each day draws the blood to the scalp, causing free and normal circulation, which stimulates the hair to a new, healthy growth. Sent on trial under guarantee. Write for free particulars. The Modern Vacuum Cap Co., 617 Belden Block, Denver, Col.

FACTORY AND MILL SUPPLIES.

FACTORIES. CUT DOWN YOUR INSURANCE by putting in a Caldwell Tank and Tower for fire protection. Once up, no further expense. Endorsed by all insurance companies. References in every section. Arkay Stave Co., of Columbus, Miss., says: "Saves us \$20 a month." Illustrated Catalogue and Price List free. W. E. Caldwell Co., Station D, Louisville, Ky.

WANTED—MISCELLANEOUS.

Wanted, Platinum Seals, we pay \$1.50 per dwt. for clean PLATINUM SCRAP. Send by Registered Mail for Safety. National Refinery, 239 Taylor Ave., Newport, Ky.

GAS-LIGHTING APPLIANCES.

THE "PNEU-WAY" of lighting gas! Lights Welshbachs without electricity from button on wall! Easily installed, ever-lasting. Ask your gas company or write Pneumatic Gas Lighting Company, 150 Nassau St., N. Y.

MACHINERY FOR SALE.

REMOVED to larger quarters, we offer our large stock of new and second-hand machinery; also boilers, engines, dynamos, motors, materials and supplies. Liberty Machinery Mart, 153 West Street, New York.

BOOKS AND MAGAZINES.

DEEP BREATHING—How, When and Where. A 64-page illustrated book on this vital subject on receipt of 10 cents. Address P. von Boeckmann, R. S. 750, Bristol Building, 50 Fifth Avenue, New York.

THE POCKET LAWYER.—A handy, practical reference book containing all needed information on legal subjects, Banking, Labor Legislation, Etc. Price 10 cts. Postage prepaid. Landsberg Bros., 96 Fulton St., N. Y.

SOUVENIR POST CARDS.

LIFE-MOTION POST CARDS.—New York's latest fad. Application of a light produces moving picture effect. An evening's fun can be provided with a set of these cards. Special Offer—Set of 9 assorted subjects, postpaid, 50c. Eagle Card Co., 2 Park Place, N. Y.

1,000 POST CARDS \$5. 500-44: made to order from many Photo or Print with your imprint on each as publisher. Workmanship guaranteed. Goods delivered within 10 days. Rich Photo Process Co., Dept. F, 28 E. 23d St., N. Y.

PHOTOGRAPHY.

WE PHOTOGRAPH any thing, any where, any time. Building, Paintings, Plans, Models, Machinery, Estates, etc. Illustrations for Advertisers. The General Photographic Co., 1215 E. 4th, Daily's Theatre Bldg., N. Y. City

AUTOS.

UNDERSTAND YOUR AUTOMOBILE! The Motor Car Model tells all about construction, mechanism and location of every part. Strongly bound in Cardboard, 9 1/2 x 13 1/2. Colored Plates. Condensed Text, giving comprehensive ideas of working. \$1.50 postpaid. Whitaker, 12 Bible House, New York.

ASTRONOMY.

STARS AND PLANETS—learn to know them at a glance! Astronomy in simplest and most fascinating form. The Revolving Planisphere shows clearly principal stars visible any hour in year. Simple, handy, reliable. Only 35c. T. Whitaker, Publisher, 123 Bible House, New York.

SCHOOLS AND COLLEGES.

GEO. H. WILSON, the World's Champion, has written a booklet, "Vaudeville, Stage Dancing and Entertaining." It is absolutely free and very interesting. Just address Wilson's Vaudeville School, 263 W. 42d St., N. Y.

PATENT Laws and Office Practices.—Thoroughly practical course by mail for attorneys and inventors. Free specimen pages and information. Cor. School of Patent Law, Dept. A, 1855 Mintwood Place, Washington, D. C.

ALCOHOL MANUFACTURING.

EXPERT ADVICE in the manufacturing of alcohol and compressed yeast. Analysis of all raw materials and by-products. H. H. Freund, Technical Fermentation Chemist, 145 East 23d St., New York.

COINS, MEDALS, CURIOSITIES.

FROM ALL AGES AND COUNTRIES.—Largest stock in America. \$1.50 to \$10 paid for gold dollars. Illustrated premium catalogue, 10 cents. New York Coin and Stamp Co., 551 Broadway, New York.

Lamp cluster fixture, electric, S. R. Fralick	844,276
Lamp shade, F. Thiedig	843,974
Lamp sockets, machine for making shells for electric, J. Beck	843,789
Lamps, illuminant for incandescent electric, O. M. Thewless	844,213
Lamps, machine for making stems of incandescent, Howell & Burrows	843,750
Lamps, etc., socket seal for electric, L. T. Hatfield	844,126
Latch, gate, J. Crawford	844,126
Lathes, cylinder grinding attachment for, G. P. Morris	844,265
Leather splitting machine, J. J. Heys	844,128
Letter folding device, J. Baum	843,571
Leuco derivatives of gallicyanins and aromatic amines and making same, H. Loretan	844,155
Leveling and scraping machine, M. P. Zin	843,784
Lifter, J. Regel	844,239
Lime and cement forming material, cal-	
Lime spreader, J. H. D. E. Kefauver	843,878
Limeum and carpet stretcher, Giddings & Emerick	843,743
Liquid receptacle, E. Newbegin	844,037
Lock, See Gate lock	
Lock, N. B. Hurd	843,607
Lock, W. F. Clay	843,869
Lock, Katzenberger	844,138
Locomotive ash pan, Eckenrode & Baldwin	844,267
Locomotive, electric, A. F. Batchelder	843,788
Locomotive reel, mine, C. O. Palmer	843,694
Loom shuttle, F. H. Stetsen	843,912
Looms, selvsage forming attachment for, T. Garisio	843,884
Lubricator, F. C. Tees	844,211
Lubricator, L. Kaczander	844,281
Mail box, residence, W. H. Granger	843,805
Mail delivery apparatus, J. R. Harris	844,125
Mangles, feeding attachment for, Slack & Riley	843,709
Map case, W. McMaster	843,837
Marble polishing machine, J. R. Peirce	843,624
Marl, making carbide, utilizing, H. L. Hartenstein	844,018
Massaging apparatus, E. M. Funk	843,674
Match box, E. A. Gerken	844,119
Match safe, M. E. Mitchell	843,685
Matrix making, means to position plates and blocks, F. H. Brown et al.	843,578
Matrix making plate and block attached, P. H. Brown, et al.	843,577
Maul, pest, E. Simmons	843,636
Measure and register, beer, W. H. Miner	843,957
Meat chapping machine, E. Lacey	843,898
Meat cutter, J. & K. Poskeell	843,696
Mechanical movement, J. D. A. Johnson	843,823
Mechanical movement, W. H. Vess	843,917
Metal and concrete structure, H. Mannhardt	843,683
Metal cylinder for treating heated, J. W. Mosher	844,255

Metal expanding machine, H. E. White	843,728
Metal structure, expanded, A. P. White	843,726
Metallurgical process, E. R. Taylor	843,777
Milk powder, manufacture of, A. Glas	843,938
Milking machine, apparatus for operating, B. & F. Ljungstrom	843,757
Mill, J. Dain, Jr.	844,303
Mold, G. H. Terry	843,716
Mold, H. Bessert	844,234
Mold, J. V. Beland	844,236
Molding machine, H. Bessert	844,235
Motion to sieve boxes and other bodies, means for imparting gyratory, E. R. Draver	844,005
Motors, arrangement for regulation of speed of compensated single phase, Arnold & La Cour	843,731
Mower, lawn, J. P. Jasper	843,821
Mower, lawn, W. W. McCarty	843,961
Music cabinet, sheet, O. H. Stewart	843,711
Musical instrument, mechanical, J. McTammany	844,310
Musical instrument of player, automatic, P. B. Klugh	843,755
Musical instruments, tailpiece for stringed, E. D. Sen	843,851
Nail plate heating furnace, W. S. Myers	843,620
Neckband stretcher, J. Fischer	844,110
Nest, P. E. Smidesang	843,850
Newspaper receptacle, M. D. Turletot	844,059
Nippers, W. J. Jenkins	844,134
Nozzle, I. W. Hoover	843,945
Nut and pipe wrench, H. B. Shaver	843,969
Nut lock, A. E. Ogden	843,840
Nut locking washer, R. A. Schindler	843,704
Nuts, dies and punches for making hexagonal, G. Dunham	843,875
Oil extracting apparatus, cotton, R. S. Woodward, Jr.	843,984
Oil from oleaginous seeds, extracting, R. S. Woodward, Jr.	843,983
Oiler, wagon, H. Leidy	844,149
Optical instrument, J. J. Fric	844,012
Ores, treatment of sulfid, Baker & Smith	843,986
Outlet boxes, plaster holder for, A. McMurtre	843,962
Overalls, Eckel & Tegeder	843,876
Packing, C. Restein	843,930
Pail support, A. W. McIntyre	844,175
Paper and textile goods, roll for finishing, E. A. Rusden	843,700
Paper box machine, Rowell & Little	844,190
Paper hanger's trestle, J. R. Kingsley	844,143
Paper package, toilet, A. H. Scott	843,771
Paper tray, F. B. Davidson	843,933
Patterns on pattern plates, apparatus for locating, H. R. Frisbie	844,117
Pen retainer, fountain, L. D. Van Valkenburg	844,061
Penholder, J. Flach	843,767
Pen, sharpening, W. E. Cary	843,999
Photographic print drier, J. B. Farquharson	844,271
Photographic printing machine, J. F. Jungkind	844,135
Piano flange attaching bar, F. G. Billings	844,238
Piano seat or bench, adjustable, J. P. Clark	843,584
Piano touch regulator, Wallace & Jones	843,721
Picture hanger, T. P. Hall	843,942
Picture transmitting mechanism, telegraphic, E. & M. Bellin	844,086
Pigs' feet drier and singeing oven, H. Loesch	844,153
Pine retaining, E. Fischer	844,274
Pipe coupling, automatic train, F. H. Rutherford	843,911
Pipe couplings, clamping ring for, J. Clark	844,250
Pipe hanger, A. McMurtre	844,636
Pipe hanger, adjustable and elastic, A. F. Schafer	843,632
Pipe joint, Haller & Machell	843,892
Planer, C. Hooghouse	843,818
Planimeter, E. M. Seville	844,195
Planter, corn and cotton, A. J. H. Reid	843,699
Planter, marker, corn, A. E. Starrett	844,290
Plow, M. J. Brexer	843,993
Plow, N. O. Flint	844,112
Plow attachment, E. B. Barrows	844,084
Plug, attachment, J. G. Peterson	844,044
Pneumatic carrier, M. B. Rifo	843,769
Poles, shoe for wooden, C. O. Muller	843,762
Post, See Hitching post	
Post anchoring device, P. T. Bailey	844,231
Post cards and the like, coin freed apparatus for picture, S. Wistoft	843,859
Post hole digger, W. B. Nicholson	843,765
Post hole digger, J. S. Durning	843,800
Potato digger, sulky, I. A. Dodge	844,106
Power brake, L. P. Fingert	843,625
Power transmission, M. Moskowitz	844,165
Power transmission, apparatus, hydraulic, G. L. M. Derwald	843,874
Power transmission gear, J. H. Morrison	843,687
Preserving jar, C. A. Stenius	844,050
Printer's border, W. D. Palmer	843,766
Printer's hook, T. Wensel	843,648
Printing in several colors, system of machinery for, E. Lambert	843,829
Printing machine, label, E. Z. Taylor	844,055
Printing machines, feed device for sheet metal, A. J. Ford	844,113
Printing, photochemical, J. W. Ippers	843,947
Printing press, automatic sheet gage for, C. M. Morrison	843,688
Printing surfaces, apparatus for producing, E. Mertens	844,162
Projectile and fuse plug therefor, C. F. & H. L. Cowdrey	843,665
Pulley block, E. K. Woolly	843,982
Pump, oil, G. T. Ferguson	844,208
Pumps, seat for puppet or foot valves of, L. M. Gerwe	843,597
Punch, automatic prick, Adell & Starrett	843,655
Punching machine, W. F. Lautenschlager	843,899
Puzzle, F. Ringl	844,180
Puzzle, W. J. Webb	844,246
Rack, L. B. Webb	844,267
Rail chair, J. H. Snell	844,050
Rail check, adjustable guard, G. M. Ervin	843,880
Rail fastener, adjustable guard, C. C. Korus	843,897
Rail fastener, adjustable guard, F. Glenton, Jr.	843,939
Rail joint, J. A. J. Vance	843,853
Rail joint, Irwin & Strawn	844,132
Rail joints, seating strip for, B. Grubbs	843,807
Railway buffer, W. F. Bossert	844,092
Railway frog, J. E. Graham, reissue	12,605
Railway gate for grade crossings, electric, C. W. Mendenhall	844,284
Railway rail joint, J. C. Wallace	843,918
Railway rail stay, H. C. Spoenburg	843,710
Railway rails, anticreep and brace for, E. L. Knight	844,145
Railway screw spikes, bushing for, A. Stucki	843,713
Railway signal system, A. L. Ruthven	843,703
Railway sleepers, machine for cutting rail seats in, A. Collet	844,100
Railway splice, J. S. Beck	843,732
Railway switch, C. D. Fuller	844,014
Railway switch, G. E. Stewart	844,200
Razor, safety, F. H. Arnold	843,923
Reciprocating engine, W. Mauss	844,161
Reeling and unreeling attachment, A. J. Determann	844,260
Refining engine, S. R. Wagg	844,063
Refrigerating apparatus, J. H. Holmgreen	843,894
Refrigerator, C. Dukelew, et al.	843,668
Refrigerator, F. C. Trotter	843,978
Refuse burner, C. D. Stevens	843,971
Rein holding attachment for harness, R. F. Hayner	843,600
Rheostat, starting, L. S. Chapman	843,735
Ring and roller and like mill, E. Barthelme	844,085
Ring mold, F. C. Widmann	844,072
Roasting furnace, J. Klepetko	843,825
Rock drill feeding mechanism, T. Turner	843,718
Roll manufacturing mold, C. Johns	843,679
Rolling, expanding, and beading roller tubes in one operation, tool and holder for, Todd & Shupert	844,215
Roof structure, H. Thaden	844,212
Roofs, walls, and buildings, metallic covering for, S. Taylor	844,056
Rotary engine, A. Bretscher	844,094
Sash construction, E. L. Charroin	844,301

Is **THIS** the letter of **YOUR** line?

A

	PAGE
Accountants	8
Advertisement Writers	17
Architects	15
Artists	4
All Pencil Users	1-32

No matter what you do, there's a right Lead Pencil for your work.

Dixon's Pencil Guide describes it by name and number so you can get it anywhere. The Guide is alphabetically indexed by vocations. Find your page and your pencil is before you. The book is free.

If your dealer doesn't keep Dixon's Pencils, send 16 cents for samples, worth double the money.

DEPT. W. JOSEPH DIXON CRUCIBLE CO., JERSEY CITY, N. J.

KING Folding CANVAS BOATS

Lighter, more durable than wood. Serviceable in salt water. Puncture-proof; not sinkable; can't tip over. A revelation in boat construction. Can be carried by hand, or checked as baggage. When not in use, fold up into a package. Send for Catalog, 100 Englewood, KING FOLDING BOAT CO., 683 West North Street, Kalamazoo, Mich.

M

SORE THROAT

To prove the Efficiency of

Hydrozone

to Sore Throat Sufferers, I will send **One 25 Cent Bottle Free** to anyone mentioning this paper and sending 10 cents to pay postage and packing. Hydrozone is a harmless germicide, indorsed and successfully used by leading physicians. Not genuine without my signature on label. Ask for Booklet on Treatment of Diseases. Sold by Leading Drug-gists.

Prof. Charles H. Harchand

Dept. U, 63 Prince Street, New York

FERRO


Auto-Marine Engine

The one marine gasoline engine of perfect reliability. Made from blue print to finished engine by the most skilled organization in the business. One, two and three cylinders—1½ to 25-H.P. The immediately get-at-able, easily understood, easily managed, absolutely reliable engine. Every wearing part adjustable. Cylinders taken off without disturbing pipes, bearings, crank shaft, or base. No visible water pipes, no grease cups, no leaky bearings. A strong, dependable engine in every detail. Equipped for salt water. Send 10 cents for our

complete Treatise on Marine Gasoline Engines or write for free catalog, which fully and plainly describes the construction of the perfect engine. Send to-day.

The FERRO Machine & Foundry Co.
75 Wade Building, Cleveland, Ohio
Large Stock carried in Eastern Branch
79 Cortlandt street, NEW YORK CITY

Our patterns or materials cost you only half the price asked by others.



BUILD YOUR OWN BOAT

We are the largest builders of pleasure boats in the world. We sell you full size working patterns, knock-down frames and materials from bone-dry stock, at half the price asked by others. We use these patterns and stock every day in building our regular boats. You are not buying theories. Catalog free. DETROIT BOAT CO., No. 27 Bellevue Ave., Detroit, Mich.

The Strelinger

Noted for Reliability, Durability, Economy and Power.



Mechanical or Jump Spark Ignition.

If you are contemplating the purchase of a Marine Gasoline Engine, our general reduction in prices for 1907 will interest you. Catalog and Prices on application.

THE STRELINGER MARINE ENGINE CO.
48 Fort Street E.
Detroit, Mich.

1 to 4 Cylinder.

3 to 5 H. P.

\$49




Little Giant
GASOLINE MOTORS

Reliable, Reversible, Two Cycle. Two and Three Port. Guaranteed for one year. Simple and easy to operate. Our Catalog A3 is worth your having.

UNITED MFG. CO., - - Detroit, Mich.

Packard Enameled Ignition Cable



Why not eliminate the tantalizing uncertainty of your ignition system by using a tested and guaranteed article that has so gloriously stood the test of time?

THE PACKARD ELECTRIC CO., Warren, Ohio

A Home-Made 100-Mile Wireless Telegraph Set

Read SCIENTIFIC AMERICAN SUPPLEMENT 165 for a thorough, clear description, by A. Frederick Collins, of the construction of a 100-mile wireless telegraph outfit. Numerous, adequate diagrams accompany the text. Price 10 cents by mail. Order from your newsdealer or from

MUNN & CO., 361 Broadway, New York


Scenery, theatrical, L. J. Carter	843,583
Scholar's companion, A. Foster	844,114
Screen, See Grain screen	
Screen, C. R. Allen	843,785
Seal press, cording and wiring, E. J. Brooks	844,095
Sealing closure for vessels, G. T. Reed	843,845
Sealing jars and the like, ring for, W. B. Penn	843,740
Sectional boiler or furnace, J. M. W. Kitchen	843,612
Sewing machine folding attachment, H. Nederman	843,538
Sewing machine, loop lock-stitch, F. W. Merrick	843,760
Sewing machine operating device, hand, M. J. Rapier	844,187
Sewing shoe soles to uppers, J. A. Rhault, reissue	12,607
Shade and curtain fixture, combined, S. R. Auker	843,658
Shaft support, vehicle, H. S. Elliott	844,260
Shafting, clamp collar for, S. T. Murchie	843,806
Shears or the like, F. D. Davies	843,667
Sheave block, E. Ludford	844,150
Sheet metal slip cover can for lard and other articles, J. Dister	843,799
Sheet metal slip cover can for lard and other materials, J. Dister	843,798
Sheets or units, apparatus for cutting, folding, and interfolding, S. Wheeler	843,781
Shell, exploding, A. Wratzke	844,225
Shipping box or crate, J. E. Hitch	843,816
Shipping box or crate, knockdown, J. E. Hitch	843,815
Shoe-upper pounding machine, S. J. Wentworth	844,293
Shovels, scraper attachment for, W. H. Colclough	844,002
Shovels, teeth for excavating, F. J. Thomas, reissue	12,608
Show cases and the like, adjustable leg for, J. Taussig	843,973
Sieve cleaner, D. W. Marmen	844,030
Sight feed lubricator, P. Wertz	843,856
Sign, A. G. Wallin	843,779
Sign, illuminator, E. E. Bellamy	844,037
Skid and truck, P. W. Young	843,854
Skirt hanger, M. H. Cazier	843,794
Skirt support and blouse stay, I. B. Hogan	844,021
Skirt supporter, W. R. White	843,782
Sliding gate, Kerber & Bakehaus	843,681
Snap fastener, F. G. Wiseloge	843,652
Snap fastener, C. C. Korns	843,896
Smoke consumer for locomotive and like boilers, K. Schleyder	843,848
Snap fastener, A. J. Grove	844,280
Soldering implement, can, S. A. Varney	844,062
Soldering iron, E. L. Vieth	843,645
Sole attachment, shoe, A. W. Billingham	844,057
Speed indicator, L. L. Denis	844,258
Spinning and twisting apparatus, ring, J. Hayden, Jr.	843,810
Square, folding, A. E. Sellers	844,205
Square, try, R. A. Breul	844,243
Stamp affixer, postage, P. W. Cherry	844,302
Stamping machines, counter block and die for, J. A. McNulty	844,171
Stanchion assembling apparatus, Wasson & Hutchings	844,218
Stay, garment, A. E. Magers	844,160
Steam generator, C. Lucke	844,158
Steam making apparatus, P. M. Knepp	843,613
Steam trap, Moffat & Butler	843,868
Steel manufacturing, B. E. Eldred	843,592
Steering mechanism, C. Baker	844,232
Stenciling appliance, C. D. White	843,820
Steve, E. G. Van Wie	843,643
Steve and range attachment, E. C. & E. L. Kessler	844,142
Stove, cook, W. R. K. Stanford	843,773
Stove, gas, E. G. Van Wie	843,644
Stove, heating, L. H. Thurston	844,282
Surgical eye magnet appliance, J. B. Wantz	843,978
Surgical instrument, H. H. De Pew	843,587
Suspender link, B. J. Balliett	843,887
Switch operating mechanism, automatic, C. R. Traxler	843,641
Table utensil, G. Laramy	843,853
Tablet machine, J. V. Brann	844,093
Tag clip, A. McCallum	843,860
Tag, key ring, T. F. Moore	843,858
Teaching touch typewriting, device for, Keesling & Beach	844,025
Telegraph key, J. J. Ghegan	844,278
Telephone hook switch, O. C. Cadden	843,888
Telephone lines, coin collector for, F. R. McBerty	844,034
Telephone lines, harmonic signaling for, station, W. W. Dean	844,257
Telephone receiver, H. W. Hafl	843,591
Telephone receiver attachment, J. R. Challen	844,288
Telephone transmitters, antiseptic guard for, G. E. Grimm	843,940
Telephone trunking system, W. W. Dean	843,871
Telephones, arm support for, L. Barrella	844,083
Telescope with prisms, P. F. Putz	844,186
Theater, H. Helbig	844,127
Theatrical apparatus, R. F. Staley	844,207
Thill coupling, L. W. Ward	843,723
Thill coupling, antirattler, W. Cox	843,736
Tie plate, E. L. Flinn	843,585
Tire, H. L. Slager	844,201
Tobacco leaf sizing machine, H. Schumacher	844,048
Tobacco packing and shipping can, A. H. Gregg	843,745
Tongue switch, E. B. Entwistle	843,879
Tool and tool holder, compound, O. S. Perkins	844,043
Tool, combination, A. Galperin	843,836
Tool handle, J. N. Howard	844,130
Tool holder and tool, self-tightening, E. S. Costa	843,931
Tools, automatic feeder for, Carnahan & Murphy	844,247
Toy, P. F. Van Halder	843,642
Transmission mechanism, F. Strickland	844,210
Transmission mechanism, J. J. Troeger	844,217
Transmitting system, selective, J. L. Hall	843,746
Trap, See Steam trap	
Tray, serving, C. A. Weiss	844,219
Trolley retriever, F. M. Miller	843,761
Truck, W. H. Armstrong	843,570
Truck, car, W. S. Adams	844,076
Truck, car, G. Lindenthal	844,150
Truck equipment, car, G. Lindenthal	844,151
Truck skid, F. G. McGinnis	843,835
Trunk, G. S. Eggeman	843,877
Truss, P. Kaseler	844,137
Tubes, mechanism for the manufacture of seamless, M. F. Capron	843,868
Turpentine bucket, N. E. Stone	843,815
Type making machine, F. H. Brown, et al	843,576
Typewriter, C. T. Brown	843,897
Typewriter, E. B. Pierce	844,183
Typewriters, variable feed mechanism for, F. Schuler	844,288
Typewriting machine, E. F. Kunath	843,828
Typewriting machine, E. G. Latta	843,831
Typewriting machine, B. C. Stickney	843,814
Typewriting machine, S. H. Donaldson	844,264
Typewriting machine ribbon mechanism, E. G. Latta	843,830
Upsetting machine, E. G. Beker	843,780
Vacuum creating device for jars, etc., G. T. Reed	843,846
Valve, T. Barton	843,888
Valve, R. Schneider	844,182
Valve, H. H. Cruger	844,255
Valve, F. H. Harmer	844,307
Valve, flushing, W. S. White	844,221
Valve, for drain traps, back pressure, J. F. Conrad	844,003
Valve for heating systems, A. P. Broomell	843,896
Valve, hot blast, E. Farge	843,935
Valve operator, steam and air, D. H. Green	843,598
Valve seats, machine for refacing, Lacey & Ulrich	843,615
Valve, self-closing, N. Nilson	844,180
Valves or other movable devices from a distant station, means for controlling, E. M. Hewlett	843,814
Vaporizer, M. Seligson	843,705
Vehicle cover, B. L. Westbrook	844,220
Vehicle, motor, M. Fischer	844,011
Vehicle running gear, motor, Warrington & Marmon, reissue	12,609
Vehicle wheel, A. Fay	843,738
Vehicle wheel, J. S. Stevenson	843,813
Vending apparatus, controlled, Cace & Mayo	844,248

SKIDOO!

MARINE ENGINE

For Use in Canoes, Rowboats and Launches

Pat.
Pend.



The 2-Cycle-Engine-Sensation of the Year. Entirely new design introducing many exclusive features which challenge comparison with any other engine of its class, regardless of cost. Runs on Gasoline Distillate, Kerosene or Alcohol without change in equipment

2 Actual BARE H. P. ENGINE \$23
Engine with Accessories, complete, \$36.75
With Accessories and Boat Fittings, complete, \$38.50


Weight, bare, 52 pounds; height from base 11¼ inches. Swiftest, most powerful, efficient and reliable engine of its size on earth. Drives Canoe, Rowboat or 14 to 20-foot Launch, with load, 6 to 10 miles per hour. Easy to install and operate. Reversible—runs either way. Unfailing endurance powers—economical and safe—cannot back-fire. Simple and compact in design, strong and durable in construction. Elevated gearless commutator of special design, plunger pump without visible pipe connections, perfect lubrication. Highest grade material and workmanship.

SOLD UNDER 5-YEAR GUARANTEE!
DESCRIPTIVE CATALOG FREE

BELLE ISLE MOTOR CO., Detroit, Mich.

KAHN SYSTEM

of Reinforced Concrete



The requirements of modern buildings are fully met by the **Kahn System of Reinforced Concrete**.

If **Speed** is demanded it can be obtained in an unprecedented degree by the Kahn System, and yet this speed is accompanied by

Perfect Safety when in the hands of experienced men exercising care in handling the details and giving proper attention to the requirements of the design.

Stability is equally a characteristic of this method of construction, and is testified to by the appearance all over the country of buildings having the enduring qualities of structures carved out of solid rock; in other words, monolithic in type and, therefore, best adapted to withstand the attacks of time and other destructive elements.

The Kahn System is based on the use of the Kahn Trussed Bar, with rigidly attached, shop-prepared diagonals, whereby the cost of installing is reduced to the lowest possible point, and the highest degree of reinforcing efficiency is secured.

The Kahn System is endorsed not only by official tests, but by the even more convincing tests of actual practice—structures now in daily use and open to public inspection and investigation. For example: such buildings as the United States Naval Hospitals at Washington and Annapolis, and numerous other Government buildings; the Farwell, Ozmun & Kirk Co. Warehouse, St. Paul, Minn.; the immense automobile plants of the Cadillac, Packard, Pierce, Garford, and Thomas companies, and hundreds of other structures, including warehouses, factories, office buildings, railroad roundhouses, coal breakers, bridges and viaducts.

During the coming year we will continue the publication of the "Trussed Concrete Bulletin," and if you will write your request on your business letter head, we will be pleased to place your name upon our mailing list.

Trussed Concrete Steel Company
75 W. Congress Street
DETROIT

London

Toronto

A New and Better Kind of Soap

Always clean and pure. In bottles, safe from contamination. What you use has never been used before. A pure, delicately perfumed cleanser, germicide, antiseptic.

The Way Its Used

BENDER'S SANITARY LIQUID TOILET SOAP

The only proper soap for Hotels, Public Buildings, Offices, Parlor Cars, Steamships and the Home.

Quart bottles.....25c.
Half bottles.....15c.
Soap Holder (Patented) \$2.00

Should be on every wash-stand. A push on the button gives just the desired amount—no waste, no dirt, no contagious germs. Write for Illustrated Circular. On Sale at drug stores, department stores or direct from

BENDER MFG. CO.
 540 Land Title Bldg., Phila., Pa.

Vermicelli and the like, machine for manufacturing and bundling, B. F. A. Courtney	843,932
Vessel closing device, W. B. Penn	843,802
Veterinary instrument, A. Kepler	844,141
Wagon body, C. Leavitt	844,147
Wagon jack, I. Chupe	843,772
Wagon loading device, R. Pedersen	843,685
Wagon running gear, W. McIntosh	843,691
Walls, making composite, E. Martin	843,956
Warp stop-motion detector, W. Fehr	843,882
Washboard, renewable front, W. G. Frost	844,013
Washer. See Nut locking washer.	
Washing apparatus, F. H. Cole	843,585
Washing machine, J. R. Carter	843,734
Watch, stop, A. Gerson	843,887
Water closet flush valve, J. Kelly	843,949
Water heater, H. S. Humphrey	844,131
Water purifying apparatus, J. M. Murphy	844,167
Water purifying apparatus, A. E. Dieterich	844,262
Water rating and controlling machine, automatic adjustable, W. J. McBride	843,959
Water softening plant, A. B. Bellows	843,572
Waterer, hog, P. Bernard	843,925
Watering trough, stock, Geritzen & Roghair	844,277
Wave action, protecting objects from, P. Brasher	843,926
Wave motor, H. L. McDufee	844,174
Weighing machine, automatic, H. Richardson	844,188
Welding machine, die, W. B. Hankins	843,809
Wells, machine for reviving gas, Van Arsdaale & Spearman	844,060
Wheel flange, attachable, H. L. Hegland	843,943
Whistles, megaphone attachment for steam, R. H. Courtney, Jr.	844,254
Window, A. Assorati	844,229
Window chair, adjustable, D. S. Leger	844,148
Window lifter, N. R. Evans	843,881
Wire grip, V. W. White	843,921
Wire painting machine, J. P. Famous	844,109
Wire stretcher, Hemenway & Thomson	843,603
Wire stretcher, O. C. A. Schwen	844,194
Wire stretcher, J. G. Dietrich	844,263
Wrench, D. J. McOsker	844,176
Yoke, cattle, G. J. Dean	843,586
Plate or dish, E. E. Walter	38,441
Plate or dish, E. Schnepf	38,442

DESIGNS.

Sign, illuminated chandelier, L. K. Liggett	38,444
Type, font of, A. Gottschling	38,443

TRADE MARKS.

Alloy of nickel, manganese, and copper, Isabellenhutte G. m. b. H.	60,525	60,526
Antiseptic solution, John Wyeth and Brother	60,628	60,628
Automobiles, Fairbanks, Morse & Co.	60,518	60,518
Beer, lager, Eastern Brewing Co.	60,543	60,543
Beer, root, B. C. Parker Co.	60,613	60,613
Boots and shoes, leather, Geo. N. La Monte Shoe Co.	60,477	60,477
Boots and shoes, leather, Menzies Shoe Co.	60,538	60,538
Boots and shoes, leather and cloth, Geo. F. Dittmann Boot & Shoe Co.	60,547	60,547
Boots, shoes, and slippers, leather, M. J. Meyer & Co.	60,459	60,459
Bread, cakes, biscuits, and crackers, Stewart Bread Co.	60,464	60,464
Brushes, artists', L. & C. Hardtmuth	60,532	60,532
Brushes, paint and varnish, S. H. French & Co.	60,522	60,522
Buggies and surreys, open and top, Blount Carriage & Body Co.	60,509	60,509
Candles, Will & Baumer Co.	60,500	60,500
Canned corn and succotash, H. L. Forhan	60,475	60,475
Canned fruits and vegetables, H. L. Forhan	60,476	60,476
Canned lobsters, H. L. Forhan	60,473	60,473
Canned, pickled, and preserved fish, John Conradsen A/S	60,631	60,632
Cards, playing, United States Playing Card Co.	60,618	60,618
Carpet sweepers, Bissell Carpet Sweeper Co.	60,505	60,508
Catalogues and pamphlets, J. C. Virden	60,466	60,466
Chemical substances, certain, Actien-Gesellschaft fur Anilin-Fabrikation	60,591	60,592
Chemicals, certain, Dr. O. Knoder & Co.	60,607	60,607
Chocolate, cocoa, and candy, Puritan Pure Food Co.	60,461	60,461
Chocolates and bonbons, F. H. Dow & Co.	60,454	60,454
Cigarettes, J. G. Saffa	60,567	60,567
Cigarettes and smoking tobacco, Calisto Lopez & Co.	60,510	60,510
Cigars, W. H. Barlow	60,503	60,503
Cigars, Cifuentes, Fernandez y Ca.	60,514	60,514
Cigars, H. E. Lockwood	60,537	60,537
Cigars, O'Connell & Gruss	60,561	60,561
Clam preparation, Rosenstein Brothers	60,491	60,491
Cleaning paste, Flash Chemical Co.	60,521	60,521
Clothes drying machines, Chicago Dryer Co.	60,512	60,512
Clothing, certain, Dayton Clothing Manufacturing Co.	60,542	60,542
Clothing, certain, Stork Co.	60,617	60,617
Coats, overcoats, vests, and trousers, Stein Bloch Co.	60,573	60,573
Coats, vests, pants, and overalls, duck, M. E. Smith & Co.	60,559	60,559
Coffee, Shackleton, Asplen & Co.	60,463	60,463
Coffee, Reilly, Taylor & Co.	60,490	60,490
Coffee and tea, C. R. Maltby Co.	60,448	60,448
Coffee in grain, J. Fernandez	60,520	60,520
Coffee, wheat, Potter & Wrightington	60,489	60,489
Corset covers and petticoats, Leumann, Boesch & Weingart	60,558	60,558
Cotton piece goods, Arnold, Karberg & Co.	60,502	60,502
Cutting and tools, certain, Simmons Hardware Co.	60,570	60,570
Dyes and chemical preparations for dyeing purposes, Actien-Gesellschaft fur Anilin-Fabrikation	60,587	60,587
Dyes, wool, Actien-Gesellschaft fur Anilin-Fabrikation	60,585	60,585
Dyestuffs, coal tar, Actien-Gesellschaft fur Anilin-Fabrikation	60,586	60,586
Electric fuses, Electric Device Co.	60,544	60,544
Electric sparking and igniting apparatus, Societe Generale des Huiles et Poudres Industrielles l'Oleo	60,571	60,571
Elixir of the digestive ferments, John Wyeth & Brother	60,630	60,630
Embroidery hoops, Gibbs Manufacturing Co.	60,552	60,552
Emulsion of mixed fats, John Wyeth & Brother	60,629	60,629
Erasers or erasing compositions, certain, A. Sommer	60,496	60,496
Exercising devices, elastic cord, Whitely Exerciser Co.	60,582	60,582
Extract of the pancreas gland, Fairchild Bros. & Foster	60,625	60,625
Fastening devices, certain, Penn Hardware Co.	60,610	60,610
Fertilizers, Scott Fertilizer Co. of Cicli County	60,495	60,495
Fibrous materials covered, etc., with a plastic compound, Celluloid Co.	60,449	60,449
Flavoring extracts, Greever-Lotspeich Manufacturing Co.	60,478	60,478
Flour, wheat, F. G. Stritzinger & Co.	60,465	60,465
Food for infants and invalids, prepared, Woolrich & Co.	60,501	60,501
Fumigants, Mass & Walstein Co.	60,609	60,609
Glue, Hall & Ruckel	60,604	60,604
Gun implements and certain equipments, Winchester Repeating Arms Co.	60,620	60,620
Hosiery, H. Frank & Sons	60,546	60,546
Insecticide, liquid, Cerrao Manufacturing Co.	60,590	60,590
Instep or arch support, William H. Wood	60,584	60,584
Insulation material, certain, Union Fibre Co.	60,578	60,578
Iron smoothing compound, A. Lewis	60,634	60,634
Journal, agricultural, L. Tucker & Son	60,497	60,497
Lace curtains, I. H. Hassall	60,554	60,554
Lamps, incandescent, Shelby Electric Co.	60,569	60,569
Laxative salts, compound, Buhler Laboratory Co.	60,623	60,623
Leather and leather soles, sole, Regal Shoe Co.	60,563	60,563
Leather dressing, Regal Shoe Co.	60,565	60,565
Lightning rods, St. Louis Lightning Rod Co.	60,575	60,575
Locks, night latches, and padlocks, cylinder, Russell & Erwin Manufacturing Co.	60,566	60,566
Lotion for scales and burns, E. W. Shryver	60,614	60,614
Machinery parts, certain, Latrobe Steel and Coupler Co.	60,536	60,536
Magazine, American Contractor Publishing Co.	60,468	60,468

SPECIAL 60-DAY OFFER TO INTRODUCE OUR LATEST LARGE, POWERFUL CHROMATIC TELESCOPE, WITH SOLAR EYE-PIECE

FACE TO FACE WITH THE SUN!

See the spots on the Sun.

3 1/2 FT. LONG ONLY \$1.00

NEEDED ON FARM, SEA OR RANCH.

POSITIVELY such a good telescope was never sold for this price before. These Telescopes are made by one of the largest manufacturers of Europe, measure closed 12 inches and open over 3 1/2 feet in 5 sections. They are BRASS BOUND, BRASS SAFETY CAP on each end to exclude dust, etc., with **POWERFUL LENSES**, scientifically ground and adjusted. **GUARANTEED BY THE MAKER.** Heretofore Telescopes of this size have been sold from \$5.00 to \$5.00. Every sojourner in the country or at seaside resorts should certainly secure one of these instruments; and no farmer should be without one. Objects miles away are brought to view with astonishing clearness. Sent by express for \$1 safely packed; if by mail, \$1.10. Our new catalogue of Watches, etc., sent with each order. This is a grand offer and you should not miss it. **WE WARRANT** each Telescope **JUST AS REPRESENTED** or money refunded. **WHAT A TOURIST SAYS:** New York, Nov. 4, 1905. Messrs. Kirtland Bros. & Co. GENTLEMEN: I had with me on my recent European trip, one of your Excelsior Solar Telescopes, with which I had the pleasure of observing an Eclipse of the Sun. At the Austrian Tyrol it was almost 80 per cent concealed. Your Solar eye-piece is a great thing. Its value to me on this occasion was many times greater than the entire outlay for the Telescope. Yours truly, L. S. HENRY. Send \$1.10 by Registered Letter, Post Office Money Order, Express Money Order, or Bank Draft payable to our order.

KIRTLAND BROS. & CO., Dept. S. A., 90 Chambers Street, New York

We equip our vehicles with bodies to suit your special requirements.

PRICE, - \$2000

The Rapid Idea

A car for every Commercial purpose

Hotel Bus, Sixteen-Passenger.

I want to tell you more about the most complete line of commercial motor vehicles made in the world. We have not been satisfied with one model, or even two or three, but have produced a line of cars that will meet every purpose in the commercial world—light and heavy delivery wagons, light and heavy trucks, hotel bus or baggage wagon, sight-seeing cars carrying from 12 to 35 passengers—every kind of car you could ask for. And where it is wanted, we design special bodies to suit the requirements of our customers.

Every car is propelled by the famous "Rapid" Motor—a strong, light engine that is simple in operation, reliable, and speedy. Every one is fully guaranteed for one year.

I want you to tell me what kind of delivery or passenger service you need, and I will write you about the car for your special purpose. Catalog free on request.

G. S. HENRY, Sales Manager, **Rapid Motor Vehicle Co., Pontiac, Mich.**

Every car guaranteed for one year.

PRICE, - \$1800

Twelve-Passenger Sight-Seeing Car.

THIS BOOK IS FREE

Would you like to succeed in business; to obtain a good paying position; to secure an increase in salary? Would you possess the capacity that directs and controls large business enterprises? If so, you should follow the example of hundreds of others who have prepared themselves for increase in salary through our assistance.

Our Free Book "How to Become an Expert Bookkeeper"

is the title of a treatise on Bookkeeping and Business. It tells of a system of accounts by which you can learn bookkeeping quickly at your own home without loss of time or money. We guarantee it. It is a book of intense interest to those who aspire to success. To advertise our School and to help the ambitious, we are giving this book away without any condition whatever. It is absolutely free. Send name and address and receive the book without cost.

COMMERCIAL CORRESPONDENCE SCHOOLS
 8906 Commercial Bldg., Rochester, N. Y.

The Metropolitan Magazine

The Aggressive Magazine for 1907

THE March Issue will contain the first chapters of The Great Historical Series relating to **THE MEXICAN WAR**. The articles will be full of Dramatic Human Interest. The Illustrations, many of them reproductions of old rare prints, are extraordinary both in conception and treatment.

SUBSCRIBE NOW and read the series from beginning to end.

MOTOR-BOATING: A good deal of space in the March Issue will also be devoted to the growth and development of the Motor-Boat Industry. The article, written by Mr. W. S. Dudley, will be of interest to all readers and especially so to the owner or prospective purchaser of one of these handy little craft. Some of the pictures to accompany the article are full of action and unique.

Subscription Price \$1.50 per Year. Single Copy 15 Cents.

THE METROPOLITAN MAGAZINE
 3 West 29th Street, New York City

BUILD A BOAT

BY THE WEATHERWAX METHOD

ARE you thinking of buying or building a Boat? We **Build Boats** of every kind from a 9 foot Row Boat to a 40 foot Power Launch or a 125 foot Steam Yacht. We are the **only Boat Builders who sell Boat Patterns**. Our complete, accurate, actual size **Boat Patterns**, with illustrated and simple, easy-to-follow instructions, will enable you to "**Build a Boat**" for yourself, or for any one else. We also furnish Knock Down Frames, ready to set up and easily put together, saving time and labor. Beside, we furnish Marine Hardware, Motor Engines from two (2) to any desired Horse Power, and everything that goes into the Building of Boats.

When you buy a Boat, or a Boat Pattern, from us you get a guarantee of satisfaction that carries the weight of a **large factory behind it**: this means a great deal to you, and the best is always the cheapest.

Write for our Free Catalog J, showing 57 New and Improved 1907 Models.

BAY CITY BOAT MFG. CO.
 Bay City, Mich., U. S. A.

References: Bradstreet's, Dun's, any Bank at Bay City, Mich.

2 H.P. Detroit Engine

For \$29.50

Starts without cranking; no cams, valves, springs or sprockets. Only 3 moving parts. All bearings bab-bit. For your Row Boat, Sail Boat, Launch. Send for testimonials. **SEND FOR FREE CATALOG.**

DETROIT ENGINE WORKS,
 1332 Jefferson Ave., Detroit, Mich.

Sparks That "Spark"

If you want your battery to furnish the kind of sparks that get all possible power out of your motor car or boat, install an

Apple Battery Charger

A dynamo right on your car that keeps the batteries always full and ready to furnish a strong, sure current. Write to-day for information.

The Dayton Electrical Mfg. Co., 98 St. Clair St., Dayton, Ohio

SPARK COILS

Their Construction Simply Explained

Scientific American Supplement 160 describes the making of a 1 1/4-inch spark coil and condenser.

Scientific American Supplement 1514 tells you how to make a coil for gas-engine ignition.

Scientific American Supplement 1522 explains fully the construction of a jump-spark coil and condenser for gas-engine ignition.

Scientific American Supplement 1124 describes the construction of a 6-inch spark coil.

Scientific American Supplement 1087 gives a full account of the making of an alternating current coil giving a 5-inch spark.


Scientific American Supplement 1527 describes a 4-inch spark coil and condenser.

Scientific American Supplement 1402 gives data for the construction of coils of a definite length of spark.

The above-mentioned set of seven papers will be supplied for 70 cents.

Any single copy will be mailed for 10 cts.

MUNN & COMPANY, Publishers
 361 Broadway New York



A Popular ELGIN

Every watch movement bearing the name ELGIN is the best movement of its kind made.

There are varying grades of ELGIN movements—the values of which are fixed by the number of jewels and the quality of materials used in construction.

The movement which meets the great demand for a popular-priced watch is the famous G. M. WHEELER movement, a name almost as great as ELGIN itself.

This movement can now be had in the popular sizes, for men's and boys' use, and in the models so much desired. Ask your dealer.

ELGIN NATIONAL WATCH CO.,
Elgin, Ill.


We Know You Can Build this Boat from Pioneer Patterns



LACK of skill with tools or lack of confidence in yourself matters nothing. We take all the risk of failure. We guarantee your success because Pioneer Patterns are so simple, perfect and practical we know you will be successful. We are so confident of this that we will give you 30 days—a full month's trial. If you are then dissatisfied—if Pioneer Patterns are not all we claim for them—simple, easy to follow, and thoroughly practical, just return them and get your money back without question or quibble. If you have not time or inclination to build from patterns, it is of course much easier to build on Pioneer Knock-Down frames which include perfect parts—fitted, tested, set up complete in our shops, then knocked down for shipment. You have merely to reassemble them. The hard part is done for you. Only common tools needed. Patterns and instructions for finishing absolutely free with frames. By building your own boat you save two-thirds the boatbuilder's price. Pioneer Knock-Down frames save nearly their entire cost in freight alone. Take advantage of this offer today, build your boat complete from Pioneer Patterns or knock-down frames, before spring, in your spare hours. Write today for free booklet, or send for the 22-page 9x12 book on boatbuilding. Prices, descriptions and 40 illustrations of 40 styles of boats you can build, and other practical information. Money back if not satisfied.

Pioneer Boat & Pattern Co., Wharf 52, Bay City, Mich.

Freeman's Auto-Boat Chair



Will give you extra seats in your boat without crowding anyone. The frame is made of crucible spring steel and enameled black. The seat and back-rest are upholstered in artificial, waterproof leather. Will stand 200 pounds under strain. Folds flat to store away when not in use. Size, seat, 17 in. high, 10 in. wide.

Sold by all Auto-Boat Supply Houses or by us direct

Description Booklet Free

RACINE METAL CHAIR CO.
411 Main Street RACINE, WIS.




Curtiss Airship Motors

7 H. P., 50 Pounds.

All extras ready to install. Now used by every successful aeronaut. Highest Award at Lewis & Clark Exposition. World's Record, Ormond Beach, Fla. Send for Catalog M.

Latest record, one mile in 46 2-5 seconds.

G. H. CURTISS MFG. CO., Hammondsport, N. Y.



Reversible Marine Engines

1 1/2 to 30 H.P.

Send for catalog. Valuable Features—Prices Low

Termaat & Monahan Co.
Oshkosh, Wis.

Magazine, A. Capper	60,470
Magazine, Porter, Taylor & Co.	60,488
Magazine, monthly, F. H. Chase	60,450
Magazine, monthly, L. Darbyshire	60,452
Malt preparation, Erste Wiener Export- Malzfabrik Hauser & Sobotka	60,472
Medicinal and toilet preparations, certain, Colgate & Co.	60,595
Medicinal remedy, M. J. Breitenbach	60,594
Medicine for certain named diseases, J. C. Hutchinson	60,605
Medicine for constipation, C. C. Langsdorf ..	60,608
Medicines, certain, Frederick Stearns & Co. .	60,598
Medicines, certain, Potter Drug and Chem- ical Corporation	60,611
Metal and wood working machines, certain parts of, Whitman & Barnes Manufac- turing Co.	60,583
Metal dressings, and polish, S. M. Mixby & Co.	60,462
Metal manufactures, certain, Taylor Iron and Steel Co.	60,576
Metal ware, certain solid and plated, Amer- ican Silver Co.	60,593
Milk, butter, and cheese, condensed, Nestle & Anglo-Swiss Condensed Milk Co.	60,486
Neckwear supporters, Blumenkrohn Crochet Button Works	60,541
Oats, H. O. (Hornby's Oatmeal) Co.	60,479
Oil, olive, H. Etienne Boule	60,456
Ointment, F. Henkelman	60,627
Paints and varnishes, Billings, King & Co. .	60,504
Paints, enamels, stains, and varnishes, Dol- phin White Lead and Color Works	60,453
Paper bags, Schorsch & Co.	60,492
Paper cutting machines and knives therefor, Child Acme Cutter and Press Co.	60,513
Pencils and point protectors, lead, American Lead Pencil Co.	60,469
Pens, penholders, and lead pencils, E. Faber Peptonized beef and bread, John Wyeth & Brother	60,457
Perfumery and cologne, Hall & Ruckel	60,606
Perfumery and toilet and bath washes, Smith Kline & French Co.	60,603
Perfumes, sachet, face, and talcum powders and toilet washes, Smith Kline & French Co.	60,616
Photographic developers, Actien-Gesellschaft fur Anilin-Fabrikation	60,615
Photographic plates and films, Actien-Gesell- schaft fur Anilin-Fabrikation	60,590
Pills, Potter Drug and Chemical Corporation. Plaster formed of wood fiber, Pittsburgh Plate Glass Co.	60,467
Pliers, Hammel, Riglander & Co.	60,562
Potash or lye, caustic, E. N. Hall	60,524
Powder, tooth, S. H. Gunder	60,601
Pretzels, cakes, crackers, biscuits, and bread, Oakdale Baking Co.	60,600
Radiator air valves and damper clips, L. J. Mueller Furnace Co.	60,460
Railway equipment, certain, Latrobe Steel and Coupler Co.	60,533
Remedies for the cure of the liquor habit, C. W. De Freest	60,535
Remedy for consumption, H. C. Fehrlin	60,624
Remedy for rheumatism, H. B. Wilson	60,626
Rope with a weatherproof finish, George Cut- ter Co.	60,619
Rosettes, General Electric Co.	60,548
Rubber belting, hose, and packing, Mercer Rubber Co.	60,523
Rubber boots and shoes, Hood Rubber Co. .	60,485
Rubber hose, belting, packing, and printing blankets, Mineralized Rubber Co.	60,481
Rum, John E. Cassidy & Son	60,487
Sad Irons, Enterprise Manufacturing Co. of Pennsylvania	60,557
Saddles and harness, La Grange Saddlery Co. .	60,517
Sausages, hams, bacon, salt pork, and lard, Jones Dairy Farm	60,534
Sewing machines, parts, and attachments, Wheeler & Wilson Manufacturing Co.	60,458
Shirts, negligee and workmen's Heynemann & Co.	60,581
Size for threads and yarns, Erste Wiener Ex- port-Malzfabrik Hauser & Sobotka	60,555
Soap, cotton seed oil, Union Oil Co.	60,596
Spices, mustards, and flavoring extracts, Mc- Cormick & Co.	60,579
Spices, pepper, and flavoring extracts, J. De Wees	60,560
Stoves and ranges, Southern Stove Works, Branch Continental Stove Co.	60,471
Stoves, heating, Novelty Manufacturing Co. .	60,572
Surgical dressing and appliances, certain, J. Ellwood Lee Co.	60,540
Syringes and atomizers, Mineralized Rubber Co.	60,527
Tea, Crescent Manufacturing Co.	60,539
Tea, M. & J. B. Kellauer & Co.	60,539
Toilet preparations, certain, J. M. Layat	60,451
Tonic, Ferrenzymo, Capsule Co.	60,483
Tonic beverage, S. Greenspon	60,597
Watches and parts thereof, Elgin National Watch Co.	60,553
Water, table, G. Truesdell	60,545
Wheat farina, pearl barley, and corn starch, E. R. Burke & Co.	60,577
Whisky, Charles Denney & Co.	60,455
Whisky, John E. Cassidy & Son	60,511
Whisky, Schuetz, Renzlehausen & Co.	60,556
Whisky, Stein Brothers	60,568
Whisky, Wolcott Co.	60,574
Wire rope, George Cutter Co.	60,621

LABELS.

"Curzon Complexion Cream," for complexion cream or paste, J. W. Hosler	13,358
"Do-Do Syrup," for a medicine, L. G. Denton ..	13,361
"Dr. J. O. Lambert's Anti-Consumptive Syrup," for a medicinal compound, Fayette & Agnew	13,362
"Gold King," for canned tomatoes, Zeigler Bros. Canning Co.	13,353
"Hop Bud," for beer, Klausmann Brewery Branch of the St. Louis Brewing Asso- ciation	13,350
"Lincks," for cigars, Schmitt & Co.	13,340
"Little Sweet Heart Pepsin Gum," for chew- ing gum, L. F. Jordan	13,351
"Men's Apparel," for men's apparel, W. C. Both	13,351
"Oysters," for canned oysters, A. Booth & Co.	13,364
"Pineapple," for a medicinal preparation, Lakewood Pine Co.	13,357
"Pure Food Brand Extra Fancy Cream Sugar Corn," for canned corn, T. Roberts & Co. .	13,363
"Pure Food Brand Garden Grown Sifted Pease," for canned peas, T. Roberts & Co.	13,356
"Pure Food Brand Tomatoes," for canned tomatoes, T. Roberts & Co.	13,355
"Scherman's Egg Shampoo," for a shampoo, J. Scherman & Co.	13,354
"Scherman's Liquid Shampoo," for a liquid shampoo, J. Scherman & Co.	13,359
"The Matchless Match," for matches, J. W. Henderson	13,360

PRINTS.

"Fashionable Coat Sleeves," for coat sleeves, Ed. V. Price & Co.	1,906
"Lapin's Magic Straw Hat Cleaner," for a straw hat cleaner, Essential Chemical Co. .	1,909
"The E. V. D. Way," for undershirts and drawers, Erlanger Bros.	1,905
"The House of a Thousand Tailors," for men's and boys' coats, vests, and trous- ers, Ed. V. Price & Co.	1,907

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.



The Car of Steady Service

The new utility car, Model 21, has been positively proven the most convenient, simple and serviceable car ever built.

The unit power plant in this car stands far beyond all others in compactness, accessibility and efficiency.

These are not mere generalities but positive points of superiority, and we stand ready to prove every claim by actual demonstration.


See our nearest representative or write for our catalog. It contains valuable information that you cannot afford to miss.

Main Office and Factory, Kenosha, Wisconsin.

Branches:

Boston, Chicago, Milwaukee, Philadelphia, San Francisco.

Thomas B. Jeffery & Company



Model 21, 20-22 H. P. \$1,350.


BOUND BOOKS AT SHEET PRICES

A FEW SETS of the New Americanized Encyclopaedia Britannica, slightly discolored by exposure in the store, must be disposed of before inventory

It would require an expert to discover that these books are not in every way perfect, and in most cases out of the entire set one or two volumes only show the slightest blemish.

Trivial as these imperfections are, we prefer to state candidly that the books are not quite perfect, and offset this by a liberal cut in the price. Rather than rebind the discolored volumes, we offer the set at the cost of the sheets.

This is positively your last opportunity of getting this great work of reference at bargain prices.



THE NEW AMERICANIZED ENCYCLOPAEDIA BRITANNICA

This elaborate work contains 15 volumes, 9x6 1/2 in. in size, 10,000 double column pages, 37,000 biographies, over 100 superb maps, and hundreds of priceless illustrations, many of them in color.

Answers every question, resolves every doubt, and settles every dispute. It is first in authority, first in wealth of information, but latest in date of publication. Its contributors include such immortals as Huxley, Darwin, Tyndall and Herbert Spencer. It is thoroughly up-to-date, and includes the very latest information on air-ships, wireless telegraphy, the Russo-Japanese War, etc.

The possession of the right Cyclopaedia puts you 10 years ahead of your less progressive neighbor.

Owing to a copyright injunction, this great Cyclopaedia will be permanently withdrawn from circulation in a short time. After that time the publisher will be legally restrained from selling the work at any price.

SENT FREE FOR EXAMINATION We are the only house that submits free for examination a complete set of its Encyclopaedia. We ask for no deposit. We pay the transportation charges, and allow ample time for a careful examination of the work, which you may return at our expense if it fails to satisfy you. All other houses offer a pamphlet, but a book agent brings it—and you cannot see their books unless you give an absolute order and pay something on account. We need not insist on the fairness of our method.

\$1.00 SECURES THE ENTIRE SET Fill up and send the accompanying coupon and we will send you PREPAID a complete 15 volume set of the New Americanized Encyclopaedia Britannica in half morocco binding. Examine it at your leisure and return it at our expense, if, for any reason, it fails to satisfy. Send no money with the coupon. The regular price is \$75.00 for the half morocco Encyclopaedia, sold through agents. We will close out these few 15 volume sets for \$39.00.

If you like the books you will have immediate possession thereof. You can then pay just one dollar and the balance a little each month.

SIEGEL COOPER CO., New York

NAME.....
ADDRESS.....

CUT OUT AND SEND THIS COUPON
Send on approval, prepaid, a complete set of the New Americanized Encyclopaedia Britannica in half morocco binding at the special price of \$39.00. If this is satisfactory I agree to pay thereon \$1.00 as Club Fee within 5 days after the receipt of goods and \$2.00 each month thereafter for 18 months. Title to remain in Siegel Cooper Co. till the full purchase price has been paid. If the books are not satisfactory I am to notify you, and hold them subject to your order.

FLOORS

ROOFS



A UNIQUE HANDBOOK

The contents of this book were prepared under the direction of acknowledged authorities on lathing and plastering, and represent the results of the best and most up-to-date practice. The comprehensive and practical manner in which these subjects are treated makes this a handbook which should find a place in the library of every architect, engineer, contractor, and builder.

"Clinton Wire Lath" is handsomely and substantially bound in boards and is illustrated with working drawings and photographs of types of construction and applications. It will be sent free on application to any of our offices.

The embossed medallion shows the Maine Memorial Chapel of the new U. S. Naval Academy at Annapolis, the plaster work in which was done on Clinton wire lath.

In sending for "Clinton Wire Lath," ask for the new Catalog of the Clinton Fireproofing System—the System with the Continuous Bond—of which Clinton Electrically Welded Fabric forms an integral part.

CLINTON WIRE CLOTH CO.
CLINTON, MASS.

Sweet's Index describes and illustrates the Clinton Fireproofing System—the System with the Continuous Bond—and its application. The border is a photographic reproduction of a section of Clinton Electrically Welded Fabric.

CEILINGS

FIREPROOFING DEPARTMENTS
ALBERT OLIVER
1 MADISON AVENUE
NEW YORK

Baltimore:
Washington:
Pittsburg:
Chicago:

George T. Welsh
Equitable Building
Rosslyn Supply Co.
Colorado Building
Houston Bros. Co.
Clinton Wire Cloth Co.
237 Lake Street

Columbus, O.:
St. Louis:
San Francisco:
Seattle:

Kyle & Dugan
282 E. Broad Street
Hunkins-Willis Lime and Cement Co.
South End 18th Street Bridge
L. A. Norris
835 Monadnock Building
L. A. Norris
909 Alaska Building

PARTI-
TIONS

In the Material and Construction of

Power-Driven Vessels

allowances must be carefully made for the strains that must bear on every part and section of the craft.

Pennsylvania Interlocking Rubber Tiling

is the only material that can be used for decks and flooring possessing sufficient resiliency to be absolutely unaffected by the severest and most constant wrenching. When, at last, the boat must be put out of commission this rubber tiling will be found to be as good as new.

Moreover, it is entirely non-slippery and of extremely elegant appearance and design.


Write for our Book-of-Designs-in-Color, with full description.



PENNSYLVANIA RUBBER COMPANY
Jeannette, Pa.

New York—1741 Broadway
Chicago—1241 Michigan Avenue
Philadelphia—615 N. Broad Street
Atlanta, Ga.—102 N. Prior Street

Boston—20 Park Square
Buffalo—717 Main Street
Detroit—237 Jefferson Avenue
Cleveland—2134-6 E. Ninth Street
London—26 City Road



The ... Remington Typewriter

has completed the thirty-third year of its history with a gain in business of

31%

Over the Year Before

Our enormous increases are derived from three sources: from the man who is buying his first Remington; from the man who is buying more Remingtons; and from the man who has tried other than Remingtons.

Remington Typewriter Co.
New York and Everywhere

ELECTRICAL ENGINEERING

Electrical Engineers are not looking for work. The work is looking for them—at wages which leave a margin for enjoyment and savings. Write to-day for our free 200-page book describing our courses in Electrical Engineering.

**CIVIL ENGINEERING**

To plan a great trunk line, or a vast park or lay out a city is a task of the highest order. The opportunity to master this profession lies with you. Write to us to-day for our free 200-page book describing this and many other courses.

CARPENTRY

There is many a doctor and lawyer not earning as much as a good carpenter. There is always demand for skilled workers. Master the trade and give yourself an independent position in the community. Send for our 200-page book describing 60 correspondence courses. Write to-day.

**COLLEGE PREPARATORY COURSE**

There is a simple, inexpensive way to prepare yourself for entrance to resident Engineering Schools without losing a moment of time from your present work. Write at once for our 200-page book describing this course.

MECHANICAL DRAWING

Is agreeable work and opens the way to great opportunities. It will pay you well, and you can master it at a little expense. Write at once and we will send you Free a 200-page book, describing 60 courses of instruction.

**STRUCTURAL ENGINEERING**

Tunnels, bridges, canals, subways (the age of subways is just beginning)—somebody will be engineering their construction 20 years from now. Why should it not be you? Write without delay for our 200-page book describing our courses. It is Free.

**MECHANICAL ENGINEERING**

The Motor Car Industry alone has opened a new and profitable field of employment for thousands of mechanical experts. We teach you by mail. Our 200-page book illustrating Courses in Mechanical Engineering is Free. Write to-day.

**American School of Correspondence**
CHICAGO

Mention Scientific American, 2-23-07

**TYPEWRITERS ALL MAKES**

All the Standard Machines SOLD or RENTED ANYWHERE, at 1/4 to 1/2 of the price. BEST REPAIRS APPLIED on price. Shipped with privilege of examination. Write for "Catalog" TYPEWRITER EMPORIUM, 202 LaSalle Street, CHICAGO

Before You Invest

A dollar in anything get my book "How to Judge Investments." It tells you all about everything you should know before making any kind of an investment, either for a large or small amount. This book gives the soundest advice and may save you many dollars. Send two-cent stamp for a copy, do it now.

Send your name and address and get the Investors' Review for

3 Months Free

This will keep you reliably posted on various kinds of investments. Address
Editor INVESTORS' REVIEW, 1382 Gaff Bldg., CHICAGO, ILL.

Electrocraft

The only Practical Magazine devoted to electrical construction. Describes wiring diagrams, modern systems and approved devices. Sample copy on request. ELECTRO-CRAFT, Detroit, Mich.

**DO YOU USE GRINDSTONES?**

If so we can supply you. All sizes mounted and unmounted, always kept in stock. Remember, we make a specialty of selecting stones for all special purposes. Send for catalogue "1".
The CLEVELAND STONE CO.
2d Floor, Wilshire, Cleveland, O.

60 YEARS' EXPERIENCE
PATENTSTRADE MARKS
DESIGNS
COPYRIGHTS & C.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. HANDBOOK on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the

Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all new dealers.
MUNN & Co. 361 Broadway, New York
Branch Office, 625 F St., Washington, D. C.

LOFTIS SYSTEM Diamonds on Credit

You Can Easily Own a Diamond or Watch. Pay 1-4 on delivery, balance 8 monthly payments. Descriptive catalogue free. Write today. Old Reliable, Original Diamond and Watch Credit House
Loftis Bros. & Co. Dept. B150, 92 State St., Chicago, Ill.

LET US BE YOUR FACTORY

WRITE FOR ESTIMATE ON ANY ARTICLE YOU WANT MANUFACTURED
STAMPINGS, MODELS, EXPR. WORK
WRITE FOR FREE BOOKLET
THE CLOBE MACHINE & STAMPING CO.
970 Hamilton St., Cleveland, O.

A MONEY MAKER

Hollow Concrete Building Blocks
Best, Fastest, Simplest, Cheapest
Machine. Fully guaranteed.
THE PETTYJOHN CO.
615 N. 6th Street, Terre Haute, Ind.

ICE MACHINES

Corliss Engines, Brewers
and Bottlers' Machinery. THE VILTER
MFG. CO. 899 Clinton St., Milwaukee, Wis.

MODELS & EXPERIMENTAL WORK.

Inventions developed. Special Machinery.
E. V. BAILLARD. 24 Frankfort Street, New York.

RUBBER

Expert Manufacturers
Fine Jobbing Work
PARKER, STEARNS & CO., 228-229 South Street, New York

MODELS & CHICAGO MODEL WORKS

ESTABLISHED 1867. 179 E. MADISON ST. CHICAGO, ILL.
WRITE FOR CATALOGUE OF MODEL SUPPLIES

MR. INVENTOR

Send us your models or drawings for our lowest prices.
We can develop, perfect or manufacture your invention.
MONARCH TOOL CO., 128 Opera Place, Cincinnati, O.

Dies, Tools, Models and Special Machinery.

MOORE & MOORE, CHICAGO, U. S. A.
OFFICE: 301 SOUTH AVENUE. WORKS: INDIANAPOLIS & FRANKLIN STREETS

Specialties & Patents Bought and Sold

American Commerce & Specialty Co., Inc., 95 Dearborn St., Chicago

GEO. M. MAYER, 1131 MONADNOCK, CHICAGO

WORKING DRAWINGS

DRYING MACHINES.

For Sand, Clays, Minerals, Wood Pulp,
Fertilizers, Chemicals, Ores, Ground Silica and Mica
and other Granulated Materials. S. E. WERRELL, HANNIBAL, MO.

NOVELTIES & PATENTED ARTICLES

MANUFACTURED BY CONTRACT. PUNCHING DIES, SPECIAL MACHINERY.
E. KONIGSLOW STAMPING & TOOL WORKS, CLEVELAND, O.

Experimental & Model Work

Dir. & advice free. Wm. Gardam & Son, 45-51 Rose St., N.Y.

THE SCHWERTLE STAMP CO.

STEEL STAMPS, LETTERS & FIGURES
BRIDGEPORT, CONN.

INVENTORS

We manufacture METAL SPECIALTIES of all kinds to order;
largest equipment, lowest prices. Send sample or FREE
model for low estimate and best expert advice.
THE EAGLE TOOL CO., Dept. A, Cincinnati, O.

MASON'S NEW PAT. WHIP HOISTS

save expense and liability incident to Elevators.
Adopted by principal storehouses in New York & Boston
Mand. by VOLNEY W. MASON & CO., Inc.
Providence, R. I., U. S. A.

Magical Apparatus.

Grand Book Catalogue. Over 700 engravings
25c. Parlor Tricks Catalogue, free.
MARTINKA & CO., Mfrs., 493 Sixth Ave., New York

NAME PLATES—STEEL STAMPS

EMPLOYEE CHECKS, KEY TAGS & BADGES.
J. ROBBINS MFG. CO. 58 KNEELAND ST.
SEND FOR CATALOGUE "BOSTON, MASS.

LEARN PLUMBING

A few months' instruction at our school
under the supervision of expert plumbers will enable
you to earn regular plumber's wages. We have a special
department to aid our students in securing a position
after graduation. Write to-day for FREE ILLUSTRATED
CATALOGUE. ST. LOUIS TRADE
SCHOOL, 3972 Olive Street, St. Louis, Mo.

VENTRILOQUISM

Learned by any Man or Boy at home. Small cost. Send
to-day 2-cent stamp for particulars and proof.
O. A. SMITH, Room 215, 2040 Knoxville Ave., Peoria, Ill.

LEARN WATCHMAKING

We teach it thoroughly in as many months as it
formerly took years. Does away with tedious apprenticeship.
Money earned while studying. Positions secured.
Easy terms. Send for catalog.
ST. LOUIS WATCHMAKING SCHOOL, St. Louis, Mo.

National ADJUSTABLE Window Ventilators.

Responsible agents wanted everywhere. New proposition
and unlimited field. Descriptive booklet and full
information mailed immediately on request. GET IT
EARLY. National Ventilator Co., Dept. 8,
149-151 S. Jefferson St., CHICAGO

Cushman MARINE MOTOR

is the most reliable, economical and
durable engine built.
Will use either Gasoline or Al
cohol. Skillfully designed and very
simple. Will always take you home
and win you many races.
For catalogue write
4 to 5 H. P. Wt. 125 Lbs. CUSHMAN MOTOR CO
See our exhibition,
Madison Square Garden. Lincoln, Neb.

HEADQUARTERS

for Bronze Inscription Tablets, Signs,
Bank Work, and Ornamental Brass
Work of all kinds. Designs furnished
ALBERT RUSSELL & SONS CO.
Woodland Bronze Works Dept. Newburyport, Mass.

A LITTLE STRONGER THAN NECESSARY**SOLAR Lamps and Generators**
MOTOR BOATS
AUTOMOBILES and BICYCLES

Solars are not only of simple, strong construction, but made of best material—heavy drawn brass. Their few parts add to their solidity. The way these parts are put together—riveted and screwed (never soldered)—further fortifies Solars against the hardest knocks and jars.

Their construction is not only durable, but scientific in EXACT FOCUS, utilizing ALL the light.


Each lamp thoroughly inspected before shipment.

Solars are the Strongest
Lamps made, and give
the Strongest Light.

Our 1907 catalogue describes our entire line—both
Lamps and Generators. It's free—want one?

BADGER BRASS MFG. CO., Kenosha, Wis.

Eastern Branch, 11th Ave. 36th & 37th Sts., New York City

**Mullins**

Makes Everything In

Art Architectural Sheet Metal Work

Statuary—Ornamental Sheet Metal Work—Skylights—Fireproof
Windows—Art Metal Tile Roofing—Steel Ceilings—Finials—
Wrought Iron Grilles—Cornices, etc., etc. Estimates, models and
designs submitted for architects, builders and contractors.

Our 120-Page Catalogue of stock designs will be sent on request.
The W. H. Mullins Co., 203 Franklin Street, Salem, Ohio.

Two Gifts In One

within the reach of all

**The Metropolitan Magazine**

is one of the most popular
magazines in America. It is
noted for its clean, whole-
some, snappy fiction, its
handsome illustrations and
its cheerfulness of purpose.
It has indeed been well termed
"The Magazine of
Cheerfulness," and its policy
is to uplift, to please and to
educate.

THE METROPOLITAN MAGAZINE

is taking front rank among
the leading popular maga-
zines of the country. No
magazine offers a better list
of contributors; none offers
more beautiful illustrations;
few, if any, offer articles of
such wide popular interest.
Look up any number on the
newsstand and judge for
yourself. The Magazine
may be sent to a different
address from your own if
you wish.

The annual subscription
price is \$1.50, or 15 cents
for a single copy.

The Tabard Inn Library

The lowest price
of a Tabard Inn Exchangeable
Book is \$1.18. A Brand New
Book of your own selection from
the accompanying list will be
mailed you prepaid in the combi-
nation herein offered. The books
are well bound in cloth and hand-
somely illustrated. Once you
own a Tabard Inn Exchangeable
Book it is your own property,
but you can exchange it for an-
other as often as you like on pay-
ment of a fee of five cents. There
are a million Tabard Inn Library
Books in circulation and two
thousand exchange stations all
over the United States and in some
cities in Canada.



A new cloth-bound book in
a Tabard Inn Bookcase.

A BRAND NEW BOOK (your own selection)
THE METROPOLITAN MAGAZINE—any address

Both for \$2.10

List of the Latest Books

- The Fighting Chance
Robert W. Chambers
- Chippings Borough
Stanley J. Weyman
- The Awakening of Helena Ritchie
Margaret Deland
- Prisoners
Mary Cholmondeley
- On Newfound River
Thomas Nelson Page
- Coniston
Winston Churchill
- Sir Nigel
A. Conan Doyle
- The Treasure of Heaven
Marie Correlli
- Panama (Isthmus and Canal)
C. H. Forbes Lindsay
- Puck of Pook's Hill
Rudyard Kipling
- The Tides of Barnegat
F. Hopkinson Smith
- The Bishop of Cottoncown
John Trotwood Moore
- The Lion and the Mouse
Chas. Klein and Arthur Hornblow
- The Incomplete Amorist
E. Nesbit
- Jane Cable
George Barr McCutcheon
- The Doctor
Ralph Connor
- Anthony Overman
Miriam Michelson
- Buchanan's Wife
Justus Miles Forman
- By the Light of the Soul
Mary E. Wilkins-Freeman
- White Fang
Jack London
- Rosemary in Search of a Father
C. N. & A. M. Williamson
- The White Plume
S. R. Crockett

Many of these books

are among
the most
popular of
the day.

FORM OF ORDER

THE TABARD INN LIBRARY
1611 Chestnut St., Philadelphia

DEAR SIR:—I enclose herewith \$2.10 for which
you will enter my name for THE METROPOLITAN
MAGAZINE for one year beginning with the...
number, and send me by mail prepaid a new copy of the
following Book... the Book to be
in a Tabard Inn Case and to be exchangeable forever
at any Tabard Inn Library in the United States.


Name.....

S. A. Full Address.....



WE MANUFACTURE MOULDED AND SPECIAL RUBBER GOODS OF EVERY DESCRIPTION AND CAN FURNISH ANY SPECIAL RUBBER ARTICLE TO YOUR SATISFACTION.

NEW YORK BELTING & PACKING CO. LTD.
91-93 CHAMBERS STREET, NEW YORK.



CHARTER
Stationaries, Portables, Hoisters, Pumps, Saws and Boat Outfits, Combined with Dynamos.
Gasoline, Gas, Kerosene.
Send for Catalogue.
State Power Needs.
CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

CRUDE ASBESTOS
DIRECT FROM MINES
PREPARED ASBESTOS FIBRE for Manufacturers use
R. H. MARTIN,
OFFICE, ST. PAUL BUILDING
220 B'way, New York.



BRISTOL'S Recording Instruments
For Pressure, Temperature and Electricity in all ranges
INSURE SAFE & ECONOMICAL OPERATION
Write for Catalog T, stating conditions
THE BRISTOL CO., Waterbury, Conn., U.S.A.
New York, 114 Liberty Street Chicago, 123 Monmouth Building

THE DIAGRAPH
(Trade Mark Registered)
The Improved Stencil Cutting Machine
Is a saving of 90 per cent in your Shipping Department worth considering?
Just a word will bring our free illustrated booklet describing the Diagraph and our "No Error" System of shipping goods.
American Diagraph Co.,
10 N. Second Street, St. Louis, U.S.A.



WM. H. BRISTOL Electric Pyrometers
Portable or Recording Forms.
All ranges to 2000° F. Practical, Accurate, Inexpensive. Guaranteed to give satisfaction. Send for circulars.
Wm. H. Bristol, 45 Vesey St., New York.



COMPLETE ELECTRIC LIGHT OUTFITS
For Yachts, Launches, Residences, Etc.
We are specialists and have all sizes of the finest outfits that money can buy, guaranteed fully. We contract to install anything electrical in any boat no matter how large or small.
Our standard outfits can be installed by anyone with the detailed directions furnished.
Incandescent and Arc Searchlights.
For catalogue and details address Electrical Department.
RICHARDSON ENGINEERING CO., Hartford, Conn.



THE "LEADER."
1 1/2 H. P. Gasoline Auto-Marine Engine
Built like a watch. Beautifully finished. Accurately constructed. Light, Strong, Reliable, and Noiseless in operation. Suitable for launches from 15 to 19 feet in length. Price complete, \$75 net, no discount. Thoroughly guaranteed. Perfect Speed Control. Complete descriptive Catalog upon application. Manufactured by
CLAUDE SINTZ,
292 S. Front St., Grand Rapids, Mich.

Electrical Engineering
and Experimental Work of Every Description
We have every facility for producing first-class work promptly. Our factory is equipped with modern machinery throughout.
C. F. SPLITDORF
Engineering Dept. 17-27 Vandewater St., N. Y. City

GIANT STEAM SHOVELS
Toledo, Ohio, U.S.A.
125 Vulcan Place
The Vulcan Iron Works Co.



Mullins Advice to Boat Buyers

Before you buy Any boat, built by Any manufacturer, selling at Any price, ask:
First—Is your hull guaranteed against puncture, and will you pay for repairs if it is punctured?
Second—Is your hull guaranteed against leaking, water-logging, and open seams?
Third—Is your hull equipped with air-tight compartments, and guaranteed as safe as a life-boat?
Fourth—Will you guarantee Absolutely the speed of your various boats, and will you take them back and refund the purchase price if they do not make the speed guaranteed?
Fifth—Is your engine guaranteed to be free from defects in workmanship and material, commercially accurate, perfect running, and will you, in case of my inability to run my engine, send a man to start it for me?

Mullins Pressed Steel Boats

Are Sold Under the Above Absolute Guarantee

They are built of smooth, pressed steel plates, with air chambers in each end like a life boat. The smooth, steel hull has handsome lines, and glides through the water with the least possible resistance—they are faster, more durable, and safer—they don't crack, leak, dry out or sink—are elegant in design and finish.

Write For Our Large Illustrated Catalogue of Motor Boats—Row Boats—Hunting and Fishing Boats.


The W. H. Mullins Company, 118 Franklin Street, Salem, Ohio.

The GRIFFIN Mill

The Greatest Pulverizing Machine in the World

Used Wherever Portland Cement is Made

OVER 50 PER CENT. OF THE PORTLAND CEMENT MANUFACTURED IN THE UNITED STATES TO-DAY IS GROUND IN THE GRIFFIN MILL.



The Griffin Mill pulverizes more cement than the combined output of all other machines used for this purpose.

Thoroughly tested by continually successful and constantly increasing use during the past sixteen years.

Portland Cement Clinker reduced from 1/2 inch to required fineness in one operation, with no auxiliary apparatus. No other machine made will do this.

Buy the GRIFFIN MILL and get the BEST. It holds the world record from every standpoint.

Send for Catalogue and full information.


Bradley Pulverizer Company, 92 State St., Boston

Bausch & Lomb Microscopes

are used in the leading laboratories everywhere. If they were not the best they would not be so universally used. If you are about to buy a microscope for any purpose, write first for a catalog of Bausch & Lomb Microscopes and Accessories.

Bausch & Lomb Optical Co.
ROCHESTER, N.Y.
NEW YORK BOSTON WASHINGTON CHICAGO SAN FRANCISCO.

Send First for the I.H.C. Catalogue



Before installing a gas and gasoline engine for any purpose, it will pay you to obtain and examine carefully the I. H. C. gasoline engine catalogue.

It tells and shows by means of many illustrations the excellent features of construction and operation which give I. H. C. engines their superiority. By reading this catalogue carefully you will place yourself in position to decide accurately what engine is best for you to buy.


I. H. C. gas and gasoline engines are made right to furnish abundant power with the least annoyance and at least cost. They are strong and simple, sturdy and dependable, powerful and durable. Send to-day for catalogue.

I. H. C. engines are built in the following style and sizes: Vertical, 2 and 3-H. P. Horizontal, 4, 6, 8, 10, 12, 15 and 20-H. P.

The International Harvester Company of America, Inc. 7 C Monroe Street, Chicago, Ill.

Scales
All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Saws, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. **CHICAGO SCALE CO., Chicago, Ill.**

This watch only \$21



In offering this fine high grade Hampton watch at \$21, we believe we are giving readers of the Scientific American the greatest watch value ever offered for the money. It is a gentleman's size, 2 1/2 inch diameter, perfectly adjusted to standard time, and is guaranteed to pass inspection on any railroad in the United States. Jewellers ask \$21 for this watch, but we will send it to you on receipt of \$21. We can also furnish the same watch in 17 jewel for \$12.85, the regular price of which is \$19 in jewelry stores. Either of these watches will be sent upon receipt of price with privilege of return, if not exactly as represented. Don't think a false proposition! We also want to call your attention to our handsomely illustrated catalogue of Watches, Diamonds, Cut Glass, Silverware, Embroidered Goods and Jewelry Novelties. Write for it today—It's FREE.
JOHN C. FIERIK & CO., 80 Fierik Bldg., Springfield, Ill.

STEAM USERS

Rainbow Packing

The original and only genuine red sheet packing.

The only effective and most economical flange packing in existence.

Can't blow Rainbow out.

For steam, air, hot or cold water, acid and ammonia joints.

Beware of imitations.

Look for the trade mark—the word Rainbow in a diamond in black, three rows of which extend the full length of each roll.

Manufactured exclusively by
PEERLESS RUBBER MFG. CO.
16 Warren St., New York

BALSAM SANITISSUE

A New Toilet Paper

Treated with aromatic Canada Balsam, which makes it the softest and strongest toilet paper made. Antiseptic, and comes wrapped in parchment in sealed cartons. Costs no more than common makes—10c, 15c, 25c.
Fifty Sheets Free, or \$1.00 worth sent, prepaid, anywhere in United States and Canada, on receipt of price.
SCOTT PAPER CO., 504 GLENWOOD AVE., PHILADELPHIA.

THE Nulite Vapor Lamps
For Home, Store and Street
We also manufacture Table Lamps, Wall Lamps, Chandeliers, Street Lamps, Etc. 100 Candle Power seven hours ONE CENT. No Wicks. No Smoke. No odor. Absolutely safe. THEY SELL AT SIGHT. Exclusive territory to good agents. Write for catalogue and prices.
Chicago Solar Light Co. Dept. G, Chicago

Merkel Motor Cycle

The only comfortable, non-injurious motor cycle on the market, built on the latest model, including the famous "Merkel" motor, Grip control, and Spring Frame and Fork, absolutely the safest and speediest roadster or racer yet made.

Write for Catalogue and Prices
MERKEL MOTOR CO.
1092, 26th Avenue, Milwaukee, Wis.

HEIMET OIL LUBRICATES ANYTHING
IF YOU HAVE A MOTOR, TRUCK, CYCLES, ETC.
15 to 21 South Clinton Street.

Holsten Spark Plug

The plug that will not short circuit which the manufacturer has guaranteed for five years.
Will replace any part that does not live up to their guarantee or money refunded if the trouble is their fault, as it is the only plug that is interchangeable. The battery and vibrator must be in good condition or the plug will not work for that is where the trouble is always found, battery exhausted, or vibrator out of adjustment or terminals loose. As the plug is really a little engine it needs some light oil at the movable parts the same as the engine you use when you let it stand any length of time. Send for particulars. In all sizes and threads.
TRIUMPH ENGINEERING CO.
Price \$2.50 each 226-228 Lafayette St., cor. Spring, New York City



DR. SIMON NEWCOMB,
(Department of Astronomy.)



PRESIDENT R. S. WOODWARD,
OF CARNEGIE INSTITUTION.



FREDERICK CONVERSE BEACH,
(Editor in Chief.)



GEORGE EDWIN RINES,
(Managing Editor.)




PRESIDENT ARTHUR T. HADLEY,
OF YALE.



PRESIDENT DAVID S. JORDAN,
OF LELAND STANFORD.



HON. JOSEPH H. CHOATE.



Copyright, 1903, by J. E. Purdy
PRESIDENT BENJ. IDE WHEELER,
OF CALIFORNIA.



PROF. CASSIUS J. KEYSER,
OF COLUMBIA.
(Department of Mathematics.)



ANDREW S. DRAPER,
NEW YORK STATE COMMISSIONER OF EDUCATION,
(Department of Education.)

16

VOLS.

? ? ? ? ? ? ? ? ? ? ? ?
? ?

? The NEW AMERICANA ?

? is the only reference publication which covers the entire realm of human knowledge and which brings this proven knowledge down to the exact present.
? THE AMERICANA is the Great Question Answerer of the age.
? Starting at the very beginning, every department of Science, of History, of Literature, of Religion—of the thousand and one subjects which interest
? and attract the human mind—all are included within its pages.

? WHO CAN ANSWER ?

? the countless questions of the inquiring mind of the child?
? Over 2,000 scholars and experts have, in THE AMERICANA, supplied the knowledge and information which enables parents to
? answer these questions accurately—information which can be found
? in no other reference publication.
? Knowledge has increased so rapidly during recent years that no mind,
? however well trained, can grasp and retain the exact facts concerning any
? simple subject.
? THE AMERICANA is the one publication that, covering the entire
? field of human knowledge, appeals equally to the child, the parent, the scholar, the man of business, the lawyer, the physician, the clergyman
? and the librarian.

?
? "TAKEN all in all we have no hesitation in saying that
? this great American production, in the extent and usefulness of its contents, in its technical arrangement, in its original
? conception and brilliant performance, is without a peer."
? —*Review of Reviews Magazine.*
?
? ? ? ? ? ? ? ? ? ? ? ?



EDWARD EVERETT HALE.



CARDINAL GIBBONS.



PROF. J. E. CREIGHTON,
OF CORNELL.
(Department of Philosophy.)



Copyright, 1902, by J. E. Purdy
THOMAS W. HIGGINSON.

FREE ON REQUEST

AMERICANA, or of its exceptional value and sumptuous appearance. Let us send you therefore a handsome 120-page book containing specimen pages, maps, full-page plates, duotones, color plates, and text illustrations, with portraits of celebrities, full-page photographic plates of the most interesting and up-to-date subjects—The Americana being the best illustrated of all reference works. With the object of making the AMERICANA quickly and widely known, before placing the work in the hands of dealers for general distribution, we will accept orders direct at a large reduction from the established price. Those interested are requested to make application immediately. The work is sold exclusively in connection with the **SCIENTIFIC AMERICAN** and cannot be otherwise obtained.

No mere advertisement can convey an adequate idea of the vast interest and immense utility of the

REQUEST BLANK SCIENTIFIC AMERICAN COMPILING DEPT. 258 FIFTH AVENUE, NEW YORK CITY

GENTLEMEN: Please send, without expense to me, your 120-page Book of Specimen Pages, Maps, Duo tones, Color Plates, Portraits, etc., of the NEW AMERICANA, with particulars regarding prices and your easy-payment plan.

Name.....
Occupation.....
Street.....
Town and State.....

CUT OUT AND MAIL TO-DAY

BUILD YOUR OWN BOAT

No Tool Experience Necessary—Costs but a Trifle.

You need only a set of Brooks Patterns—a little lumber, hardware, common household tools—and your spare time. 21,311 people built boats last year by the Brooks system. WHY NOT YOU?

The Brooks System consists of exact size patterns and fully illustrated instructions. The patterns are printed on heavy paper and there is a pattern for every piece of the boat.

The instructions and illustrations thoroughly cover every step of the construction. Each boat has its special instruction sheet. We tell you how to lay a certain pattern on a particular piece of material—how to mark and cut it out—how to fasten it into place with the right size nail, screw or bolt. We then show you an illustration of the work properly done.

We give you an itemized list of all the materials required—telling how the lumber should be dressed and purchased without waste.

A Business Opportunity

There is a big profit in boat building. Seventy-five per cent. of the selling price of boats is for design—labor and the boat factory's big profit. We furnish the design—you put up the boat and get the profit. We have established hundreds in the boat-building business. One man built twenty-seven boats from the one set of patterns last year. You can supply your customers with any kind of a boat they desire—racing—semi-speed or family launches—dories—tenders—tarpons—stern-paddle wheelers—sail-boats—larks—skip jacks—skiffs—row boats—duck boats and canoes.

SPEED. We can give you 28 miles per hour with 60 Horse Power engine—20 miles with 15 Horse Power—16 miles with 10 Horse Power—8 miles with 2 Horse Power—all proved over measured courses last year.

Why You Should Use the Brooks System


We are the Originators of the Pattern System of Boat Building. Our goods are Standard. We have continually improved and perfected our System. We have the largest factory of its kind in the world. (Covers 20 acres of ground and nearly 10 acres of floor space.) We own the standing timber—cut and manufacture it ourselves—do this where the timber grows. You pay no middleman's profit. We are the largest retailers of marine hardware and boat fittings in the United States. We buy in enormous quantities in the open market and at right prices. We sell right. We handle not only one part of a boat or frame, but every part and piece entering into the construction of a boat—framing—planking—decking—hardware and fittings—complete or in part as you desire. Our frames are all made by duplicating machinery—each part is perfect and accurately fitted. Every pattern is worked out scientifically and the result is both artistic and practical. Your boat is an assured success. Get our catalog for prices on all parts and materials. Our No. 5—16-foot launch, frame with patterns to finish, \$15.00. Our No. 15—22-foot speed launch, frame with patterns to finish, \$20.00. These are regular prices listed in our catalog—other frames in proportion. Patterns are absolutely free with all knock-down frames. We sell for less than it costs others to manufacture. We offer the largest and most complete line of boats of all kinds—for all purposes.

Special freight rates and quick dispatch on foreign shipments. We prepay carriage charges on patterns to any part of the world.

REDUCED PRICES. Patterns of all row boats and canoes \$1.50 to \$2.00. Launches and sail boats under 21 feet \$4.00 to \$5.00. From 21 to 30 feet \$5.00 to \$10.00. Satisfaction guaranteed or money refunded.

Don't fail to get our big FREE Catalog.

It fully illustrates our big line of boats. Contains a number of testimonials from amateur builders and photographs of the boats they have built.



BROOKS SYSTEM

BROOKS BOAT MFG. CO.

ORIGINATORS OF THE PATTERN SYSTEM OF BOAT BUILDING.

422 SHIP ST. SAGINAW, MICH. U.S.A.

(FORMERLY OF BAY CITY, MICH.)